

HOLMES



SAND80-8228  
Unlimited Release

# A Plan for the Commercialization of Solar Thermal Central Receiver Systems

M. J. Fish, L. D. Brandt

Prepared by Sandia National Laboratories, Albuquerque, New Mexico 87185 and Livermore, California 94550 for the United States Department of Energy under Contract DE-AC04-76DP00789.

Printed November 1980



Issued by Sandia National Laboratories, operated for the United States  
Department of Energy by Sandia Corporation.

---

#### **NOTICE**

This report was prepared as an account of work sponsored by the United States Government. Neither the United States nor the United States Department of Energy, nor any of their employees, makes any warranty, express or implied, or assumes any legal liability to responsibility for the accuracy, completeness or usefulness of any information, apparatus, product or process disclosed, or represents that its use would not infringe privately owned rights.

Printed in the United States of America  
Available from  
National Technical Information Service  
U. S. Department of Commerce  
5285 Port Royal Road  
Springfield, VA 22161  
Price: Printed Copy \$5.25; Microfiche \$3.00

SAND80-8228  
Unlimited Release  
Printed November 1980

A PLAN FOR THE COMMERCIALIZATION OF SOLAR  
THERMAL CENTRAL RECEIVER SYSTEMS

Miriam J. Fish  
Larry D. Brandt  
Energy Systems Studies Division  
Sandia National Laboratories, Livermore

ABSTRACT

Concepts for solar thermal central receiver plants have evolved through continuing research and development into designs that are projected to have higher efficiency and lower cost. Recent studies have combined these results with rising costs of fossil fired plants and fuels to show that solar central receiver plants can be a competitive alternative for large scale electrical production. Because of these findings, commercialization of the concept is now receiving increased attention by both government and private groups involved with development of the technology. This report recommends the elements of a government program to achieve successful commercialization by the early 1990's. The recommendations integrate utility requirements for demonstration and risk sharing with supplier needs for manufacturing process development. Program timing and costs are presented, and the effects of program modifications are briefly discussed.

## CONTENTS

|   | <u>Page</u> |
|---|-------------|
| Introduction  | 9           |
| Approach  | 12          |
| Summary   | 15          |
| Program Elements for Central Receiver Commercialization | 17          |
| Phase 1: Research and Development                       | 17          |
| Phase 2: Demonstration                                  | 17          |
| Barstow   | 17          |
| Additional Demonstration                                | 17          |
| Intermediate Level Heliostat Production                 | 21          |
| Information Dissemination                               | 21          |
| Phase 3: Commercial Development                         | 21          |
| Initial Heliostat Mass Production                       | 22          |
| Balance of Plant Designs                                | 22          |
| Federal Government Incentive Program                    | 22          |
| Utility Commission Policy Revision                      | 23          |
| Phase 4: Commercialized Technology                      | 24          |
| Timing of Program Elements                              | 24          |
| Roles of Participants                                   | 26          |
| Costs for Commercialization                             | 30          |
| Modifications to the Plan                               | 37          |
| Conclusions   | 38          |
| REFERENCES  | 39          |
| APPENDIX--PROGRAM COSTS BASED ON OIL DISPLACEMENT       | 40          |

## ILLUSTRATIONS

| <u>No.</u> |  | <u>Page</u> |
|------------|--|-------------|
| 1.         | Energy Cost Comparison Between Solar Central Receiver and Coal Plants          | 10          |
| 2.         | Highlights of the Commercialization Plan                                       | 16          |
| 3.         | Program Timing   | 25          |
| 4.         | Schematic of Solar Plant Cost Variation with Time                              | 33          |
| 5.         | Equivalent Costs of Solar Central Receiver and Coal Plants                     | 34          |
| A-1        | Equivalent Costs of Solar Central Receiver Plants and Fuel Value in Oil Plants | 41          |

## TABLES

| <u>No.</u> |  | <u>Page</u> |
|------------|--|-------------|
| I.         | Evolution of New Energy Technologies                         | 11          |
| II.        | Summary of Utility Views                                     | 13          |
| III.       | Summary of Heliostat Supplier Views                          | 14          |
| IV.        | Evolution of Solar Central Receivers                         | 18          |
| V.         | Major Elements for Commercialization                         | 19          |
| VI.        | Government, User, Supplier Roles in Commercialization        | 27          |
| VII.       | Actions of Government, Users, Suppliers in Commercialization | 28          |
| VIII.      | Near Term DOE Activities                                     | 29          |
| IX.        | Coal Plant and Fuel Cost/Performance Assumptions             | 30          |
| X.         | Solar Plant Cost/Performance Assumptions                     | 31          |

TABLES (con't)

| <u>No.</u> |  | <u>Page</u> |
|------------|--|-------------|
| XI.        | Economic Assumptions                                     | 32          |
| XII.       | Total Program Costs to the Government, Coal Displacement | 35          |
| XIII.      | Required Budget Authority                                | 36          |
| A-I.       | Total Program Costs to the Government, Oil Displacement  | 42          |

## A PLAN FOR THE COMMERCIALIZATION OF SOLAR THERMAL CENTRAL RECEIVER SYSTEMS

### Introduction

Commercialization of the solar thermal central receiver concept is receiving increased interest as a result of several recent studies assessing its potential (1-4). These studies indicate that: 1) solar central receiver plants using mass produced heliostats can compete with conventional coal fired plants for large scale electrical production over a wide range of fuel cost projections, as shown in the example result of Figure 1; and 2) the solar central receiver concept is often the preferred choice among solar technologies for a large number of thermal and electrical applications and plant sizes. Based on these findings, the Division of Solar Thermal Energy Systems and the San Francisco Operations Office of the Department of Energy have requested that Sandia National Laboratories, as technical manager for this program, recommend a plan identifying an appropriate government role to accelerate, if possible, the commercialization of solar central receivers for large scale energy production. This report presents those recommendations.

A useful way to view the thrust of a commercialization study for any new energy technology is through the simple overview of technology evolution presented in Table I. The phases of Table I are typical of the progression of a new technology from initial conception to the time it stands on its own in the commercial marketplace. Activities in one phase may significantly overlap activities in another phase(s), but the framework of Table I provides the starting point for understanding the role of any given program element and its interaction with other parts of the overall plan. Phase 1 centers on research and development in which the choices for implementing the technology are narrowed and pursued. Phase 1 results lead into a demonstration period (Phase 2) in which most of the uncertainties in the working of the integrated system in real operating environments are resolved. While technical acceptance should be accomplished in Phase 2, economic viability will probably not be achieved due to the lack of established stable design procedures and large scale manufacturing facilities. Phase 3 activities must attack the economic hurdles in order to insure that both private user and supply sectors are established. Finally, the technology is ready to move into Phase 4 in which it can compete on its own for large scale energy production. In the context of Table I this report presents a plan for getting to Phase 4 from current R&D activities. In particular, major government programs, their timing, and estimated costs in Phases 2 and 3 are identified.




FIGURE 1. Energy Cost Comparison Between Solar Central Receiver and Coal Plants (cost and economic assumptions in Tables IX, X, XI in main text).



TABLE I

EVOLUTION OF NEW ENERGY TECHNOLOGIES

|         | Phase 1<br>Research and<br>Development   | Phase 2<br>Demonstration   | Phase 3<br>Commercial<br>Development  | Phase 4<br>Commercialized<br>Technology   |
|---------|--|--|---|---|
| Purpose | <ul style="list-style-type: none"> <li>• Conceive and screen new ideas</li> <li>• Develop data base</li> </ul> | <ul style="list-style-type: none"> <li>• Resolve system technical uncertainties</li> </ul> | <ul style="list-style-type: none"> <li>• Establish private supply and market sectors</li> </ul> | <ul style="list-style-type: none"> <li>• Implement large scale energy production through user initiated projects</li> </ul> |

## Approach

The two major but interconnected elements for successful commercialization are market acceptance and an established supply sector. Therefore, potential users and suppliers have been involved in formulating the plan recommended here. The particular programs discussed are aimed at integrating the needs of both sides in a compatible manner. Since the best characterized market for the technology to date is the electric utilities, and the major requirement on the supply side is achieving heliostat mass production, the authors have concentrated on identifying the major decision criteria of the utilities and potential heliostat manufacturers for committing to the central receiver concept. With respect to the balance of plant, it was felt that tower construction and steam turbine/generator systems were already well established technologies, and that receiver and storage systems would benefit most from continuing research and development activities rather than production economies of scale. Hence, the attention has been devoted to understanding how heliostat costs can be expected to change with time as a result of production process development.

The primary vehicle for identifying user and supplier requirements has been a series of meetings and follow-on exchanges with a number of southwestern U. S. utilities, both in and out of the current DOE program, and with several potential heliostat manufacturers currently involved in the program. The meetings were focused through a set of questions addressing concerns appropriate to the individual group with whom we were interacting. Although the number of potential users and suppliers interviewed was limited, it was felt that the major considerations for both were identified. The basis for this conclusion is that the views of the groups interviewed later in the process had already been expressed in earlier meetings with other groups. While this result might have been anticipated for the suppliers, it was also the case for the diverse group of users contacted. The utilities interviewed spanned a spectrum from innovative to very conservative with respect to their ability and/or desire to participate in the introduction of new technologies, and their levels of knowledge of the central receiver program varied widely. In spite of these differences, a consistent set of program recommendations evolved. The findings from these meetings are detailed in other reports (5,6); summaries are presented in Tables II and III.

The commercialization program elements discussed in this report result from the integration of user and supplier recommendations at a minimum level of government commitment to assure a high probability of success in a 10-15 year time frame.

TABLE II  
SUMMARY OF UTILITY VIEWS

---

\*On adopting central receivers for significant energy displacement

- Early plants would be designed for evaluating technology alternatives while minimizing system complexity
  - Receiver technology choice varies (no clear consensus for water/steam, salt, sodium)
  - Peaking applications (little or no storage)
- Later plants approach optimum solar application and technology
  - Higher capacity factors (intermediate to base load designs)
  - Most cost effective receiver technologies, as identified in early plants

\*On the extent of demonstration (Phase 2, Table I)

- Barstow is necessary as the first technical integration step and as a clear sign of federal commitment to large scale technology development
- Larger demonstration(s) at 50 MW<sub>e</sub> minimum are required
  - Minimum size for grid interaction
  - Intermediate size for scaling to full commercial
- Preferences vary for receiver/storage technology (salt, sodium, water/steam)
- 2-5 years reliable operation on a utility grid must be demonstrated

\*On the government role in commercial development (Phase 3, Table I)

- Incentives are the desirable approach to overcome noncompetitive cost portion of first commercial plants
- Incentive policies must be in place early and approved for a substantial period of time (through early 90's minimum) to avoid unnecessary lags between demonstration and user commitment

\*On the role of the state regulatory commissions

- New approaches for high risk capital intensive technologies are required
-

TABLE III

SUMMARY OF HELIOSTAT SUPPLIER VIEWS

---

- \* Competition is essential
    - Multiple supplier capability maintained beyond R&D
  - \* Desirable path of each supplier to mass production proceeds through three steps
    - Design and prototype construction
      - 1-10 units
    - Continuous intermediate scale production
      - 2000 - 5000 units/yr
      - ~3 years
      - Some investment in tooling
    - Initial mass production
      - 15,000 - 30,000 units/yr
      - 5 years minimum
      - Dedicated manufacturing lines
-

## Summary

The highlights of this commercialization plan are presented in Figure 2. The important points to be made about Figure 2 are summarized below. Detailed discussions can be found in the sections following.

1. Additional demonstration beyond Barstow to meet user requirements will also provide a market for heliostats produced at intermediate production levels (see Table III). This opportunity to satisfy critical user and supplier needs simultaneously is a cornerstone to achieving commercialization.
2. It is recommended that the noncompetitive cost fraction in the first commercial plants be overcome with properly structured federal incentives (e.g., added tax credits, accelerated depreciation allowances, financing of manufacturing facilities, etc.). Moreover, these policies need to be adopted by 1983 in order to minimize lags between demonstration and construction of the early commercial plants.
3. Utility commission policy revisions are an important complement to federal actions for implementing this technology. Suggested actions, such as capital recovery guarantees for the first plants, or combined stock holder and customer sharing of savings resulting from federal incentives, are discussed in the text.
4. The total costs to the government for the program presented here are estimated to be approximately \$1.2 - \$2.2 billion, depending on the cost of alternatives. This total includes approximately \$340 million for program operating expenses, primarily for continuing research and development activities, \$460 - \$610 million for demonstration beyond Barstow, and \$380 - \$1200 million in incentives. These costs are spread over the 12 year period between now and 1992.




FIGURE 2. Highlights of the Commercialization Plan.

## Program Elements for Central Receiver Commercialization

Retaining the structure of Table I, the goals of each phase in an evolving energy technology can be stated more specifically for solar central receivers as shown in Table IV. These goals are translated into recommended program elements in Table V. While these programs are far from the only choices, they do represent a minimum effort for successful commercialization based on both user and supplier requirements and preferences. The considerations behind the choices are discussed below.

### Phase 1: Research and Development

The emphasis of the DOE program to date has been research and development (R&D). A number of conceptual and preliminary designs for the various subsystems are documented (see reference 7 for a review and bibliography). Both scale and full size hardware has been tested. Moreover, design iterations and component testing are ongoing and will continue as more experimental data and analytical capabilities become available. As a part of commercialization, continuing R&D efforts are essential to the evaluation of new technical options and applications as they arise. While the details of R&D integration with other activities are not the main concern of this study, routine and widespread dissemination of R&D results is very important for generating and maintaining interest in technology development.

### Phase 2: Demonstration

As indicated in Table IV, the demonstration phase is aimed at both users and suppliers. The recommended program elements are designed to address a critical hurdle facing each side: adequate system demonstration for the users and continuous intermediate level heliostat production for about three years for the suppliers. With proper program planning, both barriers can be overcome simultaneously as discussed below.

Barstow--The 10 MW<sub>e</sub> plant under construction near Barstow is a necessary first step to get the technology on a commercialization path. As the first operating integrated system, Barstow is expected by most utilities to have a number of start-up problems (5). After these are worked out, however, potential users will want to see the plant demonstrate 2-5 years of operating reliability comparable to more conventional options. This will qualify the project as a useful experiment from which estimates on operating and maintenance requirements can be made. This kind of information is important not only for economic assessments of the technology, but also as input to the next designs planned for construction. In addition, timely completion of the Barstow project is required as a clear sign to both users and suppliers of the government's commitment to develop solar as a viable option for large scale energy production.

100 MW<sub>e</sub> Additional Demonstration--While Barstow is the required first step, it alone is not sufficient for attracting widespread utility interest. This is due primarily to the small size and experimental nature of the Barstow project and to a lesser extent, to the receiver/storage design for which more cost effective choices are now known. The demonstration projects in this part

TABLE IV  
EVOLUTION OF SOLAR CENTRAL RECEIVERS

|         | Phase 1<br>Research and<br>Development   | Phase 2<br>Demonstration   | Phase 3<br>Commercial<br>Development   | Phase 4<br>Commercialized<br>Technology  |
|---------|--|--|--|--|
| Purpose | <ul style="list-style-type: none"> <li>• Conceive and screen new ideas</li> <li>• Develop technology base</li> </ul> | <ul style="list-style-type: none"> <li>• Establish user confidence and support through adequate system demonstration</li> <li>• Provide small market for heliostats</li> </ul> | <ul style="list-style-type: none"> <li>• Provide economic incentives to build first commercial plants</li> <li>• Provide market for initial mass production of heliostats</li> </ul> | <ul style="list-style-type: none"> <li>• Build full size commercial plants using established designs</li> <li>• Large scale mass production</li> </ul> |



TABLE V

## MAJOR ELEMENTS FOR COMMERCIALIZATION

| Phase 1<br>Research and<br>Development   | Phase 2<br>Demonstration  | Phase 3<br>Commercial<br>Development  | Phase 4<br>Commercialized<br>Technology  |
|--|---|---|--|
| <ul style="list-style-type: none"> <li>• Conceptual and preliminary designs</li> <li>• Component and subsystem testing               <ul style="list-style-type: none"> <li>-Heliostat prototype evaluation</li> <li>-Central Receiver Test Facility experiments</li> <li>-Storage, steam generator subsystem research experiments</li> </ul> </li> <li>Applied research               <ul style="list-style-type: none"> <li>-Materials development</li> </ul> </li> <li>• Information dissemination</li> </ul> | <ul style="list-style-type: none"> <li>• Barstow</li> <li>• Additional demonstration totaling 100 MWe equivalent<sup>1</sup> <ul style="list-style-type: none"> <li>- 50 MWe plants</li> <li>- Salt, sodium, improved water/steam</li> </ul> </li> <li>• Intermediate level heliostat production<sup>1</sup> <ul style="list-style-type: none"> <li>-2K-5K units/yr</li> <li>- ~3 yrs minimum</li> <li>-2 suppliers minimum</li> </ul> </li> <li>• Information dissemination</li> </ul> | <ul style="list-style-type: none"> <li>• Initial heliostat mass production               <ul style="list-style-type: none"> <li>-15K-30K units/yr</li> <li>-5 yrs stable production</li> </ul> </li> <li>• Balance of plant designs               <ul style="list-style-type: none"> <li>-1st plant design and engineering</li> </ul> </li> <li>• Federal government incentive program               <ul style="list-style-type: none"> <li>- Timing critical</li> </ul> </li> <li>• Utility commission policy revisions</li> </ul> | <ul style="list-style-type: none"> <li>• No special programs or provisions for solar central receivers</li> <li>• Product improvement</li> </ul> |

<sup>1</sup>Can be satisfied with repowering program.

of the program are recommended as a move from experimentation at Barstow to technical demonstrations addressing two important commercial aspects of plant size and economic potential.

The recommendations for these follow-on projects are based on strong utility opinions (5). The groups interviewed generally agreed that demonstrations at 50 MW<sub>e</sub> operated by utilities in their existing grid for 2-5 years would be the minimum acceptable effort to capture their serious attention. This size satisfies minimal requirements for grid interaction so that backup capacity requirements for solar plants can be characterized. In addition, component scaling limitations dictate an intermediate step at about this size in progressing from pilot plants such as Barstow to full commercial modules lying between 150 and 400 MW<sub>e</sub>. Both of these points are important in the approach to commercial readiness.

Besides moving toward attractive commercial sizes, these demonstrations can utilize designs with improved economic potential and user acceptability. In the time since the Barstow design was selected, designs for heliostats and receiver/storage technologies of greater potential cost effectiveness have evolved (7). Heliostats currently under development have larger reflective areas and lighter weights per unit area, both of which lead to lower costs on a \$/m<sup>2</sup> basis. Receiver/storage designs with better cost and performance over the Barstow choice include improved water/steam, molten salt, and liquid sodium technologies. Based on their experience with conventional power generation to date, many utilities are leaning toward water/steam receivers as their early commercial choice. For a number of other utilities, however, the preference is with either salt or sodium because of the higher potential cost effectiveness of these technologies and the ease with which modern steam conditions, including reheat, can be produced. The choice of any of these technologies for demonstration at 50 MW<sub>e</sub> might require an intermediate component development or pilot plant step between testing at the Central Receiver Test Facility and the 50 MW<sub>e</sub> design if there are any serious material or equipment uncertainties in scaling. (An important function of the continuing R&D program is to evaluate the necessity of such activities.) Although this would be a conservative approach which might extend the time scale of the program, its lower risk may be justified for orderly commercialization (8).

The above considerations lead to the recommendation that total demonstration should be about 100 MW<sub>e</sub>. At this level, two plants of 50 MW<sub>e</sub> each could be built. These would satisfy minimum demonstration size requirements and allow the implementation of more than one receiver/storage technology. Given the diversity of preferences for receiver/storage designs and lack of test results and operating experience, multiple demonstrations are very important in order to attract a larger number of users to commit to the first commercial plants. While a number of the utilities view the early commercial plants in peaking applications (5), studies indicate that central receiver plant economics are enhanced at higher capacity factors, i.e., with the addition of several hours of storage. Hence, at least one of the demonstrations should include adequate storage to address the technical issues of operation from storage and to provide more data on solar plant capacity credit to the utility grid. This proposed level of demonstration will require ~10,000-15,000 heliostats. It is worth noting here that the draft repowering plan proposed by DOE/SAN in January, 1980, (9) would satisfy these demonstration needs.

Intermediate Level Heliostat Production--Potential heliostat suppliers interviewed in the course of this study agreed on the necessity of a stage of intermediate production at a level of 2000-5000 units/year for about three years (6). This transition step from prototype construction to mass production serves several vital functions. The heliostat design evolves to a mass producible version, and effective mass production processes are developed. Both these events can occur because investment in production tooling is at a small enough level to allow modifications. Moreover, the three year period makes field experience from the first units produced in this mode available for any necessary design modifications in later units. All these factors increase the certainty that an acceptable product can be consistently manufactured when the commitment to mass production facilities is finally made.

Only with strong assurance of a large potential market, however, will suppliers be willing to enter into this intermediate development stage on their own, and the market will evolve only with adequate demonstration as discussed above. By electing to demonstrate the technology to meet user requirements, the government can provide the market for intermediate level heliostat production, and moreover, the recommended scale of demonstration (10,000-15,000 heliostats) is large enough to support a minimum of two competitive suppliers. Maintaining competition during this early stage of production is important to promote cost reductions.

While these actions will not unconditionally guarantee the birth of a market and large supply industry, they will demonstrate the technology in a significant commercial market and provide the base for production of moderate cost heliostats. This opportunity to overcome simultaneously two major hurdles facing the technology, namely adequate demonstration for the users compatible with production levels to stimulate suppliers, is one of the key aspects of this plan for accelerating commercialization.

Information Dissemination--A dedicated effort to keep all parties, particularly the potential customers, informed of the progress of the program will become increasingly important in accelerating user decisions to commit to the technology. Mechanisms for routinely conveying important program findings in R&D and data from demonstration projects need to be developed by DOE. These activities might include widespread distribution of concise written summaries to users, suppliers, and state and federal government officials. In addition, individuals charged with marketing responsibilities in the program would be very effective for making personal contacts with a larger group of potential users unfamiliar with the status of the technology.

### Phase 3: Commercial Development

Phase 2 activities bring central receiver systems to the point of technical readiness and offer the first step to economic viability by demonstrating receiver/storage systems of high potential cost effectiveness and by providing a market for heliostats produced in the intermediate manufacturing stage. Program activities in Phase 3 are aimed at completing the move to full economic competitiveness. Noncompetitive plant costs existing at the beginning of Phase 3 will be due to the small scale of mass production expected and the added expense in design and engineering of the first commercial plants. These conditions are expected to disappear by the end of Phase 3 resulting in competitive costs for central receiver systems.

Initial Heliostat Mass Production--Based on the continued involvement of two or more suppliers through intermediate heliostat production in Phase 2, it is anticipated that at least two suppliers will then be ready to move into mass production at a level of 15,000 - 30,000 units/year. Both scaling limitations from intermediate production levels (note similarity to utility practice) and uncertainties in the initial market size suggest this range as a maximum. The market uncertainties present at the beginning of Phase 3 will also cause suppliers to reduce their capital investment by purchasing readily available parts from outside manufacturers and to recover investment costs fairly rapidly, on the order of 3-5 years. These factors suggest that the Phase 3 heliostats will cost about \$150/m<sup>2</sup> (6). This is significantly higher than the competitive range of \$75-\$100/m<sup>2</sup> estimated for mature mass production facilities, in which few parts are purchased and the capital recovery period is 8-10 years (10,11). Supplier commitment to this manufacturing strategy and to higher production volumes will occur as the market grows and more suppliers are attracted into the competition for a market share.

Balance of Plant Designs--The tower and turbine/generator subsystems of the central receiver plant are established technologies whose costs, in constant dollars, should remain at their current levels. However, the receiver and storage subsystems in the plants built in Phase 3 are expected to cost 50 - 100% above the estimates for stable "nth" plant designs. One contributing factor is the added design and engineering required to adapt the demonstrated technologies to the wide range of operating environments and specifications for commercial plants. As a result of this design evolution, suppliers of these components will find themselves in a corresponding evolutionary process of production development similar in nature to the intermediate heliostat production stage of Phase 2. Thus production tooling costs will be written off over relatively small numbers of installations. As more plants are built, receiver and storage design approaches will stabilize. Balance of plant costs can then be expected to approach "nth" plant estimates.

Federal Government Incentive Policies--As discussed above, full economic competitiveness is not likely to occur until after some period of initial heliostat mass production and after a few iterations on receiver/storage designs. In the interim, some vehicle for eliminating the cost/value differences to the users and/or suppliers must be provided in order to get plants built. The approach most favored by both the utilities and potential heliostat suppliers is the adoption of federal incentives to encourage the construction of the first commercial plants. The incentives might take the form of special investment tax credits, low interest loans, accelerated write-off periods, government funding of manufacturing facilities, etc. While each of these approaches has some merit, careful and immediate study by appropriate groups in DOE should be devoted to identifying the most effective ones. (Reference 12 provides an excellent starting point for this activity.) The incentives can be aimed at users or suppliers or both; e.g., additional investment tax credits can be offered to both those who will invest in production capabilities for solar equipment and those who buy and install it. The strong advantage of incentives is that the users are allowed maximum control in carrying out their projects, and the suppliers are encouraged to attract directly as many customers as possible for their product. Hence, the climate for normal commercial interactions is encouraged.

The effectiveness of this approach, however, is highly dependent on getting the incentives in place soon enough so that users and suppliers will be able to respond with little or no lag time after adequate demonstration in Phase 2. Because of anticipated long lead times for siting and licensing of the first plants for which procedures will not be well established, the utilities need incentives in place which will insure solar's economic attractiveness 2-4 years before construction is started. In addition, the suppliers require 2-3 years between the time a market is anticipated and the completion of a production facility. These facts point out the need to establish incentives as soon as possible, namely in the next year or two. Otherwise, gaps between demonstration periods and construction commitments by users can be expected.

Due to user and supplier planning requirements for commercialization by the early 1990's, the incentive program needs to be implemented rapidly and to remain in effect for a sufficient amount of time to insure the elimination of cost/value differences existing for the first commercial plants being built in Phase 3. This total time amounts to the sum of the planning and commitment times of users and suppliers (2-4 years) plus the required manufacturing investment recovery periods for the suppliers of the first plants (about 5 years). Two sets of incentives, one appropriate to the users and the other for suppliers, would help assure that both sectors will make their planning and commitment moves early.

Utility Commission Policy Revision--Current practices of most utility commissions tend to favor projects with lower initial capital investment even if operating costs are high. The up front project costs must be folded immediately into the rate base whereas increased operating costs can be added over time. Thus, higher initial investment costs mean higher near term increases in the rate base. This approach obviously favors fossil plants in comparison with solar. In addition, a new energy option, such as central receivers, whose reliability is not well characterized certainly offers higher risk to the customers whose interest are at stake. These considerations coupled with future economic uncertainties have made utility commissions reluctant to approve projects using unproven technologies.

In order to implement a new option such as the central receiver concept in the regulated utility environment, some commission policy revisions will be necessary. The utilities need encouragement that commissions will be receptive to new technology adoption and that they will allow some insurance against the risk of implementation. Effective actions might include: a guaranteed return on the investment in the event of premature shutdown before the end of the project's anticipated economic life; recovery of the investment starting in the construction period instead of when the plant comes on line; write-off of first of a kind plants as overhead (R&D) expenses; etc. In addition, changes in current practices regarding federal incentives are required in order that the federal incentive program recommended here be useful to the utilities. For example, typical commission policy is to pass through directly to the ratepayer, in the form of lower allowed charges, any favorable federal policy such as investment tax credits. The utilities need to share some part of these benefits in order to make financing of high risk projects attractive.

These actions on the state level are extremely important and may even be critical in accelerating commercialization of any of the new energy technologies. It is recommended, therefore, that the federal government establish a program to educate state policy makers and to implement, if necessary, regulations requiring utility commissions to evaluate new energy options in their state.

#### Phase 4: Commercialized Technology

At this point all special government programs or provisions can expire because the central receiver technology will be established as a competitive alternative for large scale energy production, in a position to compete using only those economic incentives enjoyed by other energy technologies. In the event of an established priority for accelerated penetration at this time, e.g., to achieve a 1 quad penetration goal by 2000, there may be some desire to keep or modify the special incentives adopted for the purposes of Phase 3. This topic, however, is not the focus of this report.

#### Timing of Programs

There must be substantial parallel development of the programs for each phase discussed in the previous sections in order to minimize the time to Phase 4. Figure 3 reorders the programs for commercialization listed in Table V in a time sequence. Starting times and durations for each program are based on points already discussed and on the current status of the program. Dashed lines imply uncertainty in activity starting and stopping times. When both user and supplier requirements are taken into account, and if the recommended actions are adopted, the technology can be competitive by 1992, assuming moderate coal price escalation rates.

Figure 3 also indicates interconnections between the various program elements based on the discussions in the previous sections. The Barstow project should move into startup and operation by the beginning of 1982. User requirements of reliable operation for two years minimum results in a 1984 to 1985 date at which the Barstow project becomes an influential factor in their planning activities. For the additional demonstration, the proposed scope of DOE's repowering program would satisfy both user needs for demonstration size and supplier requirements for intermediate heliostat production. This aspect plus the timeliness of the program recommend it as the choice for satisfying the purposes of Phase 2 beyond Barstow. The time required for selection, design, and construction of these projects restricts start-up of these plants to 1985 at the earliest. The need by the users to see these plants in operation for a minimum of two years results in a 1987 date when the earliest user initiated projects can be expected to begin. A slip in the repowering schedule will postpone this date. In addition, the two to four year user planning period prior to commitment means that users should be starting this activity as early as 1983 if they are to be in a position to start design and construction by 1987. At this early date, serious planning will take place only with the guarantee of the economic competitiveness of the solar plant in the late 1980's. In other words, the incentive program must be in effect by 1983 in order to minimize lags between demonstration and commitment.




FIGURE 3. Program Timing.

The heliostat production development schedule also points out the necessity for a long term incentive program since the recommended production development path will not result in mature mass production until 1992. The intermediate production timing couples well with the design and construction schedule for repowering. There is also a fortuitous match between the user assessment period for operation of the demonstration projects and the time required for constructing initial heliostat mass production facilities. By about 1987 some users could be ready to commit, and the manufacturing capabilities should be available to meet the demand. Following about five years of initial mass production, a move to larger production facilities coupled to mature designs can be expected. Costs attain their competitive levels at this point, and the transition to the fully commercialized technology is then complete in the 1990's.

### Roles of Participants

The general roles of the principal actors in each phase are outlined in Table VI. One can see in Table VI a shift from nearly exclusive government funding in Phase 1 to projects totally initiated and funded by the users in Phase 4. It is also important to note that some amount of user cost sharing is recommended as early as the Phase 2 demonstrations in order to indicate user, as well as government, commitment to developing the technology. This precedent has already been established for the Barstow plant. The additional demonstrations should include user commitment to the value of the solar plant in their application, taking into account both the costs of alternative technologies and the risks for central receivers. This is the most straightforward way to achieve serious user participation.

Table VII combines Figure 3 and Table VI to indicate major specific actions to be taken by each of the groups and the times at which they should be taken.

Since this plan is recommending that the federal government through DOE take the initiative in the early years, a more detailed breakdown of the near term activities of DOE are indicated in Table VIII. A 1983 date for implementing incentives at both the federal and state levels suggests that the formulation of these measures begin immediately. In addition, the three year plus construction period for repowering projects means that the funds for this activity need to be in place by fiscal year 1982. Again the groundwork needs to be laid as soon as possible. A slip in these early activities pushes user acceptance and supplier commitment further out in the later years and postpones the estimated 1992 date for full commercialization.



TABLE VI

## GOVERNMENT, USER, SUPPLIER ROLES IN COMMERCIALIZATION

|            | Phase 1<br>Research and<br>Development   | Phase 2<br>Demonstration  | Phase 3<br>Commercial<br>Development   | Phase 4<br>Commercialized<br>Technology   |
|------------|--|---|--|---|
| Government | <ul style="list-style-type: none"> <li>• Provide pioneering costs</li> <li>• Provide test facilities</li> <li>• Disseminate results</li> <li>• Plan for long term</li> </ul> | <ul style="list-style-type: none"> <li>• Provide most of funding</li> <li>• Assume most of risk</li> <li>• Exercise some control to assure projects meet long range goals</li> <li>• Remove government barriers</li> </ul>              | <ul style="list-style-type: none"> <li>• Provide funding equal to cost minus value through financial incentives</li> <li>• Exercise minimum control</li> </ul>     | <ul style="list-style-type: none"> <li>• Treat solar as any other developed technology</li> </ul>   |
| User       | <ul style="list-style-type: none"> <li>• Define potential applications</li> </ul>  | <ul style="list-style-type: none"> <li>• Provide some funding</li> <li>• Assume some risk</li> <li>• Begin individual economic assessments</li> </ul>   | <ul style="list-style-type: none"> <li>• Initiate and control most of project</li> <li>• Complete economic assessments</li> </ul>                                  | <ul style="list-style-type: none"> <li>• Control projects completely</li> </ul>   |
| Suppliers  | <ul style="list-style-type: none"> <li>• Perform R&amp;D</li> <li>• Develop data on present and expected costs</li> </ul>  | <ul style="list-style-type: none"> <li>• Manufacture heliostats at intermediate production levels</li> <li>• Process development <ul style="list-style-type: none"> <li>- Heliostats</li> <li>- Balance of plant</li> </ul> </li> </ul> | <ul style="list-style-type: none"> <li>• Manufacture heliostats at initial mass production levels</li> <li>• Design and engineer first plants in detail</li> </ul> | <ul style="list-style-type: none"> <li>• Manufacture at high mass production volumes</li> <li>• Establish design and engineering procedures for balance of plant</li> </ul> |

TABLE VII

ACTIONS OF GOVERNMENT, USERS, SUPPLIERS IN COMMERCIALIZATION

---

Government

- Approve repowering projects - 1980
- Complete Barstow - 1981
- Adopt incentive polices - 1983
- Fund and complete repowering projects - 1982 + 1985
- Terminate special incentives - 1992

Users

- Begin planning activities - 1983
- Evaluate Barstow operation - 1985
- Evaluate repowering projects - 1987
- Commit to construction - 1987 +


Heliostat Suppliers

- Produce at intermediate levels - 1982 + 1985
- Enter initial mass production phase
  - Begin facility construction - 1985
  - Begin production - 1987
- Move into large scale mass production - 1992 +

Balance of Plant Suppliers


- Design and construct repowering plants - 1981 + 1984
  - Design and construct first commercial plants - 1985 + 1992
  - Enter stable component production phase - 1992 +
-

DEMONSTRATION PROGRAMS




- |  |  |
|--|--|
| <ol style="list-style-type: none"> <li>1. Issue PON for repowering.</li> <li>2. Insure budget approval for repowering.</li> <li>3. Select repowering construction projects.</li> <li>4. Complete Barstow construction, begin operation.</li> </ol> | <ol style="list-style-type: none"> <li>5. Insure budget approval for remaining repowering funds.</li> <li>6. Same as 5.</li> <li>7. Same as 5.</li> <li>8. Complete repowering project construction, begin operation.</li> </ol> |
|--|--|

INCENTIVE PROGRAMS



- |   |   |
|---|---|
| <ol style="list-style-type: none"> <li>1. Begin federal incentive review.</li> <li>2. Set up group to evaluate state policies, interact with PUC's.</li> <li>3. Propose federal incentive package to Congress.</li> </ol> | <ol style="list-style-type: none"> <li>4. Propose actions affecting state level policies.</li> <li>5. Secure federal incentives legislation.</li> <li>6. Secure legislation (if any) affecting state policies.</li> </ol> |
|---|---|



- |  |  |
|--|--|
| <ol style="list-style-type: none"> <li>1. Begin review of information transfer mechanisms.</li> <li>2. Establish responsibility for information transfer.</li> </ol> | <ol style="list-style-type: none"> <li>3. Review information transfer programs, revise if necessary.</li> <li>4. Same as 3.</li> </ol> |
|--|--|

● Start activity      ■ Intermediate goals      ▲ Completion points

TABLE VIII. Near Term DOE Activities.

## Costs for Commercialization

In estimating program costs for demonstration in Phase 2 and incentive allowances in Phase 3, two factors must be considered. Obviously, the estimates on the solar plant costs in each phase provide the upper bound on expected program costs. On the other hand, the solar plant will have some value associated with it depending on the kind and amount of energy it displaces. As a baseline for estimating program costs, the value of the solar plant was bounded by the cost of a coal plant and fuel with the assumptions of Table IX. The solar plant cost assumptions are given in Table X, the economic assumptions in Table XI.

TABLE IX

### COAL PLANT AND FUEL COST/PERFORMANCE ASSUMPTIONS

---

- \* Installed Plant Cost - \$925/kW<sub>e</sub> (1980)<sup>1</sup>
- \* Delivered Coal Cost - \$1.50/10<sup>6</sup> BTU (1980)<sup>2</sup>
- \* Fuel Escalation - 1% above inflation thru plant life<sup>3</sup>
- \* Capacity factor - 50%<sup>4</sup>
- \* Heat Rate - 10,000 BTU/kw-hr

---

<sup>1</sup>Suggested from EPRI Technical Assessment Guide (13; late 1978 estimate escalated to mid-1980) and optimistic utility opinion.

<sup>2</sup>Typical of current new contract prices in the Southwest.

<sup>3</sup>Approximately equivalent to: 6% above inflation through 1985 followed by 0% real escalation throughout remainder of plant life.

<sup>4</sup>Average size for comparison with solar plant.

---

TABLE X  
SOLAR PLANT COST/PERFORMANCE ASSUMPTIONS

---

- \* 50% capacity factor average
  - \* Phase 2 - Demonstration Plants
    - Repowering application - no turbine/generator or land costs included
    - Optimal system design with improved receiver/storage technologies (i.e., salt, sodium, improved water/steam) -30% decrease in direct costs compared to Barstow
    - Government involvement similar to Barstow -60% distributables and indirects budget<sup>1</sup>
    - Heliostat costs from intermediate level production - \$300/m<sup>2</sup>
    - Installed solar plant costs - \$7600/kW<sub>e</sub><sup>2</sup>
    - Plant efficiency ~22% (incident sunshine to electricity)
  - \* Phase 3 - Early Commercial Plants
    - Small commercial plant diseconomies of scale ~10%
    - First plant design and engineering on balance of plant - 50% over nth plant costs
    - \$200/kW<sub>e</sub> for turbine/generator
    - Heliostat costs from low level mass production - \$150/m<sup>2</sup>
    - Installed solar plant cost - \$2,400/kW<sub>e</sub>
    - Plant efficiency ~22%<sup>3</sup>
  - \* Phase 4 - Commercialized Technology
    - Installed solar plant costs - \$1600/kW<sub>e</sub>
- 

<sup>1</sup>Decreased government supervision, simplified procurement procedures, etc., compared to Barstow can greatly reduce this value.

<sup>2</sup>Consistency with repowering plan estimates (reference 9) discussed in reference 14.

<sup>3</sup>Poorer field performance in larger Phase 3 plants compensated for with more efficient balance of plant components to give about the same efficiency as Phase 2 plants.

TABLE XI  
ECONOMIC ASSUMPTIONS

---

|                                    |
|------------------------------------|
| General Inflation - 8%             |
| Capital Escalation - 8%            |
| Discount Rate - 10%                |
| Fixed Charge Rate - 17.75%         |
| Interest During Construction - 25% |
| Plant Operating Life - 30 years    |

---

Based on these assumptions, the costs for commercialization can be estimated. A realistic scenario would suggest solar plant costs changing with time in a manner similar to the schematic illustrated in Figure 4. Costs for plants built in the five year period of Phase 3 should decline as design and engineering practices become better established. Some discontinuity can then be expected in the transition to the fully commercialized technology (Phase 4) as shown. This should occur as initial production facilities are paid off and/or larger production economies of scale come into effect. For the purpose of the first order analysis of this plan, however, the estimated average cost of the solar plants during each phase has been used. Figure 5 presents the equivalent costs of the solar and coal plants for each of the phases.

The total cost to the government is evaluated as the difference between the two cost curves in each phase times the total installed capacity. In Phase 2, the total is based on two heliostat suppliers producing 2000 units/year for three years; at 50% capacity factor, this amounts to an installed capacity of about 80 MW<sub>e</sub>. In Phase 3, heliostat production is at 15,000 units/year from two suppliers for five years; at 50% capacity factor, this is 900 - 950 MW<sub>e</sub>. Total program costs are \$1.2 billion as shown in Table XII. This assumes user participation to the full value of the conventional coal plant alternative. A more pessimistic approach would acknowledge user reluctance to credit the demonstration and first commercial plants with full value due to the risk associated with the technology at that time. The extreme of no user cost sharing in the demonstration plants and no capacity credit (i.e., fuel displacement value only for the first commercial plants) results in the costs shown in parentheses. The Appendix presents the same analysis based on oil displacement rather than coal for comparison.

It is important to distinguish the nature of the various costs presented in Table XII. Both the operating (primarily R&D) and demonstration costs are direct government expenditures totaling \$810-\$965 M with most of it spent by 1985. Table XIII indicates the year by year profile. The remaining costs are in the form of incentives, which can limit government contributions to a cost effective level. Should the technology not be ready for widespread user acceptance by 1987 or if the incentives prove inadequate, then they will not




FIGURE 4. Schematic of Solar Plant Cost Variation with Time.




FIGURE 5. Equivalent Costs of Solar Central Receiver and Coal Plants.



TABLE XII

## TOTAL PROGRAM COSTS TO THE GOVERNMENT (1980 \$)

| FY 1981 → FY 1992  |                                  |
|--|----------------------------------|
| Demonstration Plants   | \$467 M (\$623 M <sup>1</sup> )  |
| Incentives for First Commercial Plants   | \$383 M (\$1215 M <sup>2</sup> ) |
| Operating Expenses<br>(Continued R&D, demonstration<br>project operation, capital equipment) | \$342 M <sup>3</sup>             |
| TOTAL  | \$1182 M (\$2170 M)              |

|                               |
|-------------------------------|
| Installed Capacity ~ 1000 MWe |
|-------------------------------|

<sup>1</sup>No user cost share; both figures include \$10 M for completion of Barstow in 1981.

<sup>2</sup>Solar plant value based only on fuel displacement only.

<sup>3</sup>From current Multi-Year Program Plan.

TABLE XIII

REQUIRED BUDGET AUTHORITY (1980\$)<sup>1</sup>

| FY                | 81   | 82    | 83    | 84    | 85   | 86   | 87   | 88   | 89   | 90   | 91   | 92   | Cumulative         |
|-------------------|------|-------|-------|-------|------|------|------|------|------|------|------|------|--------------------|
| Total             | 65.0 | 171.5 | 277.4 | 199.8 | 55.6 | 32.5 | 25.5 | 19.5 | 14.2 | 13.0 | 11.0 | 10.0 | 895.0              |
| Operating         | 35.2 | 50.5  | 49.4  | 36.8  | 34.6 | 30.7 | 23.7 | 18.0 | 13.0 | 12.0 | 9.0  | 9.0  | 322.9 <sup>2</sup> |
| Construction      | 28.0 | 119.0 | 226.0 | 161.0 | 19.0 | -    | -    | -    | -    | -    | -    | -    | 553.0 <sup>3</sup> |
| Capital Equipment | 1.8  | 2.0   | 2.0   | 2.0   | 2.0  | 1.8  | 1.8  | 1.5  | 1.2  | 1.0  | 1.0  | 1.0  | 19.1               |

<sup>1</sup>As of publication date.

<sup>2</sup>Includes R&D and operating expenses for Barstow and repowering (FY81-88) of ~\$10 M/yr.

<sup>3</sup>Includes \$10 M for Barstow (FY81) and assumes \$70 M (12%) cost share for repowering projects (fuel displacement value).

be subscribed to the full extent of the \$400-1200 M indicated here. Besides the lower risk to the government, incentives offer a lower cost approach than some form of direct government outlay because of the absence of the collection and budgetary approval steps associated with direct expenditures.

The average government expenditure per  $\text{kW}_e$  installed capacity is \$1200-2200/ $\text{kW}_e$ .

### Modifications to the Plan

A number of actions or different approaches to the plan recommended here can be proposed. Regardless of the particulars, any such modification will tend to either expand or narrow the scope of the proposed program. In discussing the effects of either, one should keep in mind certain points about the program recommended here.

The intent has been to provide a low risk path to commercial readiness regardless of the time required or the capacity displaced in the interim. As such, market penetration goals such as those set forth in the President's Domestic Policy Review may not be attained without a more ambitious program than outlined here. Such a program could include additional demonstration in non-utility applications in order to attract a wider market, and/or greater financial incentives early on to accelerate user commitment. The former is in fact a part of the repowering plan (9), in which industrial process heat projects, as well as utility projects, are included. Such actions, however, may require a larger government expenditure.

It should also be recognized that the recommendations presented here have been developed through an examination of the basic elements of the commercialization process. Thus, they represent a minimum effort for developing both user acceptance and supplier readiness in an orderly fashion. Changes to this plan which would compromise program elements at levels below those recommended run the risk of not developing the market and/or supply sectors as desired. For example, key elements for demonstration (Phase II) are not only user requirements, which dictate project size, but also intermediate heliostat production, whose essential characteristics include a minimum level and duration of production plus the competitive element. Sacrificing any of these could well postpone the availability of the fully commercialized technology.

While the program elements can be viewed as a conservative set with respect to risk to the users and suppliers involved, the proposed timing is optimistic. Significant overlap is recommended in anticipation of success of each activity, but a less optimistic phasing will postpone full commercialization past the twelve years suggested here. Some aggressive moves on the part of the government are called for, but the risk is minimized through the recommended approach of incentives for the transition from demonstration to the established technology.

## Conclusions

The program for commercialization of solar central receivers presented here has incorporated the major requirements of both users and suppliers. The timing is dictated by user needs for planning and demonstration and by manufacturing requirements for design iteration and production process development. As such, the program can be viewed as a conservative approach in which the technology evolves through the normal steps which might occur in a totally private commercialization effort.

The importance of the government role, however, must not be underestimated. By providing funds for large scale demonstrations and incentives for the early commercial plants, the government is accelerating the pace at which the technology is implemented. The costs achieve competitive status with component production design maturity and high production levels. Only with government involvement at the approximate levels proposed here can this happen by the early 1990's.

Key points of this plan include: (1) the ability to resolve simultaneously two problems facing adoption of the technology, i.e., adequate demonstration for the users coupled with an intermediate level of heliostat production; (2) identification of incentives, in place of direct government expenditures, as the approach for getting the first commercial plants built; the timely adoption of and long term commitment to this approach is essential; (3) total costs to the government amount to \$1.2 - \$2.2 billion; of this total, \$800-\$950 M is in the form of direct expenditures for continuing R&D and additional demonstration.

There are several remaining areas for investigation. Foremost is the effect of an added market besides electrical. In particular, recent studies (2) indicate the attractiveness of many industrial process heat applications. Revisions to this plan, if necessary, will be made in the future as this additional market is better characterized. The other important follow-on activity is the identification of the most cost effective incentives to both users and suppliers.

## REFERENCES

1. P. J. Eicker, "Comparison of Projected Electricity Costs for Coal-Fired and Central Receiver Power Plants," in Department of Energy Solar Central Receiver Semiannual Review, Sandia Report SAND79-8073, November 1979.
2. P. J. Eicker, et al., "Design, Cost, and Performance Comparisons of Several Solar Thermal Systems for Process Heat, Vol. I-V," to the published as Sandia Laboratories Report.
3. J. L. Thornton, et al., "Comparative Ranking of 0.1-10 MW<sub>e</sub> Solar Thermal Electric Power Systems," SERI/TR-351-461, August 1980.
4. W. W. Laity, et. al., "Assessment of Solar Options for Small Power Systems Applications," Battelle Report PNL-4000, September 1979.
5. M. J. Fish, "Utility Views on Solar Thermal Central Receivers," Sandia Report SAND80-8203, April 1980.
6. L. D. Brandt, "A Strategy for Heliostat Commercialization," Sandia Report, SAND80-8239, November 1980.
7. L. N. Tallerico, "A Description and Assessment of Large Solar Power Systems Technology," Sandia Report SAND79-8015, August 1979.
8. R. A. Charpie, et. al., "The Demonstration Project as a Procedure for Accelerating the Application of New Technology," DOE/RA-0003/1, February 1978.
9. L. Prince, "Solar Repowering/Industrial Retrofit Program Element Plan," Draft Report, January 1980.
10. McDonnell Douglas Astronautics Co., "Solar Central Receiver Prototype Heliostat CDRL, Final Technical Report," MDC-67399, August 1978.
11. General Motors Transportation Systems Center, "Heliostat Production Evaluation and Cost Analysis," SERI/TR-8052-1, March 1980.
12. "Southwest Project, Institutional Studies, Vol. IV," prepared for DOE, Contract No. EM-77-C-01-8720, August 1979.
13. Electric Power Research Institute, "Technical Assessment Guide," Report No. PS-1201-SR, July 1979.
14. M. J. Fish, memo to L. Prince, DOE/SAN, June 1980 (copies available by request).

## APPENDIX--PROGRAM COSTS BASED ON OIL DISPLACEMENT

The analysis in the main text on costs for commercialization is based on coal as the alternative for determining solar plant value, and as such, the results can be regarded as conservative. Arguments can be made that solar plants will actually be displacing oil or natural gas, particularly in repowering applications, and that these fuels should form the basis for determining solar plant value.

Assuming oil displacement as the criteria for solar plant value, the costs for commercialization can be determined as in the main text using the equivalent \$/kW for the oil displaced instead of the coal plant and fuel cost. Figure A-1 is the analogous version of Figure 5 in the main text. The economic assumptions are the same as those in Table XI of the main text, with the current oil price assumed as \$4.00/10<sup>6</sup> Btu escalating at 1% above inflation. The heat rate used is 8500 Btu/kW-hr. The corresponding program costs are given in Table A-I.

Since the estimated costs for the first commercial plants (Phase 3) are very close to the value of the oil displaced, this analysis suggests that the government need only demonstrate the technology at the proper level and that no special incentives will be required in getting the first commercial plants built. However, for existing facilities being forced off oil and gas, the most economical alternative is coal, and moreover, new plants are likely to be coal fired because of its economic attractiveness over the alternatives. Hence, the analysis and discussion in the main text is based on coal.




FIGURE A-1. Equivalent Costs of Solar Central Receiver Plants and Fuel Value in Oil Plants.

TABLE A-1

TOTAL PROGRAM COSTS TO THE GOVERNMENT (1980\$)  
OIL DISPLACEMENT

| FY 1981 → FY 1992                      |                                 |
|--|---------------------------------|
| Demonstration Plants                   | \$420 M (\$623 M <sup>1</sup> ) |
| Incentives for First Commercial Plants | --                              |
| Operating Expenses                     | \$342 M <sup>2</sup>            |
| TOTAL                                  | \$762 M (\$965 M <sup>1</sup> ) |

<sup>1</sup>No user cost share; \$10 M for completion of Barstow included.

<sup>2</sup>From current Multi-year Program Plan.



UNLIMITED DISTRIBUTION

FIRST RELEASE

T. Stelson, DOE/HQ  
R. San Martin, DOE/HQ  
L. S. Levine, DOE/HQ  
G. W. Braun, DOE/HQ  
W. Auer, DOE/HQ  
J. Dollard, DOE/HQ  
J. Easterling, DOE/HQ  
J. E. Rannels, DOE/HQ  
M. U. Gutstein, DOE/HQ  
L. Melamed, DOE/HQ  
G. M. Kaplan, DOE/HQ  
M. J. Katz, DOE/HQ  
Lee Barrett, DOE/HQ  
Mary Glass, DOE/HQ  
Bill Hochheiser, DOE/HQ  
Isabell Neddow, DOE/HQ  
Dan Ancona, DOE/HQ  
Gene Burcher, DOE/HQ  
Cyril Draffin, DOE/HQ  
J. Gahimer, DOE/HQ  
L. Herwig, DOE/HQ  
J. LaGrone, DOE/SAN  
J. Blasy, DOE/SAN  
R. Duval, DOE/SAN  
R. W. Hughey, DOE/SAN  
S. D. Elliott, DOE/SAN  
Larry Prince, DOE/SAN  
Fred Corona, DOE/SAN  
K. Rose, DOE/SAN  
J. Nevils, DOE/SAN  
H. Roser, DOE/ALO  
J. Weisiger, DOE/ALO  
G. Pappas, DOE/ALO  
M. Slaminski, DOE/STMPO  
R. N. Schweinberg, DOE/STMPO

M. Sparks, 1  
A. Narath, 4000; Attn: J. H. Scott, 4700  
G. E. Brandvold, 4710  
B. W. Marshall, 4713  
D. G. Schueler, 4719  
V. L. Dugan, 4720  
J. V. Otts, 4721  
J. F. Banas, 4722  
W. P. Schimmel, 4723  
T. A. Dellin, 4723  
J. A. Leonard, 4725  
H. M. Dodd, 4744

T. B. Cook, 8000;  
Attn: A. N. Blackwell, 8200  
W. J. Spencer, 8100;  
Attn: W. E. Alzheimer, 8120  
B. F. Murphey, 8300;  
Attn: D. M. Schuster, 8310  
G. W. Anderson, 8330  
W. Bauer, 8340  
D. Hartley, 8350

R. L. Rinne, 8320  
C. F. Melius, 8326  
J. J. Iannucci, 8326  
A. R. Kerstein, 8326  
M. J. Fish, 8326 (50)  
L. D. Brandt, 8328  
L. Gutierrez, 8400  
C. S. Selvage, 8420  
R. C. Wayne, 8450  
P. J. Eicker, 8451  
A. C. Skinrood, 8452  
W. G. Wilson, 8453  
Peter Dean, 8265  
Publication Division, 8265, for TIC (27)  
Publication Division, 8265/Technical Library Processes Division, 3141  
Technical Library Processes Division, 3141 (2)  
Library and Security Classification Division, 8266-2 (3)

SECOND RELEASE

Arizona Public Service  
P. O. Box 21666  
Phoenix, AZ 85036  
Attn: Bruce Broussard  
Merwin Brown  
Keith Turley  
Eric Weber

Salt River Project  
P. O. Box 1980  
Phoenix, AZ 85001  
Attn: Steve Chalmers  
Dick Durning  
Don Squire

Tucson Gas and Electric Co.  
2220 W. Sixth St.  
Tucson, AZ 85702  
Attn: J. L. Davis  
C. A. McCauley

Arizona Electric Power Cooperative, Inc.  
P. O. Box 670  
Benson, AZ 85602  
Attn: Thomas Perrine  
D. M. Smith  
Raymond Som  
Tim Hern

Pacific Gas and Electric Co.  
77 Beale St.  
San Francisco, CA 94106  
Attn: J. F. Bonner  
John Doyle  
Glen Ikemoto

Pacific Gas and Electric  
3400 Crow Canyon Road  
San Ramon, CA 94583  
Attn: Harold Seielstad  
John Wells  
Carl Weinberg

Los Angeles Department of Water and Power  
111 N. Hope Street  
Los Angeles, CA 90051  
Attn: Norman Nichols  
Ed Freudenberg  
Martin Grayman  
F. C. Osborn

Pasadena Water and Power  
100 N. Garfield Ave., Rm 301  
Pasadena, CA 91109  
Attn: J. T. Brodie

San Diego Gas and Electric Co.  
P. O. Box 1831  
San Diego, CA 92112  
Attn: Alton T. Davis  
R. G. Lacy  
J. T. Montomery  
Al Figueroa

Southern California Edison  
P. O. Box 800  
Rosemead, CA 91770  
Attn: Norm DeHaven  
Joe Reeves  
W. H. Von Kleinsmid  
Tony Fung  
George Rodrigues

Glendale Public Service Department  
119 N. Glendale Ave  
Glendale, CA 91206  
Attn: W. H. Fell

Sacramento Municipal Utility District  
P. O. Box 15830  
Sacramento, CA 95813  
Attn: Lee Keilman  
Larry Smith  
W. C. Walbridge

Burbank Public Service Department  
164 W. Magnolia Blvd.  
Burbank, CA 91502  
Attn: J. D. Woodburn

Hawaiian Electric Co. Inc.  
Box 2750  
Honolulu, HI 96803  
Attn: Carl H. Williams

Colorado-UTE Electric Association  
P. O. Box 1149  
Montrose, CO 81401  
Attn: J. J. Bugas  
K. E. Norris

Lamar Light and Power Department  
100 N. Second St.  
Lamar, CO 81052  
Attn: B. D. Carnahan

Bureau of Reclamation  
Code 1500 E  
P. O. Box 25007  
Denver, CO 80225  
Attn: Stanley Hightower

Intermountain Rural Electric Association  
2100 W. Littleton Blvd.  
Littleton, CO 80120  
Attn: S. Lewandowski

Public Service of Colorado  
P. O. Box 840  
Denver, CO 80201  
Attn: R. T. Person  
C. K. Millen  
Ed Ellis  
Robert V. Hugo  
D. T. Spangenberg  
Patrick McCarter

Southern Colorado Power Division  
Central Telephone and Utility Corp.  
P. O. Box 75  
Pueblo, CO 81002  
Attn: J. D. Perry

Trinidad Municipal Power and Light  
135 N. Animas St.  
Trinidad, CO 81082  
Attn: A. Schroeder

Redlands Water and Power Co.  
768 North Avenue  
Grand Junction, CO 81501  
Attn: R. E. Schultz

Colorado Springs Department  
of Public Utilities  
P. O. Box 1103  
Colorado Springs, CO 80947  
Attn: R. P. Washburn

Florida Power Corp.  
P. O. Box 14042  
St. Petersburg, FL 33733  
Attn: Jim Crews  
R. O. Frazee  
Larry Rodrigues  
N. B. Spake

Florida Power and Light  
P. O. Box 3100  
Miami, FL 33101  
Attn: Gary Michel

Georgia Power Co.  
P. O. Box 4545  
Atlanta, GA 30302  
Attn: Jim Miller  
Charles Whitmer

Cajun Electric Power Coop.  
P. O. Box 578  
New Roads, LA 70760  
Attn: M. L. Burgin

Houma Municipal Light Plant  
P. O. Box 987  
Houma, LA 70360  
Attn: H. M. Cancienne

Morgan City Municipal Electric Plant  
P. O. Box 1218  
Morgan City, LA 70380  
Attn: J. J. Cetalu

Ruston Utilities System  
P. O. Box 280  
Ruston, LA 71270  
Attn: B. J. Clary

Natchitoches Municipal Electric, Light,  
and Water Department  
P. O. Box 37  
Natchitoches, LA 71457  
Attn: L. C. Fletcher

New Orleans Public Service, Inc.  
P. O. Box 60340  
New Orleans, LA 70160  
Attn: W. McCollam  
W. L. Hurstell

Minden Utilities System  
Yale and Horton Sts.  
Minden, LA 71055  
Attn: E. H. Lowe

Lafayette Utilities System  
733 Jefferson St.  
Lafayette, LA 70501  
Attn: S. J. Richard

Louisiana Power and Light Co.  
142 Delaronde St.  
New Orleans, LA 71074  
Attn: E. A. Rodrigue

Central Louisiana Electric Co.  
415 Main St.  
Pineville, LA 71360  
Attn: W. D. Rosenmacher

Southwestern Electric Power Co.  
P. O. Box 1106  
Shreveport, LA 71156  
Attn: J. L. Stall

Alexandria Muncpal Power and  
Light Department  
P. O. Box 71  
Alexandria, LA 71301  
Attn: F. Stelly

Nevada Power Co.  
P. O. Box 230  
Las Vegas, NV 89151  
Attn: John Gibbs  
John Arlidge

Sierra Pacific Power Co.  
P. O. Box 10100  
Reno, NV 89510  
Attn: Gary Soule  
R. G. Richards  
A. H. Almilli

Plains Electric Generation and  
Transmission Coop.  
2401 Aztec Rd., NE  
Albuquerque, NM 87107  
Attn: S. K. Bazant  
Tom Carter

Public Service Company of New Mexico  
P. O. Box 2267  
Albuquerque, NM 87103  
Attn: D. J. Groves  
E. D. Kist  
Jack Maddox  
William C. Wygnant  
Abbas Akhil

Lea Company Electric Coop.  
Draw 1447  
Lovington, NM 88260  
Attn: K. C. Martin

Farmington Electric Utility  
P. O. Box 900  
Farmington, NM 87401  
Attn: W. J. Metheny  
D. L. Carlson

New Mexico Electric Service Corp.  
p. O. Box 920  
Hobbs, NM 88240  
Attn: R. F. Montgomery

Tucumcari Light and Power Department  
P. O. Box 1188  
Tucumcari, NM 88401  
Attn: A. Morris

Gallup Electric Department  
P. O. Box 1270  
Gallup, NM 87301  
Attn: R. C. Noe

Ponca City Municipal Water and  
Light Department  
1400 N. Union St.  
Ponca City, OK 74601  
Attn: C. E. Fulkerson

Western Farmers Coop.  
Anadarko, OK 73005  
Attn: R. E. Good

Kingfisher Municipal Light Department  
City Hall  
Kingfisher, OK 73750  
Attn: H. Gray

Oklahoma Gas and Electric Co.  
321 N. Harvey Ave.  
Oklahoma City, OK 73101  
Attn: J. G. Harlow  
Larry Franklin

Public Serice Company of Oklahoma  
P. O. Box 201  
Tulsa, OK 74102  
Attn: F. J. Meyer  
Wayne Schweikhard

Blackwell Municipal Light and  
Water Department  
224 W. Blackwell St.  
Blackwell, OK 74631  
Attn: J. R. Willis

Bonneville Power Administration  
P. O. Box 3621  
Portland, OR 97208  
Attn: Norman E. Fuller

Pacific Power and Light Co.  
920 Sixth Ave., SW  
Portland, OR 97204  
Attn: Bob Lisbakken  
Al Seekamp

Portland General Electric  
121 SW Salmon St.  
Portland, OR 97204  
Attn: Norman Sanesi

Tennessee Valley Authority  
1360 Commerce Union Bank Bldg.  
Chattanooga, TN 37401  
Attn: Rebecca Aslinger

Provo City Power Department  
251 W. 800 North  
Provo, UT 84601  
Attn: R. L. Dean

Utah Power and Light Company  
P. O. Box 899  
Salt Lake City, UT 84110  
Attn: E. A. Hunter  
S. Kent Evans

Moon Lake Electric Association  
P. O. Box 278  
Roosevelt, UT 84066  
Attn: M. J. Millett

Seattle City Light Company  
1015 Third Ave.  
Seattle, WA 98104  
Attn: C. S. Harlow

City of Tacoma  
P. O. Box 11007  
Tacoma, WA 98411  
Attn: A. C. Herstrom

Washington Water and Power Company  
P. O. Box 3727  
Spokane, WA 99220  
Attn: Donald L. Olson

Puget Sound Power and Light  
Puget Power Bldg.  
Bellevue, WA 98009  
Attn: Ron Hill

Texas Electric Service Co.  
P. O. Box 970  
Fort Worth, TX 76101  
Attn: W. G. Marquardt  
Maurice Wendt  
Jim Allison  
George A. Clary  
Pat L. Robinson

Texas Power and Light Co.,  
P. O. Box 6331  
Dallas, TX 75222  
Attn: M. J. F. Skelton  
U. Gibson  
V. Gibson

Bryan Municipal Electric System  
P. O. Box 1000  
Bryan, TX 77801  
Attn: J. T. Ard

Dallas Power and Light Co.  
1506 Commerce  
Dallas, TX 75201  
Attn: R. W. Cox  
J. B. Headrick  
Bill Aston  
Peter A. Fluck

Central Power and Light Co.  
P. O. Box 2121  
Corpus Christi, TX 78403  
Attn: Aaron Autry  
R. W. Hardy

El Paso Electric Co.  
P. O. Box 982  
El Paso, TX 7999  
Attn: Evern Wall  
Don Isbell  
Jim Brown

Gulf States Utilities  
P. O. Box 2951  
Beaumont, TX 77704  
Attn: Donham Crawford  
M. R. Lee  
Lynn Draper  
Roy J. West  
Aubrey Sprawls

Community Public Service Company  
501 West Sixth St.  
Forth Worth, TX 76102  
Attn: C. L. Cooke

Houston Lighting and Power Company  
P. O. Box 1700  
Houston, TX 77001  
Attn: J. G. Reese  
Bell Sample  
R. Murray Gordon  
David J. Pennell

Southwestern Public Service Company  
P. O. Box 1261  
Amarillo, TX 79170  
Attn: R. Tolk  
W. R. Esler  
Kenneth Ladd  
J. B. Matthews  
Alan Higgins  
J. C. Claughton

Austin Water, Light, and Power Department  
P. O. Box 1088  
Austin, TX 78767  
Attn: R. L. Hancock

Brownsville Public Utilities  
P. O. Box 3270  
Brownsville, TX 78520  
Attn: H. E. Hastings

West Texas Utilities Company  
1062 N. 3rd St.  
Abilene, TX 79604  
Attn: R. E. Kennedy  
Rick Stanaland

Garland Electric Department  
P. O. Box 189  
Garland, TX 75040  
Attn: E. E. Krause  
Bud Cariker

Denton Municipal Utilities  
Municipal Bldg.  
Denton, TX 76201  
Attn: J. C. Little

Brazos Electric Power Coop.  
P. O. Box 6296  
Waco, TX 76707  
Attn: J. E. Monahan  
G. P. Lamb

Greenville Municipal Light and  
Power Department  
P. O. Box 1049  
Greenville, TX 75401  
Attn: R. E. Nelson

South Texas Electric Coop.  
P. O. Box 2485  
Victoria, TX 77901  
Attn: O. S. Roeson

City Public Service Board of San Antonio  
P. O. Box 1771  
San Antonio, TX 78296  
Attn: J. K. Spruce  
Don Snyder

Mendina Electric Coop.  
2308 18th St.  
Hondo, TX 78861  
Attn: M. D. Vajdos

Lubbock Power and Light Department  
P. O. Box 2000  
Lubbock, TX 79414  
Attn: W. T. Wood

Kansas Power and Light Co.  
818 Kansas Ave.  
Topeka, KS 66612  
Attn: William E. Wall  
William Woellhof  
Martin Klotzback, Jr.

Kansas Gas and Electric Co.  
P. O. Box 208  
Wichita, KS 67201  
Attn: Robert Rives  
Bernard Ruddick

Kansas Corporation Commission  
State Office Bldg.  
Topeka, KS 66603  
Attn: Pete Loux  
Brian Moline  
Al Maxwell

Kansas Energy Office  
214 W. 6th St.  
Topeka, KS 66603  
Attn: Joseph King

University of Kansas  
1013 Learned Hall  
Lawrence, KS 66045  
Attn: Dr. Art Breipohl

Electric Power Research Institute  
P. O. Box 10412  
Palo Alto, CA 93403  
Attn: John Bigger  
Piet Bos  
John Cummings  
Edgar DeMeo  
Blair Swezey

University of Kansas Center for Research  
2291 Irving Hill Rd.  
Lawrence, KS 66045  
Attn: Robert F. Riordan

Gibbs and Hill, Inc.  
393 7th Ave.  
New York, NY 10001  
Attn: V. P. Buscemi

Foster Wheeler Corp.  
12 Peach Tree Hill Rd.  
Livingston, NJ 07039  
Attn: A. C. Gangadharan  
Ramjee Ragahaven

Institute of Gas Technology, Suite 218  
1825 K St., NW  
Washington, DC 25006  
Attn: Donald Glenn

National Rural Electric Cooperative  
Association  
1800 Massachusetts Ave. NW  
Washington, DC 20036  
Attn: Wilson Prichett  
Robert Partridge

Solar Planning Office West  
Suite 2500  
3333 Quebec  
Denver, CO 80207  
Attn: Ted Prythero

PFR Engineering  
4676 Admiralty Way, Suite 832  
Marina del Rey, CA 90291  
Attn: J. M. Pundyk  
Tzvi Rozenman

American Public Power Association  
2600 Virginia NW  
Washington, DC 20037  
Attn: Alex Radin

Public Service Electric and Gas Company  
80 Park Place  
Newark, NJ 07101  
Attn: Virginia Sulzberger

Interdevelopment, Inc.  
R. B. Hayes Bldg., Suite 1014  
2361 So. Jefferson Davis Hwy.  
Arlington, VA 22202  
Attn: Irene Zuk

Stone and Webster Eng. Corp.  
P. O. Box 5406  
Denver, CO 80217  
Attn: Jackson O'Connell

General Atomics  
P. O. Box 81608  
San Diego, CA 92138  
Attn: David Willemsen

Bechtel Power Corp.  
12400 East Imperial Hwy  
Norwalk, CA 90650  
Attn: Jerry Shapiro

Bechtel National Inc.  
P. O. Box 3965  
San Francisco, CA 94119  
Attn: Ernie Lam  
Paul Schmitz  
Jack Darnell

McDonnell Douglas  
5301 Bolsa Ave.  
Huntington Beach, CA 92647  
Attn: Ray Hallet  
Lee Weinstein  
W. H. P. Drummond  
C. R. Easton  
L. W. Glover  
Jim Blackmon  
Dick Fowler  
Frank Duquette

Martin Marietta  
P. O. Box 179  
Denver, CO 80201  
Attn: Lloyd Oldham  
David N. Gorman  
P. R. Brown  
H. C. Wroton



Northrup Inc.  
302 Nichols Dr.  
Hutchins, TX 75141  
Attn: J. A. Pietsch  
Jim McDowell  
R. L. Henry

Westinghouse Corp.  
P. O. Box 10864  
Pittsburgh, PA 15236  
Attn: R. W. Devlin  
J. J. Buggy

Westinghouse Electric Corp.  
East Pittsburgh, PA 15112  
Attn: John Day

Boeing Engineering and Construction  
P. O. Box 3707  
Seattle, WA 98124  
Attn: Roger Gillette  
D. K. Zimmerman  
Keith Halvorson  
J. R. Gintz  
R. Campbell

General Electric  
1 River Rd.  
Schenectady, NY 12345  
Attn: James Elsner  
John Garate  
Richard Horton  
Robert Salemme  
Edward J. Davis  
R. N. Griffin

Energy Systems Group  
Rockwell International  
8900 De Soto Ave.  
Canoga Park, CA 91304  
Attn: Tom Springer  
Ralph Balent  
Ed Ash

Solar Energy Research Institute  
1536 Cole Blvd.  
Golden, Co 80401  
Attn: Denis Hayes  
Ken Touryan  
Barry Butler  
John Thornton  
Neil Woodley  
Charles Bishop  
Bim Gupta

Ron Edelstein  
Margaret Cotton  
David Schaller  
M. Murphy

PRC Energy Analysis Co.  
7600 Old Springhouse Rd.  
McLean, VA 22101  
Attn: J. V. Conopask  
Azhar Farood  
Neil Kochman

Solar Thermal Test Facilities Users  
Association  
Suite 1204, First National Bank, East  
Albuquerque, NM 87108  
Attn: Frank Smith

Mitre Corporation  
1820 Dolly Madison Blvd.  
McLean, VA 22102  
Attn: Willard Fraize  
David Boyd

California Energy Commission  
1111 Howe Ave, M-S 70  
Sacramento, CA 95825  
Attn: Dick Pierson

California Public Utilities Commission  
State Bldg, Civic Center  
San Francisco, CA 94102  
Attn: John M. Peeples

Jet Propulsion Laboratory  
4800 Oak Grove Dr.  
Pasadena, CA 91003  
Attn: Mickey Alpert  
Vince Truscello  
Tosh Fujita  
Rosalyn Barbieri  
Ab Davis

Los Alamos Scientific Laboratory  
P. O. Box 1663  
Los Alamos, NM 87545  
Attn: Frank Finch  
Dave Freiwald  
Ken Williamson

Lawrence Livermore Laboratory  
P. O. Box 808  
Livermore, CA 94550  
Attn: C. J. Anderson L-216  
R. B. Bell L-216

E-Systems  
P. O. Box 226118  
Dallas, TX 75266  
Attn: W. J. Hesse  
Robert R. Walters

Black and Veatch  
P. O. Box 8405  
Kansas City, MO 64114  
Attn: Sheldon Levy  
J. C. Grosskreutz

Energy Advisory Council  
411 W. 13th St.  
Austin, TX 78711  
Attn: Alvin Askew

Springborn Laboratories  
Water St.  
Enfield, CT 06082  
Attn: Bernard Baum

Florida Solar Energy Center  
300 SR 401  
Cape Canaveral, FL 32920  
Attn: C. D. Beach

Dynatherm Corp.  
1 Industry Lane  
Cockeysville, MA 21030  
Attn: W. B. Bienert

Combustion Engineering  
100 Prospect Hill Rd.  
Windsor, CT 06095  
Attn: C. R. Bozzuto  
Herbert Payne

General Motors Transportation  
Systems Center  
GM Technical Center  
Warren, MI 48090  
Attn: John Britt

Gilbert Associates  
P. O. Box 1498  
Reading, PA 19603  
Attn: Elton Buell

Solar Energy Report  
P. O. Box 1519  
Washington, DC 20013  
Attn: Steve Butchock

General Electric Co.  
777 14th St., NW  
Washington, DC 20005  
Attn: Richard Buthmann  
Al Christensen

Arthur D. Little, Inc.  
1 Maritime Plaza  
San Francisco, CA 94947  
Attn: John Butterfield

NASA Lewis Research Center  
2100 Brook Park Rd.  
Cleveland, OH 44135  
Attn: Jim Calogeras

Brookhaven National Laboratory  
Upton, NY 11973  
Attn: G. Cottingham

Battelle PNL  
P. O. Box 999  
Richland, WA 99352  
Attn: Kirk Drumheller

Rocketdyne Div.  
Rockwell International  
6633 Canoga Ave.  
Canoga Park, CA 93140  
Attn: J. M. Friefeld

Office of Tech. Assessment  
United States Congress  
Washington, DC 20510  
Attn: John Furber

Exxon Enterprises Inc.  
Solar Thermal Systems  
P. O. Box 592  
Florham Park, NJ 07932  
Attn: Bob Garman

MIT Lincoln Laboratory D-337  
P. O. Box 73  
Lexington, MA 02173  
Attn: Philip Jarvinen

Honeywell/ERC  
2600 Ridgway Park  
Minneapolis, MN 55410  
Attn: R. T. LeFrois

Ford Aerospace  
3939 Fabian Way, T33  
Palo Alto, CA 94303  
Attn: I. Earl Lewis

Aerospace Corp. D-5, Rm 1110  
2350 E. El Segundo Blvd.  
El Segundo, CA 90245  
Attn: Prem Mathur  
Larry Sitney

U. S. Gypsum Co., Dept. 176-2  
101 S. Wacker Dr.  
Chicago, IL 60606  
Attn: Raymond McCleary

General Atomic Corp.  
P. O. Box 81608  
San Diego, CA 92117  
Attn: John McNeill

Sanders Associates  
333 Durand Bldg.  
Stanford, CA 94305  
Attn: Armand Poirier

Stanford Research Institute  
333 Ravenswood Ave.  
Menlo Park, CA 94025  
Attn: Art Slemmons

General Electric Co.  
3172 Porter Dr.  
Palo Alto, CA 94304  
Attn: Fred Witt

Babcock and Wilcox  
1562 Beacon  
Alliance, OH 44601  
Attn: Pari Parikh

Stone and Webster  
P. O. Box 2325  
Boston, MA 02107  
Attn: Don Guild

Badger Co., Inc.  
1 Broadway  
Cambridge, MA 02142  
Attn: Fred Gardner

RAND Corporation  
1700 Main St.  
Santa Monica, CA 92401  
Attn: Walter Baer

Scientific Applications, Inc.  
1546 Cole Blvd.  
Golden, CO 80401  
Attn: Jim Doane  
Milt Hetrick

Scientific Applications, Inc.  
1801 Ave. of the Stars  
Los Angeles, CA 90024  
Attn: Ron Hoffman

A. F. Hildebrandt  
University of Houston  
Solar Energy Laboratory  
Houston, TX 77004

T. T. Bramlette  
DFVLR-SSPS  
Linder Hohe  
5000 Koln 90  
Cologne, W. GERMANY

Scientific Applications Inc.  
8400 Westpark Dr.  
McLean, VA 22102  
Attn: Dr. Richard A. Moyle

Research Triangle Institute  
P.O. Box 12194  
Research Triangle Park, NC 22709  
Attn: Dr. Richard A. Whisnant

Accurex Corp.  
485 Clyde Ave.  
Mountain View, CA 94042  
Attn: Mitchell R. Wool

Stanley Consultants  
Stanley Bldg.  
Muscatine, Iowa 52761  
Attn: David K. Johnson

Hitachi Cable Ltd.  
777 Third Ave.  
New York, NY 10017  
Attn: Kuniaki Tomori

Aerospace Corp.  
P.O. Box 92957  
Los Angeles, CA 90009  
Attn: Dr. C. Keith Cretcher

Hans W. Wynholds Co.  
P.O. Box 731  
Cupertino, CA 95015  
Attn: Hans W. Wynholds

Pullman Power Products  
Lakeside Plaza, Suite 230  
1575 N. Universal Ave.  
Kansas City, MO 64120  
Attn: Thomas G. Tarber

Utah Power & Light Co.  
1407 West North Temple  
Salt Lake City, UT 84116  
Attn: Allen B. Rudy

Northern States Power Co.  
414 Nicollet Mall, 4th Floor  
Minneapolis, MI 55401  
Attn: Leslie C. Weber  
Frank Mach

American Electric Power Service Corp.  
2 Broadway  
New York, NY 10004  
Attn: Nicholas Tibbets

Delmarva Power  
P.O. Box 231  
Wilmington, DE 19899  
Attn: William D. Ferguson

St. Joseph Light & Power Co.  
520 Francis St.  
St. Joseph, MO 64502  
Attn: Patrick S. Hurley

Kansas RECs  
P.O. Box 4267  
Gage Center Station  
Topeka, KS 66604  
Attn: Harold Shoaf

Lamar University  
Electrical Engineering Dept.  
P.O. Box 10029  
Beaumont, TX 77710  
Attn: Dr. W. R. Wakeland

University of Wisconsin - Extension  
717 Extension Bldg.  
423 North Lake St.  
Madison, Wisconsin 53706  
Attn: Charles H. Fafard

Dr. Bruce M. Smackey  
2026 Hopewell Rd.  
Bethlehem, PA 18017

Worcester Polytechnic Institute  
Worcester, Massachusetts 01609  
Attn: Dr. James S. Demetry

Chris Kolvakas  
3 Metropolitan Circle  
Roslindale, Mass. 02131

Cincinnati Gas & Electric  
P.O. Box 960  
Cincinnati, Ohio 45201  
Attn: John B. Fisch

Oak Ridge National Laboratory  
P.O. Box X  
Oak Ridge, TN 37830  
Attn: Jesse S. Tatum

Minnesota Power & Light  
30 West Superior St.  
Duluth, Minn. 55802  
Attn: Karen Evens

Babcock and Wilcox  
91 Stirling Ave.  
Barberton, OH 44203  
Attn: Mike Seale

Lincoln Electric System  
P.O. Box 80869  
Lincoln, NE 68501  
Attn: Richard L. Kahle

Burns and McDonnell  
P.O. Box 173  
Kansas City, MO 64110  
Attn: Dayna Justus

Martin Marietta Corp.  
6801 Rockledge Dr.  
Bethesda, MD 20034  
Attn: Norman Schiff

Nebraska Public Power District  
Box 499  
Columbus, NE 68601  
Attn: Joe Pacovsky

Colorado WSUN  
Colorado Office of Energy Conservation  
1600 Downing St.  
Denver, CO 80218  
Attn: Dennis Bates

Middle South Services Inc.  
P.O. Box 61000  
New Orleans, LA 70161  
Attn: Regis G. Trumps

Empire District Electric Co.  
P.O. Box 127  
Joplin, MO 64801  
Attn: Vernon Corkle

Carolina Power & Light Co.  
P.O. Box 1551  
Raleigh, NC 27602  
Attn: Archie W. Futrell

California Public Utilities Commission  
350 McAllister St., Room 5040  
San Francisco, CA 94102  
Attn: Leonard M. Grimes, Jr.

Phillips Chemical Co.  
13-D2 Phillips Bldg.  
Bartlesville, OK 74004  
Attn: Mark Bowman

Department of Phycis  
University of Manitoba  
Room 22, Allen Physics Bldg.  
Winnipeg, Manitoba R3T 2N2  
Canada  
Attn: Dr. J. S. C. McKee

ARCO  
911 Wilshire Blvd.  
Los Angles, CA 90017  
Attn: J. H. Caldwell, Jr.

| Org. | Bldg. | Name        | Rec'd by * | Org. | Bldg. | Name | Rec'd by * |
|------|-------|-------------|------------|------|-------|------|------------|
| 4713 |       | John Holmes |            |      |       |      |            |
|      |       |             |            |      |       |      |            |
|      |       |             |            |      |       |      |            |
|      |       |             |            |      |       |      |            |
|      |       |             |            |      |       |      |            |
|      |       |             |            |      |       |      |            |
|      |       |             |            |      |       |      |            |
|      |       |             |            |      |       |      |            |
|      |       |             |            |      |       |      |            |
|      |       |             |            |      |       |      |            |
|      |       |             |            |      |       |      |            |
|      |       |             |            |      |       |      |            |
|      |       |             |            |      |       |      |            |
|      |       |             |            |      |       |      |            |
|      |       |             |            |      |       |      |            |
|      |       |             |            |      |       |      |            |
|      |       |             |            |      |       |      |            |
|      |       |             |            |      |       |      |            |
|      |       |             |            |      |       |      |            |
|      |       |             |            |      |       |      |            |
|      |       |             |            |      |       |      |            |

\* Recipient must initial on classified documents.