

# MOLTEN SALT ELECTRIC EXPERIMENT (MSEE)

## System Operation



# Molten Salt Electric Experiment (MSEE) System Operation

1275

MOLTEN SALT ELECTRIC EXPERIMENT  
(MSEE)

SYSTEM OPERATION

31 AUGUST 1984

## FORWARD

This System Operation Plan is one of three documents that describe plans for Phase II of the MSEE Project. These documents are:

### MSEE Evaluation Plan

Plan to accomplish MSEE project objectives using Phase I and Phase II test results, analysis and evaluation.

### Phase II Test Plan

Plan for tests during Phase II which will provide data needed for evaluation.

### System Operation Plan

Plan to operate MSEE by teams of utility and industry operators and obtain their feedback on the MSEE system.



## CONTENTS

Section 1	INTRODUCTION	1-1
	1.1 Background	1-1
	1.2 Objectives	1-2
Section 2	TRAINING AND OPERATING SESSIONS	2-1
Section 3	MSEE SYSTEM DESCRIPTION	3-1
	3.1 Collector Subsystem	3-4
	3.2 Master Control Subsystem	3-6
	3.3 Receiver Subsystem	3-11
	3.4 Thermal Storage Subsystem	3-22
	3.5 Steam Generation Subsystem	3-29
	3.6 Electric Power Generation Subsystem	3-38
	3.7 Heat Rejection and Feedwater Subsystem	3-46
	3.8 System Trips	3-53
Section 4	CONSOLE OPERATION	4-1
	4.1 EMCON Console Display Screen	4-1
	4.2 EMCON Console Keyboard	4-8
	4.3 Use of Console Displays	4-10
	4.3.1 Bringing a Point onto the Display	4-10
	4.3.2 Display of an Individually Entered Point	4-12
	4.3.3 Selecting a Point	4-12
	4.3.4 Clearing the Screen	4-13
	4.3.5 4 over 4 Display	4-14
	4.3.6 Single Loop Display	4-17
	4.3.7 Standard 22-line Display	4-18
	4.3.8 Graphic Displays	4-19
	4.4 Control	4-20
	4.4.1 Change Keys, Tuning Keys, Modify Keys	4-20
	4.4.2 Success/Error Messages	4-22
	4.4.3 Switch to Automatic Control	4-22
	4.4.4 Switch to Manual Control	4-23
	4.4.5 Setpoints	4-23
	4.4.6 Positional Output Commands	4-25
	4.4.7 Digital Output Commands	4-27

CONTENTS  
(Continued)

4.5	Miscellaneous Keys	4-28
4.5.1	PRINT Key	4-28
4.5.2	COPY Key	4-28
4.6	Bailey Network 90 Console	4-29
Section 5	TRAINING MATERIAL	5-1
5.1	Pre-operational Control Room Exercises	5-1
5.1.1	EMCON Console Introduction	5-1
5.1.2	Acurex Data System Familiarization	5-6
5.1.3	Receiver Subsystem Instrumentation and Control	5-7
5.1.4	Thermal Storage Subsystem Instrumentation and Control	5-9
5.1.5	SGS Instrumentation and Control	5-10
5.2	Operational Exercises	5-12
5.2.1	Receiver Cold Flow	5-12
5.2.2	Receiver Steady State Operation	5-14
5.2.3	Receiver Operation with Simulated Clouds	5-18
5.2.4	Thermal Storage Charging with Propane Heater	5-21
5.2.5	Steam Generator Steady State Operation	5-23
5.2.6	Operation of Full Electric Loop	5-25
5.2.7	System Steady State Operation	5-28
5.2.8	EPGS Steady State Performance Calculation	5-29

CONTENTS  
(Continued)

Section 6	MODES OF OPERATION AND TRANSITIONS	6-1
SECTION 7	OPERATING PROCEDURES	7-1
	7.1 Console Operating Procedures	7-1
	7.2 Receiver Operating Procedures	7-16
	7.3 Thermal Storage Operating Procedures	7-27
	7.4 Steam Generator Operating Procedures	7-39
	7.5 Electric Power Generation Operating Procedures	7-58
Section 8	EMCON GRAPHICS AND GROUPS	8-1

## FORWARD

This System Operation Plan is one of three documents that describe plans for Phase II of the MSEE Project. These documents are:

### MSEE Evaluation Plan

Plan to accomplish MSEE project objectives using Phase I and Phase II test results, analysis and evaluation.

### Phase II Test Plan

Plan for tests during Phase II which will provide data needed for evaluation.

### System Operation Plan

Plan to operate MSEE by teams of utility and industry operators and obtain their feedback on the MSEE system.

## CONTENTS

Section 1	INTRODUCTION	1-1
	1.1 Background	1-1
	1.2 Objectives	1-2
Section 2	TRAINING AND OPERATING SESSIONS	2-1
Section 3	MSEE SYSTEM DESCRIPTION	3-1
	3.1 Collector Subsystem	3-4
	3.2 Master Control Subsystem	3-6
	3.3 Receiver Subsystem	3-11
	3.4 Thermal Storage Subsystem	3-22
	3.5 Steam Generation Subsystem	3-29
	3.6 Electric Power Generation Subsystem	3-38
	3.7 Heat Rejection and Feedwater Subsystem	3-46
	3.8 System Trips	3-53
Section 4	CONSOLE OPERATION	4-1
	4.1 EMCON Console Display Screen	4-1
	4.2 EMCON Console Keyboard	4-8
	4.3 Use of Console Displays	4-10
	4.3.1 Bringing a Point onto the Display	4-10
	4.3.2 Display of an Individually Entered Point	4-12
	4.3.3 Selecting a Point	4-12
	4.3.4 Clearing the Screen	4-13
	4.3.5 4 over 4 Display	4-14
	4.3.6 Single Loop Display	4-17
	4.3.7 Standard 22-line Display	4-18
	4.3.8 Graphic Displays	4-19
	4.4 Control	4-20
	4.4.1 Change Keys, Tuning Keys, Modify Keys	4-20
	4.4.2 Success/Error Messages	4-22
	4.4.3 Switch to Automatic Control	4-22
	4.4.4 Switch to Manual Control	4-23
	4.4.5 Setpoints	4-23
	4.4.6 Positional Output Commands	4-25
	4.4.7 Digital Output Commands	4-27

CONTENTS  
(Continued)

4.5	Miscellaneous Keys	4-28
4.5.1	PRINT Key	4-28
4.5.2	COPY Key	4-28
4.6	Bailey Network 90 Console	4-29
Section 5	TRAINING MATERIAL	5-1
5.1	Pre-operational Control Room Exercises	5-1
5.1.1	EMCON Console Introduction	5-1
5.1.2	Acurex Data System Familiarization	5-6
5.1.3	Receiver Subsystem Instrumentation and Control	5-7
5.1.4	Thermal Storage Subsystem Instrumentation and Control	5-9
5.1.5	SGS Instrumentation and Control	5-10
5.2	Operational Exercises	5-12
5.2.1	Receiver Cold Flow	5-12
5.2.2	Receiver Steady State Operation	5-14
5.2.3	Receiver Operation with Simulated Clouds	5-18
5.2.4	Thermal Storage Charging with Propane Heater	5-21
5.2.5	Steam Generator Steady State Operation	5-23
5.2.6	Operation of Full Electric Loop	5-25
5.2.7	System Steady State Operation	5-28
5.2.8	EPGS Steady State Performance Calculation	5-29

CONTENTS  
(Continued)

Section 6	MODES OF OPERATION AND TRANSITIONS	6-1
SECTION 7	OPERATING PROCEDURES	7-1
	7.1 Console Operating Procedures	7-1
	7.2 Receiver Operating Procedures	7-16
	7.3 Thermal Storage Operating Procedures	7-27
	7.4 Steam Generator Operating Procedures	7-39
	7.5 Electric Power Generation Operating Procedures	7-58
Section 8	EMCON GRAPHICS AND GROUPS	8-1

## FORWARD

This System Operation Plan is one of three documents that describe plans for Phase II of the MSEE Project. These documents are:

### MSEE Evaluation Plan

Plan to accomplish MSEE project objectives using Phase I and Phase II test results, analysis and evaluation.

### Phase II Test Plan

Plan for tests during Phase II which will provide data needed for evaluation.

### System Operation Plan

Plan to operate MSEE by teams of utility and industry operators and obtain their feedback on the MSEE system.



## CONTENTS

Section 1	INTRODUCTION	1-1
	1.1 Background	1-1
	1.2 Objectives	1-2
Section 2	TRAINING AND OPERATING SESSIONS	2-1
Section 3	MSEE SYSTEM DESCRIPTION	3-1
	3.1 Collector Subsystem	3-4
	3.2 Master Control Subsystem	3-6
	3.3 Receiver Subsystem	3-11
	3.4 Thermal Storage Subsystem	3-22
	3.5 Steam Generation Subsystem	3-29
	3.6 Electric Power Generation Subsystem	3-38
	3.7 Heat Rejection and Feedwater Subsystem	3-46
	3.8 System Trips	3-53
Section 4	CONSOLE OPERATION	4-1
	4.1 EMCON Console Display Screen	4-1
	4.2 EMCON Console Keyboard	4-8
	4.3 Use of Console Displays	4-10
	4.3.1 Bringing a Point onto the Display	4-10
	4.3.2 Display of an Individually Entered Point	4-12
	4.3.3 Selecting a Point	4-12
	4.3.4 Clearing the Screen	4-13
	4.3.5 4 over 4 Display	4-14
	4.3.6 Single Loop Display	4-17
	4.3.7 Standard 22-line Display	4-18
	4.3.8 Graphic Displays	4-19
	4.4 Control	4-20
	4.4.1 Change Keys, Tuning Keys, Modify Keys	4-20
	4.4.2 Success/Error Messages	4-22
	4.4.3 Switch to Automatic Control	4-22
	4.4.4 Switch to Manual Control	4-23
	4.4.5 Setpoints	4-23
	4.4.6 Positional Output Commands	4-25
	4.4.7 Digital Output Commands	4-27

CONTENTS  
(Continued)

4.5	Miscellaneous Keys	4-28
4.5.1	PRINT Key	4-28
4.5.2	COPY Key	4-28
4.6	Bailey Network 90 Console	4-29
Section 5	TRAINING MATERIAL	5-1
5.1	Pre-operational Control Room Exercises	5-1
5.1.1	EMCON Console Introduction	5-1
5.1.2	Acurex Data System Familiarization	5-6
5.1.3	Receiver Subsystem Instrumentation and Control	5-7
5.1.4	Thermal Storage Subsystem Instrumentation and Control	5-9
5.1.5	SGS Instrumentation and Control	5-10
5.2	Operational Exercises	5-12
5.2.1	Receiver Cold Flow	5-12
5.2.2	Receiver Steady State Operation	5-14
5.2.3	Receiver Operation with Simulated Clouds	5-18
5.2.4	Thermal Storage Charging with Propane Heater	5-21
5.2.5	Steam Generator Steady State Operation	5-23
5.2.6	Operation of Full Electric Loop	5-25
5.2.7	System Steady State Operation	5-28
5.2.8	EPGS Steady State Performance Calculation	5-29

CONTENTS  
(Continued)

Section 6	MODES OF OPERATION AND TRANSITIONS	6-1
SECTION 7	OPERATING PROCEDURES	7-1
	7.1 Console Operating Procedures	7-1
	7.2 Receiver Operating Procedures	7-16
	7.3 Thermal Storage Operating Procedures	7-27
	7.4 Steam Generator Operating Procedures	7-39
	7.5 Electric Power Generation Operating Procedures	7-58
Section 8	EMCON GRAPHICS AND GROUPS	8-1



Section 1  
INTRODUCTION

1.1 BACKGROUND

Solar thermal central receiver systems have been under development since the early seventies. The first central receiver system in the United States (Solar One) uses water/steam as a heat transfer fluid in the receiver. Subsequent studies and test programs investigated molten salt, liquid sodium, and hot air as heat transfer fluids. They all possess certain advantages over water/steam, but many feel that molten nitrate salt is the most promising heat transfer fluid, particularly for utility-scale electric power plants with thermal storage.

A complete molten salt system experiment has been built at the Department of Energy (DOE) Central Receiver Test Facility (CRTF) located at Kirtland Air Force Base, Albuquerque, New Mexico. The CRTF heliostat field concentrates reflected solar energy onto a molten salt cooled solar receiver located on top of the 200-foot-tall CRTF test tower. Molten salt is pumped from a "warm" salt storage tank at ground level up the tower to the solar receiver where it is heated by absorbing solar energy and then returns to a "hot" salt storage tank at ground level. A hot salt pump delivers salt from the hot tank to a molten salt steam generator which produces steam to power a turbine/generator which feeds electricity into the local power grid.

This experiment is being conducted in two phases. The Phase I design, construction, installation, checkout, and verification effort has been completed. In Phase II, system characterization tests are being performed and the system will be operated and evaluated by utility and industry personnel. This document provides the data to be utilized by the utility and industry participants in their training and operation. The system may be run for an additional period in a potential third phase.

A consortium consisting of utilities, industries and the Electric Power Research Institute (EPRI), has helped construct and support operation of the experiment. The consortium is supplying half of the project's funding through either cash contributions or donations of in-kind engineering services. The other half is supplied by the DOE, through Sandia.

## 1.2 OBJECTIVES

The MSEE is designed as a first full-system experiment of future large-scale, central station power plants. The test and evaluation program is designed to provide data to be used in the design and operation of these commercial plants. This will be accomplished by a thorough characterization of the MSEE itself and by identifying features that should be changed in a commercial plant or its prototype. Operation of the MSEE by utility and industry personnel can make a significant contribution to this evaluation as well as provide familiarization with the operation of this type of solar power plant. Accordingly, the specific objectives of this operational phase are:

1. Demonstrate operation of a molten salt cooled central receiver solar power plant to participating utility and industry personnel. This also demonstrates power plant control by a distributed digital central system.
2. Obtain an evaluation by the participants of the MSEE design and operation and of the training methods employed in this program.

SECTION 2 TRAINING CLASS SCHEDULE

Section 2  
TRAINING AND OPERATING SESSIONS  
APS TEAM (SEPTEMBER 24 - OCTOBER 12, 1984)

Monday, September 24 -- Orientation and Master Control Subsystem

8:00 Introduction -- Conference Room  
9:00 CRTF Projects Review and Safety Briefing -- Conference Room  
9:30 Break  
9:45 MSEE System Overview -- Conference Room  
10:00 Tour of MSEE -- Field and Control Room  
11:30 Discussion and Questions -- Conference Room  
12:00 Master Control Subsystem -- Conference Room (Sections 3.2  
and 4)  
1:00 Console Operation -- Control Room (Sections 4 and 5.1.1)  
4:00 Complete

Tuesday, September 25 -- Receiver and Thermal Storage Subsystems (Sections  
3.3 and 3.4)

8:00 Subsystem Description -- Conference Room  
9:00 Tour of Receiver and Thermal Storage Subsystems -- Tower and  
Field  
10:00 Control Loops and Instrumentation -- Conference Room  
11:00 Operation, Alarms and Trips -- Conference Room  
12:00 Training - Receiver Loop Operation -- Conference Room  
(Section 7 and P&ID)  
Check Lists  
Procedures  
Console Instruction (individually in Control Room)  
(Sections 5.1.2, 5.1.3, and 5.1.4)  
4:00 Complete



Wednesday, September 26 -- Receiver Operations

8:00 Training - Receiver Loop Operation -- Conference Room  
Receiver Start-up Using Simulation -- Control Room (rotate  
groups)  
11:00 Test on Receiver Loop Start-up and Operation -- Conference  
Room  
12:00 Receiver Cold Flow -- Control Room (Section 5.2.1).  
4:00 Complete

Thursday, September 27 -- Receiver Operation

8:00 Receiver Steady State Operation (Section 5.2.2).  
4:00 Complete

Friday, September 28 -- Receiver Loop Operation

8:00 Receiver Cold Flow (Section 5.2.1) -- Control Room  
10:00 Receiver Operation with Simulated Clouds (Section 5.2.3) --  
Control Room  
4:00 Complete

Monday, October 1 -- Steam Generation Subsystem (Sections 3.5 and 3.7)

8:00 Subsystem Description -- Conference Room  
9:00 Tour of Steam Generator and HRFS Subsystems -- Field  
10:00 Control Loops and Instrumentation -- Conference Room  
11:00 Operations, Alarms and Trips -- Conference Room  
12:00 Training - Steam Generator Operation -- Conference Room  
(Section 7 and P&ID)  
Check Lists  
Procedures  
Console Instruction (individually in Control Room  
(Section 5.1.5)  
4:00 Complete

**Tuesday, October 2 -- Steam Generator Operation**

8:00 Training -- Steam Generator Operation -- Conference Room  
11:00 Test on Steam Generator Start-up and Operation -- Conference Room  
12:00 Steam Generation Operation (Section 5.2.5) -- Control Room  
4:00 Complete

**Wednesday, October 3 -- Charge Thermal Storage with Propane Heater, Operate Steam Generator**

8:00 Thermal Storage Charging with Propane Heater (Section 5.2.4)  
-- Control Room  
12:00 Steam Generator Operation (Section 5.2.5) -- Control Room  
4:00 Complete

**Thursday, October 4 -- Electric Power Generation Subsystem (Sections 3.6 and 3.7)**

8:00 Subsystem Description -- Conference Room  
9:00 Tour of EPGS and HRFS -- Field  
10:00 Control Loops and Instrumentation -- Conference Room  
11:00 Operations, Alarms and Trips -- Conference Room  
12:00 Training - EPGS Operation - Conference Room  
(Section 7 and P&ID)  
4:00 Complete

Friday, October 5 -- Operation of EPGS

- 8:00      Operation of Full Electric Loop (Section 5.2.6) -- Control Room and field  
Teams will rotate between Control Room and Turbine Room in A.M. and P.M.
- 4:00      Complete

Monday, October 8 -- System Operation

- 8:00      Discussion of System Operation -- Conference Room
- 10:00     System Steady State Operation (Section 5.2.7) -- Control Room and field  
Rotate groups between locations
- 4:00      Complete

Tuesday, October 9 -- System Operation

- 8:00      System Steady State Operation  
            (Section 5.2.7)  
EPGS Steady State Performance  
            (Section 5.2.8)  
Rotate groups between Control Room and field
- 4:00      Complete

Wednesday, October 10 -- System Operation

- 8:00      System Steady State Operation  
            (Section 5.2.7)  
EPGS Steady State Performance  
            (Section 5.2.8)  
Rotate groups between Control Room and field
- 4:00      Complete

Thursday, October 11-- System Operation and Debriefing

8:00 System Steady State Operation (Section 5.2.7) -- Control  
Room and field  
12:00 Debriefing -- Conference Room  
2:00 Briefing on Solar One  
4:00 Complete

Friday, October 12 -- Tour of Solar One  
System Operation  
Controls

Section 2  
TRAINING AND OPERATING SESSIONS  
PNM TEAM (SEPTEMBER 4 - 21, 1984)

Tuesday, September 4 -- Orientation and Master Control Subsystem

8:00	Introduction -- Conference Room
9:00	Safety Briefing -- Conference Room
9:30	Break
9:45	MSEE System Overview -- Conference Room
10:00	Tour of MSEE -- Field and Control Room
11:30	Discussion and Questions -- Conference Room
12:00	Master Control Subsystem -- Conference Room (Sections 3.2 and 4)
1:00	Console Operation -- Control Room (Sections 4 and 5.1.1)
4:00	Complete

Wednesday, September 5 -- Receiver and Thermal Storage Subsystems (Sections 3.3 and 3.4)

8:00	Subsystem Description -- Conference Room
9:00	Tour of Receiver and Thermal Storage Subsystems -- Tower and Field
10:00	Control Loops and Instrumentation -- Conference Room
11:00	Operation, Alarms and Trips -- Conference Room (Section 7 and P&ID) Check Lists Procedures Console Instruction (individually in Control Room) (Sections 5.1.2, 5.1.3, and 5.1.4)
4:00	Complete

Thursday, September 6 -- Receiver Operations

- 8:00 Training - Receiver Loop Operation -- Conference Room  
Receiver Start-up Using Simulation -- Control Room (rotate  
groups of two)
- 11:00 Test on Receiver Loop Start-up and Operation -- Conference  
Room
- 12:00 Receiver Cold Flow -- Control Room and Field (Section 5.2.1).  
Rotate groups of two in Control Room and two in field.
- 4:00 Complete

Friday, September 7 -- Receiver Operation

- 8:00 Receiver Steady State Operation (Section 5.2.2).  
Rotate groups of two in Control Room and two in field.
- 4:00 Complete

Monday, September 10 -- Steam Generation Subsystem (Sections 3.5 and 3.7)

- 8:00 Subsystem Description -- Conference Room
- 9:00 Tour of Steam Generator and HRFS Subsystems -- Field
- 10:00 Control Loops and Instrumentation -- Conference Room
- 11:00 Operations, Alarms and Trips -- Conference Room
- 12:00 Training - Steam Generator Operation -- Conference Room  
(Section 7 and P&ID)  
Check Lists  
Procedures  
Console Instruction (individually in Control Room)  
(Section 5.1.5)
- 4:00 Complete

Tuesday, September 11 -- Steam Generator Operation

8:00 Training -- Steam Generator Operation -- Conference Room  
11:00 Test on Steam Generator Start-up and Operation -- Conference Room  
12:00 Steam Generation Operation (Section 5.2.5) -- Control Room and Field  
One group of two in Control Room; other group of two in field  
4:00 Complete

Wednesday, September 12 -- Charge Thermal Storage with Propane Heater, Operate Steam Generator

8:00 Thermal Storage Charging with Propane Heater (Section 5.2.4) -- Control Room and Field  
12:00 Steam Generator Operation (Section 5.2.5) -- Control Room and field. Rotate groups from Tuesday P.M. assignments

Thursday, September 13 -- Receiver Loop Operation

8:00 Receiver Cold Flow (Section 5.2.1) -- Control Room and field  
12:00 Receiver Operation with Simulated Clouds (Section 5.2.3) -- Control Room and field  
4:00 Complete

Friday, September 14 -- Electric Power Generation Subsystem (Sections 3.6 and 3.7)

8:00 Subsystem Description -- Conference Room  
9:00 Tour of EPGS and HRFS -- Field  
10:00 Control Loops and Instrumentation -- Conference Room  
11:00 Operations, Alarms and Trips -- Conference Room  
12:00 Training - EPGS Operation - Conference Room  
(Section 7 and P&ID)  
4:00 Complete

Monday, September 17 -- Operation of EPGS

- 8:00 Operation of Full Electric Loop (Section 5.2.6) -- Control Room and field  
Team of two will rotate between Control Room and Turbine Room in A.M. and P.M.
- 4:00 Complete

Tuesday, September 18 -- System Operation

- 8:00 Discussion of System Operation -- Conference Room
- 10:00 System Steady State Operation (Section 5.2.7) -- Control Room and field  
Rotate groups of two between locations
- 4:00 Complete

Wednesday, September 19 -- System Operation

- 8:00 System Steady State Operation  
(Section 5.2.7)  
EPGS Steady State Performance  
(Section 5.2.8)  
Rotate groups of two between Control Room and field
- 4:00 Complete

Thursday, September 20 -- System Operation and Debriefing

- 8:00 System Steady State Operation (Section 5.2.7) -- Control Room and field
- 12:00 Debriefing -- Conference Room
- 4:00 Complete

Friday, September 21 -- Tour of Solar One System Operation Controls






Section 3  
MSEE SYSTEM DESCRIPTION

The MSEE system is shown as an artist's concept in Figure 3.1. It is designed to demonstrate the conversion of solar energy to electricity using molten salt and water/steam as the working fluids. The molten salt is the energy transfer medium from the receiver through thermal storage to the steam generation subsystem and water/steam is the energy transfer medium from the steam generation subsystem to the electric power generation subsystem. The system schematic is shown in Figure 3.2. The receiver, located at the top of the CRTF tower, receives concentrated solar energy from the collector field. Molten salt from the cold storage tank, located at ground level, is pumped up the tower piping and through the receiver. In the experiment, cold salt is nominally defined to have a temperature of 306°C (580°F). The salt is heated to 1000° in the receiver, flows through a downcomer, and is throttled into the hot salt storage tank. Hot salt is defined to have a nominal temperature of 1000°. Hot salt from storage is pumped through the steam generator superheater and evaporator, and is returned to the cold storage tank. An additional flow of cold salt is injected in the salt line between the superheater and evaporator to reduce the salt temperature entering the evaporator; this is to allow the use of low alloy steel in the evaporator. Main steam from the steam generator is used to drive a conventional steam turbine-generator. There are two principal advantages of this molten salt receiver system over a water/steam receiver system: the steam generator and turbine are decoupled from the receiver by the thermal storage subsystem; and, molten salt from the receiver is used directly as the thermal storage fluid, thus providing an inexpensive source of thermal storage and a constant temperature heat source for the steam generator.

The system is divided into the following subsystems:

- a) Collector (CS)
- b) Master Control (MCS)
- c) Receiver (RS)
- d) Thermal Storage (TSS)
- e) Steam Generation (SGS)
- f) Heat Rejection and Feedwater (HRFS)
- g) Electric Power Generation (EPGS)

FIGURE 3.1 Artists Concept






Figure 3.2. MSEE Flow Schematic

A tabulation of data describing the MSEE system is given on Table 3.1. A more detailed description of the MSEE subsystems is contained in the following subsections.

### 3.1 COLLECTOR SUBSYSTEM

The collector subsystem redirects, concentrates, and focuses solar radiation onto the tower-mounted receiver. The subsystem, which is already in place at the CRTF, consists of 221 two-axis tracking heliostats located north of the receiver tower, and its control system. Under optimum insolation and heliostat conditions, the heliostat field can concentrate approximately  $5 \text{ MW}_t$  onto the receiver.

Each heliostat has 25 individual mirror facets totaling  $37.2 \text{ m}^2$  ( $400 \text{ ft}^2$ ) of reflective surface. The facets are mounted on a structure and individually adjusted to provide a concentration ratio of 25 to 1 on the receiver. The structure has motor-driven azimuth and elevation gimbals, which allow it to track the sun during the day.

The heliostats are operated from the control room by the CRTF collector control system. (The CRTF collector control system is separate from the experiment master control subsystem.) The CRTF collector control system analyzes heliostat operating commands from a number of programmed test sequences or from the facility heliostat operator. Control signals are distributed to the heliostats through four heliostat array controllers and four heliostat interface modules. Each heliostat receives azimuth and elevation pointing information once every second and responds with its own status. Commands and data transmitted to the individual heliostats are received and executed by the heliostat control electronics. The electronics keep the drive motor power at the proper level until the gimbal axis encoders indicate that the desired position has been reached.

Table 3.1  
MSEE Data

- Location -- CRTF; on Kirtland Air Force Base, Albuquerque, NM
- Heliostat Field -- Existing field of 221 heliostats each with 400 ft<sup>2</sup> of mirror surface.
- Tower -- Existing concrete tower, 200 ft. high with internal lifting module
- Master control -- EMCON D-2 distributed digital control system with central consoles; separate equipment protection system.
- Receiver -- Refurbished from previous Subsystem Research Experiment.
- o Rating: 5 MW<sub>th</sub>
  - o Salt temperatures: in - 590°F; out - 1000°F (1050°F with propane heater)
  - o Configuration: cavity with door
  - o Absorber: single panel of 3/4 in Incoloy 800 tubes (18 passes, 16 tubes per pass)
  - o Peak flux: 630 kW/m<sup>2</sup> (200,000 Btu/hr - ft<sup>2</sup>)
- Thermal Storage -- Existing from previous Subsystem Research Experiment
- o Rating: 5.8 MW<sub>th</sub> Hr when operating between 590°F and 1000°F
  - o Type: 2-tank
    - Hot tank, internal insulation
    - Cold tank, external insulation
- Steam Generator -- Supplied by Babcock and Wilcox
- o Type: Forced recirculation
  - o 2 units: evaporator and superheater (both U-tube, U-shell) with steam drum separator
  - o Rating: 11,000 lb/hr of steam at 940°F and 1100 psi (3.13 MW<sub>th</sub>)
  - o Prototypical of commercial design
- Turbine Generator -- GE rebuilt unit
- o Marine turbine
  - o 750 kW<sub>e</sub> rating (500 kW<sub>e</sub> under nominal operating conditions)
- Heat Rejection and Feedwater System -- existing at CRTF
- o Feedwater treatment only
  - o 20,000 gallon demineralized water storage
  - o Dry cooling, 7 MW<sub>th</sub> capacity
  - o Spray water heat exchanger to reject heat when turbine not in use or tripped off line

## 3.2 MASTER CONTROL SUBSYSTEM

The master control subsystem (Figure 3.3) consists of an EMCON-D2 for system control and a equipment protection system. A Bailey network 90-system is used to directly control the SGS. Commands and set points are provided by the EMCON master control subsystem to the Network 90 for SGS operation and control. The equipment protection system is an independent hardwired relay shutdown system. These relay trip devices will shut down the receiver or the power generation ends of the MSEE when critical parameters reach preset limit values. These relay units are independent of the EMCON and network 90 control systems. Additionally, an Accurex Data Logger is used to collect and display all the temperature measurements relating to the heat tracing and data instrumentation.

### 3.2.1 EMCON System

The EMCON-D2 is a distributed digital control system consisting of two operator consoles, a host computer with its peripheral hardware, a communication control module, and three process control modules distributed among the subsystems. Two EMCON-D2 operator consoles are located in the CRTF main control room. The host computer is an existing DEC PDP 11/34 unit located in the control room. This computer links the operator with the process control modules, and analyzes data from the control modules for presentation on the operator consoles. The peripheral equipment includes two disk drives, an alarm system, and a data analysis system.

A communication control module links the host computer with the three field-located, process control modules. Each process control module is a small digital computer capable of monitoring a number of instrumentation points, and responding with a number of process control signals. Communications between the control modules and host computer are primarily limited to direct operator commands from the console and critical operating information from the subsystems for console display. This distributed control system reduces the number of instrumentation and control links between the subsystems and control room.

The process control module consists of a digital computer control unit, a multiplexer, an analog-to-digital converter, and a digital-to-analog converter. Analog signals from the process instrumentation are converted to

**DATA ACQUISITION**  
HP 2645A

**DATA DISPLAY SCREENS**  
HP 2645A

**MSEE OPERATION CONTROL**

**HELIOSTAT CONTROL**

**HELIOSTAT OPERATOR CONSOLE**

**ACUREX HEAT TRACE MONITOR**




Figure 3.3 Master Control Subsystem

3-7



digital signals, selected in rotation by the multiplexer, and analyzed by the control unit. The module responds with an appropriate digital control signal which is passed through the multiplexer and sent to the appropriate controller. Each process control module is capable of monitoring 30 analog signals per second, monitoring 95 thermocouples, generating 20 analog control signals, and controlling over 100 on-off switches.

One process control module (PCM 1), located below the receiver in the tower elevator, is dedicated to the control of the receiver. A second module, (PCM 2) located at the base of the tower, controls the heat rejection and electric power generation subsystem. The third module, (PCM 3), located in the control building adjacent to the salt storage tanks, is used to control the thermal storage subsystem and to command the Network 90 controlled steam generation subsystem.

The receiver subsystem PCM will modulate the salt flow rate to the receiver to maintain, as closely as possible, a constant outlet temperature of 1000°F. Individual thermocouples are located on the receiver to measure intermediate salt temperatures. From this information, the control module estimates the flux on the receiver, and feed-forward a signal to the salt control valves at the receiver inlet. The control module also controls the receiver start-up and shutdown purge and drain valves.

Control of the thermal storage subsystem involves the operation of the two salt downcomer flow control valves, cold salt pumps, salt storage tanks and piping heat tracing, and the propane-fired salt heater. The downcomer throttling valves are controlled by the receiver control system to maintain a constant level in the receiver hot surge tank. Salt equipment heat trace temperatures are monitored continuously by the Acurex Data Logger. The propane-fired salt heater is operated intermittently, under manual control, during subsystem checkouts.

Automatic control of the heat rejection and electric power generation subsystem involves the control of the steam and condensate flows to the deaerator, steam flow to the feedwater heater, and the operation of the cooling water, spray water condensate, and feedwater pumps. The EPGS condenser

temperature, level and pressure are monitored by the master control subsystem. The deaerator temperature is maintained by controlling the steam flow from the main steam header. The final feedwater temperature is maintained by controlling the main steam flow to the feedwater heater.

Automatic control of the steam generation subsystem primarily involves the control of steam pressure, steam temperature, drum water level, and the evaporator salt inlet temperature through the network 90 control system. The water level in the drum is controlled by modulating the control valve downstream of the feedwater pump. Control of the main steam pressure is accomplished by modulating the salt flow control valve downstream of the evaporator. Steam temperature is controlled using an attemperator to mix steam from the steam drum with the output of the superheater. The evaporator salt inlet temperature is controlled by monitoring the inlet salt temperature, and modulating the cold salt control valve at the mixing tee between the superheater and evaporator.

### 3.2.2 Network 90 System

The Bailey Network 90 Control System consists of two units, one process control unit (PCU) and one operation interface unit (OIU).

The PCU architecture is based on two key modules, the Controller Module (COM) and the Logic Master. Together, these modules provide a mix of both modulating and sequential control functions including: base, cascade, or ratio PID control, high/low and rate limiters, engineering units conversion, general function generator, square root, summation, multiplication, lead/lag, and transfer select, or, and, not, time delay, and several others. The controller module can service up to four analog and three digital inputs and two analog and four digital outputs. The COM also provides A/D and D/A conversion, alarm limit checking (absolute and deviation) and notification, point quality checking and interlocking.

The Operator Interface Unit (OIU) provides the high level operator interface for the Network 90 system. The OIU consists of a color CRT-based table-top console, with functional keyboard, mass storage device, and console driver electronics.

In operation, the unit performs the system information display and control requirements. The OIU console includes a CRT keyboard and pushbutton hardware for process overview, alarm indicating, loop control, trending, tuning and configuration functions.

The OIU uses microprocessor, memory and I/O modules to support system functions. It furnishes monitoring, supervisory, recording and display capability at centralized or distributed locations, along with engineering functions.

### 3.2.3 Data Acquisition

The DAS utilizes both the EMCON-D2 and an HP-1000. EMCON collects the data and HP-1000 stores and displays data. Data collected by the EMCON system is transmitted to the HP-1000 system on a terminal-to-terminal data link. The tag list for the data to be collected is in a file of 180 tags, which are divided into 6 groups of 30 tags. One group of 30 is transmitted every 10 seconds, giving a total update rate of once a minute. The data are then time tagged with day of the year, hour, minute, second, millisecond. Then the data are stored in a data file and/or displayed on one of six CRTs in a graphical form. Also, the data are transmitted in integer format, not floating point, but they are in engineering units. The data files are divided into eight-hour blocks, so if a test runs longer than eight hours, another eight-hour block is assigned to that test's file. Normally an 8-hour data block is stored in 19 tracks out of a maximum usable 1000 tracks.

The live data can be displayed on the 6 CRTs with 3 tags per screen, a time scale of 3 hours 20 minutes, and a Y-scale displayed of the first tag's display range. The other two tags are displayed using their respective ranges, but the scales are not shown on the plot. When the plot is full the plot scrolls left dropping the oldest 1/4 of the time scale data. This leaves 1/4 of the plot blank for new data. These plots can have hard copies made, but not automatically. The print is done by manual switch selection of each screen and a copy page switch.

Recovery of stored data can be done whenever live data files are not being made. These plots have a slightly different format, three being a maximum of five tags per plot, and the Y scale shown is that of the last tags range. These plots are not displayed on a CRT, but directly generated on the printer/plotter.

### 3.3 RECEIVER SUBSYSTEM

The receiver subsystem (Figure 3.4) captures the insolation redirected from the heliostat field and converts it to thermal energy in the molten salt. The subsystem consists of the receiver absorber panel, cavity enclosure with one vertical aperture door, insulation, heat tracing, cold surge tank, booster pump, hot surge tank, overflow tank, instrumentation, and control valves. The receiver is located at the top of the CRTF tower.

The receiver was tested in a previous subsystem research experiment. Since the initial experiment, the receiver has been refurbished. This refurbishment included instrumentation and control system modifications, minor structural and piping changes, and the replacement of the two original horizontal cavity doors with one vertical aperture door.

The receiver absorber is a single panel with 18 vertical passes having 16 tubes per pass. The tubes are Incoloy 800 with 19 mm (0.75 in.) outside diameter. Purge and drain valves are provided for each pair of passes.

The receiver surge tanks are designed to dampen changes in the salt flow rate and to maintain salt flow through the receiver in the event of a cold salt pump outage. The cold surge tank is pressurized with facility-supplied instrument air to supply the necessary head to force the salt through the receiver in the event of a pump outage, and to provide a surge volume within the tank. The hot surge tank operates at atmospheric pressure, and is vented to an adjacent overflow tank in the event of a control problem in the salt downcomer throttle valve.

The cold salt booster pump takes its suction from the discharge of the cold salt pump and provides the necessary head for the salt as it travels up the tower and through the receiver.

The cold salt line to the receiver starts at the booster pump, rises to the top of the hot storage tank, traverses the distance from the storage tanks to the receiver tower on an elevated pipe bridge, enters the tower, and runs up the east side of the tower in an existing pipe chase to the receiver. The hot salt line leaves the hot surge tank and traverses to the pipe chase. The hot salt downcomer carries the salt to the level of the pipe bridge. The hot salt line traverses the bridge, ending in a control valve which throttles the flow

to the hot storage tank. The salt piping is inclined between the storage tanks and the tower to ensure that the piping system will completely drain. The salt piping is electrically heat traced and insulated with calcium silicate and aluminum sheathing.

The receiver components are listed on Table 3.2; valves are described on Table 3.3; instrumentation is listed on Table 3.4; and control loops are described on Table 3.5.

3-13




Figure 3.4. Receiver Subsystem

Table 3.2  
Receiver Subsystem Components

Component	Description	Function	Nominal Operating Condition
Receiver	<ul style="list-style-type: none"> <li>- 18 ft wide x 13 ft high panel</li> <li>- 18 serpentine passes Incoloy 800 tubes</li> <li>- 16 tubes per pass</li> <li>- 3/4 in. dia. tubes</li> </ul>	<ul style="list-style-type: none"> <li>- Heat molten salt with solar energy from heliostat field</li> </ul>	<ul style="list-style-type: none"> <li>- 590°F inlet salt</li> <li>- 1050°F outlet salt</li> <li>- 96,867 lb/hr</li> <li>- 5 MW rating</li> </ul>
Cold salt booster sump	<ul style="list-style-type: none"> <li>- Carbon steel cylindrical tank</li> </ul>	<ul style="list-style-type: none"> <li>- Reservoir for cold salt pump</li> </ul>	<ul style="list-style-type: none"> <li>- 590°F salt</li> <li>- Atmospheric pressure</li> </ul>
Cold salt booster pump	<ul style="list-style-type: none"> <li>- Vertical cantilever type</li> </ul>	<ul style="list-style-type: none"> <li>- Supply additional head to outlet of cold salt pump to provide salt circulation through receiver</li> </ul>	<ul style="list-style-type: none"> <li>- 590°F salt</li> <li>- 96,867 lb/hr</li> </ul>
Cold surge tank	<ul style="list-style-type: none"> <li>- Carbon steel cylindrical tank</li> <li>- 3 ft. dia.</li> <li>- 7 ft. high</li> </ul>	<ul style="list-style-type: none"> <li>- Dampen changes in salt flow rate</li> <li>- Provide emergency salt flow through receiver until solar flux can be removed in the event of pump outage</li> </ul>	<ul style="list-style-type: none"> <li>- Pressurized to 125 psi</li> </ul>
Hot surge tank	<ul style="list-style-type: none"> <li>- Stainless steel cylindrical tank</li> <li>- 2 ft. dia.</li> <li>- 7 ft. high</li> </ul>	<ul style="list-style-type: none"> <li>- Dampen changes in salt flow rate</li> </ul>	<ul style="list-style-type: none"> <li>- Atmospheric pressure</li> </ul>

Table 3.3

## RECEIVER SUBSYSTEM REMOTE OPERATED VALVES

VALVE	MANUFACTURER	SIZE	TYPE	FAIL POSITION	FUNCTION	LOCATION
FCV-101 FCV-102	Valtek	2"	CV	FO	Receiver Flow Control	Near Receiver Lower West Corner
FCV-151	Valtek	2"	CV	FC	Receiver Fill Control Cold Surge Level Control	Above Hot Tank
FCV-161	Valtek	2"	CV	FO	Hot Surge Tank Level Control	Above Hot Tank
FCV-162	Valtek	2"	CV	FC	Hot Surge Tank Level Control (Receiver)	Above Hot Tank
FCV-180 thru FCV-189	Kieley-Mueller	1 1/2"	SV	FC	Receiver Fill and Drain	Below Receiver
FCV-190 thru FCV-198	Kieley-Mueller	1 1/2"	SV	FC	Receiver Purge	Above Receiver
FCV-199	Kieley-Mueller	2"	SV ↑ <i>shutoff valve (also called isolation valve)</i>	FC	Allow Downcomer Backflow During Receiver Fill and Permit Drainage to Cold Storage Tank During Shutdown	Above Hot Tank

CV - Control Valve  
SV - Shutoff Valve  
FO - Fail Open  
FC - Fail Close



Table 3.4

## Receiver Subsystem Instrumentation

Identifier	Description	Control Module	Display Range	Alarm Levels		Dimension	Sampling Period (sec)
				High	Low		
PT-180	Boost Pump Discharge pressure - goes to 310 psi	PCM 3	0-400	350	275	PSI	2
TE-180	Bearing temp not measured at 100% works	PCM 3	0-500	190		°F	10
TE-181	Sump vent temp normally 200-220°	PCM 3	0-1200	350		°F	10
LT-161	Hot surge tank Level normal operation is 20", during	PCM 3	0-100	70	15	inch	2
TE-183	Salt temp normally 1050°F during operation	PCM 1	0-1200	1070	500	°F	10
TE-184	Vent temp normally 100-1150°F	PCM 1	0-1200	400		°F	10
LT-151	Cold surge tank Level normally 30-40" during normal operation	PCM 1	0-100	90	10	inch	10
TE-182	Salt temp	PCM 1	0-1200	750	500	°F	10
PT-182	Pressure normally 150 PSI	PCM 1	0-200	180	10	PSI	10
TE-161	Downcomer outlet temp	PCM 3	0-1200	1070	500	°F	2
Sun	Solar insolation - not in a 90°F, represents power level at 1000  Not surge tank is vented to atmosphere, therefore it is not pressurized	PCM 3	0-1000			W/M <sup>2</sup>	5

Table 3.4

## Receiver Subsystem Instrumentation

Identifier	Description	Control Module	Display Range	Alarm Levels		Dimension	Sampling Period (sec)
				High	Low		
	Receiver						
PT-181	Inlet pressure <i>-directly related to FT-101 (8.81319, FT-101 should be 30)</i>	PCM 1	0-200	125	10	PSI	10
FT-101	Salt flow rate	PCM 1	0-100	100		KLB/hr	
TE-101	Salt inlet temp <i>FT-101 being in qt now, when called to open, see calculated valve</i>	PCM 1	0-1200	650	500	°F	2
TE-102	Salt outlet temp	PCM 1	0-1200	1060	500	°F	2
TE-103	Back tube-pass #1 outlet	PCM 1	0-1200	640	500	°F	2
TE-104	Back tube-pass #2 outlet	PCM 1	0-1200	665	500	°F	2
TE-105	Back tube-pass #3 outlet	PCM 1	0-1200	690	500	°F	2
TE-106	Back tube-pass #4 outlet	PCM 1	0-1200	720	500	°F	2
TE-107	Back tube-pass #5 outlet	PCM 1	0-1200	750	500	°F	2
TE-108	Back tube-pass #6 outlet	PCM 1	0-1200	780	500	°F	2
TE-109	Back tube-pass #7 outlet	PCM 1	0-1200	810	500	°F	2
TE-110	Back tube-pass #8 outlet	PCM 1	0-1200	835	500	°F	2
TE-111	Back tube-pass #9 outlet	PCM 1	0-1200	865	500	°F	2
TE-112	Back tube-pass #10 outlet	PCM 1	0-1200	890	500	°F	2
TE-113	Back tube-pass #11 outlet	PCM 1	0-1200	920	500	°F	2

Table 3.4  
Receiver Subsystem Instrumentation

Identifier	Description	Control Module	Display Range	Alarm Levels		Dimension	Sampling Period (sec)
				High	Low		
	Receiver (cont.)						
TE-114	Back tube-pass #11 outlet	PCM 1	0-1200	950	500	°F	2
TE-115	Back tube-pass #12 outlet	PCM 1	0-1200	975	500	°F	2
TE-116	Back tube-pass #13 outlet	PCM 1	0-1200	990	500	°F	2
TE-117	Back tube-pass #14 outlet	PCM 1	0-1200	1010	500	°F	2
TE-118	Back tube-pass #15 outlet	PCM 1	0-1200	1030	500	°F	2
3-18 TE-119	Back tube-pass #16 outlet	PCM 1	0-1200	1050	500	°F	2
TE-120	Back tube-pass #17 outlet	PCM 1	0-1200	1070	500	°F	2
TE-131	Back tube-pass #1 upper	PCM 1	0-1200	645	500	°F	10
TE-132	Back tube-pass #5 upper	PCM 1	0-1200	745	500	°F	10
TE-133	Back tube-pass #8 upper	PCM 1	0-1200	815	500	°F	10
TE-134	Back tube-pass #11 upper	PCM 1	0-1200	915	500	°F	10
TE-135	Back tube-pass #14 upper	PCM 1	0-1200	980	500	°F	10
TE-136	Back tube-pass #17 upper	PCM 1	0-1200	1045	500	°F	10
TE-137	Back tube-pass #2 middle	PCM 1	0-1200	680	500	°F	10

Table 3.4

## Receiver Subsystem Instrumentation

Identifier	Description	Control Module	Display Range	Alarm Levels		Dimension	Sampling Period (sec)
				High	Low		
	Receiver (cont.)						
TE-138	Back tube-pass #6 middle	PCM 1	0-1200	735	500	°F	10
TE-139	Back tube-pass #8 middle	PCM 1	0-1200	825	500	°F	10
TE-140	Back tube-pass #11 middle	PCM 1	0-1200	905	500	°F	10
TE-141	Back tube-pass #14 middle	PCM 1	0-1200	990	500	°F	10
TE-142	Back tube-pass #17 middle	PCM 1	0-1200	1045	500	°F	10
TE-143	Back tube-pass #1 bottom	PCM 1	0-1200	660	500	°F	10
TE-144	Back tube-pass #5 bottom	PCM 1	0-1200	725	500	°F	10
TE-145	Back tube-pass #8 bottom	PCM 1	0-1200	830	500	°F	10
TE-146	Back tube-pass #11 bottom	PCM 1	0-1200	895	500	°F	10
TE-147	Back tube-pass #14 bottom	PCM 1	0-1200	985	500	°F	10
TE-148	Back tube-pass #17 bottom	PCM 1	0-1200	1035	500	°F	10
TE-185	Header-pass #2 outlet	PCM 1	0-1200	665	500	°F	10
TE-186	Header-pass #3 outlet	PCM 1	0-1200	690	500	°F	10

Table 3.4  
Receiver Subsystem Instrumentation

Identifier	Description	Control Module	Display Range	Alarm Levels		Dimension	Sampling Period (sec)
				High	Low		
	Receiver (cont.)						
TE-187	Header-pass #4 outlet	PCM 1	0-1200	720	500	°F	10
TE-188	Header-pass #5 outlet	PCM 1	0-1200	750	500	°F	10
TE-189	Header-pass #6 outlet	PCM 1	0-1200	780	500	°F	10
TE-190	Header-pass #7 outlet	PCM 1	0-1200	810	500	°F	10
TE-191	Header-pass #8 outlet	PCM 1	0-1200	835	500	°F	10
TE-192	Header-pass #9 outlet	PCM 1	0-1200	865	500	°F	10
TE-193	Header-pass #12 outlet	PCM 1	0-1200	950	500	°F	10
TE-194	Header-pass #13 outlet	PCM 1	0-1200	975	500	°F	10
TE-195	Header-pass #14 outlet	PCM 1	0-1200	990	500	°F	10
TE-196	Header-pass #15 outlet	PCM 1	0-1200	1010	500	°F	10
TE-197	Header-pass #16 outlet	PCM 1	0-1200	1030	500	°F	10
TE-198	Header-pass #17 outlet	PCM 1	0-1200	1050	500	°F	10

3-20

Table 3.5  
Receiver Subsystem Control Loops

Controlled Variable	Mode	Set Point	Controller Inputs	Controller Output
Receiver salt flow	Constant flow (start-up & shutdown with receiver control algorithm off scan Constant Outlet Temperature (Receiver control algorithm on))	30 KLB/hr FD-101  1000°F SP. SALT	Flow set point (FD-101) Measured flow (FT-101)  Temperature set point (SP. SALT) Outlet temperature (TE-102) Inlet temperature (TE-101) Salt flow (FT-101) Receiver back tube temperatures (TE-103 thru TE-120)	FCV-101/102 position  FCV-101/102 position
Hot surge tank level	Operation	20 in FCV-161 FCV-162	Surge tank level (LT-161) Level set point	FCV-161 or FCV-162 position (selection based on salt temperature)
Receiving storage tank selection	Operation	750°F	Downcomer salt temperature (TE-161)	TE-161 < 750°F Cold storage tank selected  TE-161 > 750°F Hot storage tank selected
Cold surge tank level	Operation	~85" LT-151	Cold surge tank level (LT-151) Level set point	FCV-151 position

3-21

when TE161 reaches 750°F control goes from FCV161 & FCV162 to only FCV161 (FCV162 closes because you want the salt to go into hot storage tank)

FCV151 is in cascade with LT151

### 3.4 THERMAL STORAGE SUBSYSTEM

The thermal storage subsystem provides a cold salt source for the receiver for daytime operation, and a hot salt source for the steam generator for day and early evening operation. The TSS can also furnish a source of thermal energy for overnight freeze protection of the receiver, steam generator, and salt piping and for early morning plant start-up. The subsystem includes the hot and cold salt storage tanks, propane-fired salt heater, cold salt pump and cold salt sump. The subsystem schematic is shown on Figure 3.15. Major components are described on Table 3.6; valves are listed on Table 3.7; instrumentation is described on Table 3.8; and control loops are given on Table 3.9.

The salt pump is of a vertical cantilever design. The impeller and casing are suspended below the liquid level in a sump; the bearings are located above the liquid level and do not contact the salt.

The hot salt tank employs a unique design. To allow the use of carbon steel in the structural portions of the tank, an internal refractory insulation is used to limit the temperature of the walls, roof, and floor. A waffled Incoloy liner separates the salt and the internal insulation, and the tank foundation is cooled with circulating water to limit the floor temperature. The outside of the tank is insulated in the conventional manner with calcium silicate and aluminum sheathing. The cold salt tank is similar in design to the hot tank except that it does not require the internal insulation and liner due to its lower operating temperature.




Figure 3-5. Thermal Storage Subsystem Schematic



Table 3.6  
Thermal Storage Subsystem Components

Component	Description	Function	Nominal Operating Condition
Cold salt storage tank	<ul style="list-style-type: none"> <li>- Carbon steel cylindrical tank</li> <li>- 12.3 ft. dia.</li> <li>- 12.3 ft. high</li> <li>- 15 in fibrous external insulation</li> </ul>	<ul style="list-style-type: none"> <li>- Cold salt storage</li> </ul>	<ul style="list-style-type: none"> <li>- 590°F salt</li> </ul>
Hot salt storage tank	<ul style="list-style-type: none"> <li>- Carbon steel cylindrical shell</li> <li>- 12.3 ft. dia. stainless steel liner</li> <li>- 23.6 ft. high</li> <li>- 13-1/2 in. insulating firebrick between shell and liner</li> <li>- 2 in. fibrous external insulation</li> </ul>	<ul style="list-style-type: none"> <li>- Hot salt storage</li> </ul>	<ul style="list-style-type: none"> <li>- 1050°F salt</li> <li>- Approx. 7 MW<sub>t</sub> hr storage capacity</li> </ul>
Cold salt sump	<ul style="list-style-type: none"> <li>- Carbon steel cylindrical tank</li> <li>- 59 in. dia.</li> <li>- 66 in. deep</li> </ul>	<ul style="list-style-type: none"> <li>- Pump reservoir</li> </ul>	<ul style="list-style-type: none"> <li>- 590°F salt</li> <li>- Atmospheric pressure</li> </ul>
Cold salt pump	<ul style="list-style-type: none"> <li>- Vertical cantilever type</li> <li>- 60 H.P. driver</li> </ul>	<ul style="list-style-type: none"> <li>- Pump salt from cold storage tank to cold salt booster pump, SGS, or propane heater</li> </ul>	<ul style="list-style-type: none"> <li>- 590°F salt</li> <li>- 96,867 lb/hr</li> </ul>

3-24

Table 3.6  
Thermal Storage Subsystem Components - 2

Component	Description	Function	Nominal Operating Condition
Hot salt sump	<ul style="list-style-type: none"> <li>- Stainless steel cylindrical tank</li> <li>- 48 in. dia.</li> <li>- 49 in. deep</li> </ul>	<ul style="list-style-type: none"> <li>- Reservoir for hot salt pump</li> </ul>	<ul style="list-style-type: none"> <li>- 1050°F salt</li> <li>- Atmospheric pressure</li> </ul>
Hot salt pump	<ul style="list-style-type: none"> <li>- Vertical cantilever type</li> <li>- 7-1/2 HP driver</li> </ul>	<ul style="list-style-type: none"> <li>- Provide hot salt circulation through STS</li> </ul>	<ul style="list-style-type: none"> <li>- 1050°F salt</li> <li>- 64,680 lb/hr</li> </ul>
Propane heater	<ul style="list-style-type: none"> <li>- 3 MW propane fired heater</li> <li>- 9 ft. dia. shell</li> <li>- 24 ft. high</li> <li>- One stainless steel heating coil, 2.12 in. dia., 1640 ft. long</li> </ul>	<ul style="list-style-type: none"> <li>- Provide auxiliary salt heating capability</li> </ul>	<ul style="list-style-type: none"> <li>- 59,900 lb/hr salt</li> <li>- 590°F inlet</li> <li>- 1050°F outlet</li> </ul>

3-25

Table 3.7

## THERMAL STORAGE SUBSYSTEM REMOTE OPERATED VALVES

VALVE	MANUFACTURER	SIZE	TYPE	FAIL POSITION	FUNCTION	LOCATION
FCV-201	Valtek	3"	CV	FC	Cold Sump Level Control	Cold Storage Tank Base South Side
FCV-211	Kieley-Mueller	3"	SV	FC	Cold Sump Isolation	Pump House North Side West End
FCV-221	Valtek	3"	CV	FC	Hot Sump Level Control	Hot Storage Tank Southwest Side
FCV-231	Kieley-Mueller	3"	SV	FC	Hot Sump Isolation	Outside Pumhouse Northeast Corner
FCV-241	Valtek	2"	CV	FC	Propane Heater Flow Control	Line to Propane Heater East of FCV-231
FCV-242	Valtek	1 1/2"	SV	FC	Propane Heater Isolation	Top of Hot Tank

Table 3.8  
Thermal Storage Subsystem Instrumentation

Identifier	Description	Control Module	Display Range	Alarm Levels		Dimension	Sampling Period (sec)
				High	Low		
	Cold Storage Tank						
LT-281	Level	PCM 3	0-150	134	15	inch	10
TE-281	Lower temp	PCM 3	0-1200	700	500	°F	10
TE-282	Middle temp	PCM 3	0-1200	700	500	°F	10
TE-283	Upper temp	PCM 3	0-1200	700	500	°F	10
	Hot storage tank						
LT-291	Level	PCM 3	0-200	190	10	inch	10
TE-291	Lower temp	PCM 3	0-1200	1070	500	°F	10
TE-292	Middle temp	PCM 3	0-1200	1070	500	°F	10
TE-293	Upper temp	PCM 3	0-1200	1070	500	°F	10
	Cold salt pump						
LT-201	Sump level	PCM 3	0-60	60	15	inch	2
TE-286	Bearing temp	PCM 3	0-500	190		°F	10
TE-211	Vent temp	PCM 3	0-1200	400		°F	2
	Hot Salt Pump						
LT-221	Sump level	PCM 3	0-48	41	15	inch	2
TE-231	Vent temp	PCM 3	0-1200	400		°F	2

Table 3.9

## Thermal Storage Subsystem Control Loops

Controlled Variable	Mode	Set Point	Controller Inputs	Controller Output
Cold sump level	Operation	23 in FCV-201 (45 in fill)	Sump level (LT-201) Level set point	FCV-201 position - Flow from cold storage tank
Hot sump level	Operation	20 in FCV-221	Sump level (LT-221) Level set point	FCV-221 position - Flow from hot storage tank

### 3.5 STEAM GENERATION SUBSYSTEM

The steam generation subsystem transfers sensible heat from the molten salt to produce superheated steam for the turbine-generator. The subsystem schematic is shown on Figure 3.6. The subsystem includes an evaporator, steam drum, boiler recirculation pump, superheater, and attemperator.

The evaporator and superheater are U-tubes, U-shell heat exchangers, with low pressure salt on the shell side and high-pressure water and steam on the tube side. This shell and tube configuration has been selected to minimize thermal stresses, due to differential expansion, in the tubes and tubesheets.

A conventional steam drum, located above the evaporator, separates water droplets from the saturated steam before the latter enters the superheater, and receives feedwater from the feedwater heater. A forced recirculation design was selected, since it is preferred for power plants requiring daily start-up and shutdown.

The superheater outlet steam can be attemperated by mixing with a small amount of saturated steam from the drum. The salt flow from the superheater to the evaporator is also attemperated to 850°F, when necessary, by mixing with salt flow from the cold tank. This allows chrome-moly piping and fittings, rather than stainless steel, to be used in the evaporator.

Warmup of the steam generation subsystem is accomplished by isolating the subsystem and preheating with the subsystem's electrical heater.

Major subsystem components, valves, instrumentation, and control loops are described on Tables 3.10 through 3.13.

3-30




Figure 3.6 . Steam Generation Subsystem Schematic

Table 3.10. Steam Generation Subsystem Components

Component	Description	Function	Nominal Operating Condition
Evaporator	<ul style="list-style-type: none"> <li>- U-tube/U-shell counterflow heat exchanger</li> <li>- 8 in. dia. chrome - moly shell (salt)</li> <li>- 27 chrome-moly tubes 0.875 in. dia. 68 ft avg. length (water)</li> </ul>	<ul style="list-style-type: none"> <li>- Evaporate subcooled water to produce saturated steam/water mixture</li> </ul>	<ul style="list-style-type: none"> <li>- 850°F salt inlet</li> <li>- 590°F salt outlet</li> <li>- 78,550 lb/hr salt flow rate</li> <li>- Subcooled water inlet</li> <li>- 567°F, 1200 psi saturated steam/water outlet</li> <li>- 2.15 MW rating</li> </ul>
Superheater	<ul style="list-style-type: none"> <li>- U-tube/U-shell counterflow heat exchanger</li> <li>- 6 in. dia. stainless steel shell (salt)</li> <li>- 23 stainless steel tubes 0.500 in. dia. 33 ft. avg. length (steam)</li> </ul>	<ul style="list-style-type: none"> <li>- Heat saturated steam to superheat condition</li> </ul>	<ul style="list-style-type: none"> <li>- 1050°F salt inlet</li> <li>- 906°F salt outlet</li> <li>- 64,680 lb/hr salt flow rate</li> <li>- 567°F 1175 psi saturated steam inlet</li> <li>- 1000°F. 1100 psi superheated vapor outlet</li> <li>- 10,530 lb/hr steam flow rate</li> <li>- 0.98 MW rating</li> </ul>
Steam Drum	<ul style="list-style-type: none"> <li>- Cylindrical pressure vessel with elliptical heads</li> <li>- 24 in ID</li> <li>- 6 ft 10 in overall height</li> <li>- 2 in thick carbon steel</li> <li>- Contains primary cyclone steam separator and primary &amp; secondary steam scrubbers</li> </ul>	<ul style="list-style-type: none"> <li>- Separate steam/water mixture exiting evaporator</li> <li>- Supply saturated steam to superheater</li> <li>- Provide feedwater surge volume</li> </ul>	<ul style="list-style-type: none"> <li>- 567°F</li> <li>- 1200 psi</li> </ul>

3-31



Table 3.10. Steam Generation Subsystem Components - 2

Component	Description	Function	Nominal Operating Condition
Boiler water circulation pump	<ul style="list-style-type: none"> <li>- Canned centrifugal type</li> <li>- 5 HP driver</li> </ul>	<ul style="list-style-type: none"> <li>- Provide circulation of subcooled water from the steam drum to evaporator. Maintain high recirculation rate over full range of operating conditions.</li> </ul>	<ul style="list-style-type: none"> <li>- 560°F</li> <li>- 119 GPM</li> <li>- 111 ft. head</li> </ul>
Start-up heater	<ul style="list-style-type: none"> <li>- Chamber type electric heater</li> <li>- 3 40-kW heating elements</li> <li>- 2 15-kW heating elements</li> </ul>	<ul style="list-style-type: none"> <li>- Raise temperature and pressure of water during cold start-up to avoid salt freeze-up in evaporator</li> <li>- Heat boiler water to maintain temperature and pressure of water/steam system during diurnal hold</li> </ul>	<ul style="list-style-type: none"> <li>- 150 kW during start-up</li> <li>- Cycled during diurnal hold</li> <li>- Bypassed during normal operation</li> </ul>
Steam attemperator	<ul style="list-style-type: none"> <li>- Mixing tee</li> </ul>	<ul style="list-style-type: none"> <li>- Mix saturated steam from steam drum with superheated steam from superheater to control steam delivery temperature to turbine</li> </ul>	<ul style="list-style-type: none"> <li>- 1053 lb/hr dry saturated steam at 567°F</li> <li>- 10,529 lb/hr superheated steam at 1000°F 1100 psi</li> <li>- 11,582 lb/hr delivery steam at 950°F 1100 psi</li> </ul>
Salt attemperator (evaporator inlet)	<ul style="list-style-type: none"> <li>- Mixing tee</li> </ul>	<ul style="list-style-type: none"> <li>- Mix cold salt with superheater outlet salt to limit evaporator inlet salt temperature to 850°F because of Cr-Mo construction</li> </ul>	<ul style="list-style-type: none"> <li>- 64,680 lb/hr at 906°F</li> <li>- 13,870 lb/hr at 590°F</li> <li>- 78,550 lb/hr at 850°F supplied to evaporator</li> </ul>

3-32

Table 3.10. Steam Generation Subsystem Components - 3

Component	Description	Function	Nominal Operating Condition
Salt start-up attemperator (superheater inlet)	<ul style="list-style-type: none"> <li>- Mixing tee</li> </ul>	<ul style="list-style-type: none"> <li>- Mix cold salt with hot salt from hot tank to provide a controlled temperature increase of salt entering superheater during start-up</li> </ul>	<ul style="list-style-type: none"> <li>- Full flow of cold salt at start-up</li> <li>- No cold salt flow during operation</li> </ul>
Heat tracing	<ul style="list-style-type: none"> <li>- Electrical heating element</li> <li>- Inconel sheath</li> </ul>	<ul style="list-style-type: none"> <li>- Maintain heat exchangers and salt piping above the freezing point of salt</li> <li>- Provide freeze protection of feedwater piping and instrumentation during shutdown</li> </ul>	<ul style="list-style-type: none"> <li>- Temperature monitored by thermocouples</li> <li>- Cycle as required</li> </ul>

Table 3. 11  
SGS REMOTE OPERATED VALVES

VALVE	MANUFACTURER	SIZE	TYPE	FAIL POSITION	FUNCTION	LOCATION
FCV-301	Valtek	1"	CV	FO	Evaporator Salt Temperature Control and Cold Salt Fill	SGS Skid West Side South End
FCV-321	Valtek	2"	CV	FO	Main Salt Flow Control	SGS Skid South End
FCV-331	Fisher	1"	CV	FO	Steam Attemperator Temperature Control	SGS Skid North Side Steam Drum
FCV-341	Valtek	1"	CV	FC	Main Salt Fill	SGS Skid West Side Middle
FCV-351	Valtek	2"	CV	FO	Hot Salt Flow Control	Outside Pumphouse Northeast Corner
FCV-381	Kieley-Mueller	1"	SV	FC	Evaporator Salt Drain	SGS Skid West Side Middle
FCV-382	Kieley-Mueller	1"	SV	FC	Superheater Salt Drain	SGS Skid West Side Below Steam Drum
FCV-383	Dresser	4"	SV	FO	Evaporator Water Supply	SGS Skid Southeast Corner
FCV-384	Valtek	2"	SV	FO	Start-up Heater Supply	SGS Skid Below FCV-383

Table 3.12. SGS Instrumentation

Identifier	Description	Control Module	Display Range	Alarm Levels		Dimension	Sampling Period (sec)
				High	Low		
PT-386	Feedwater Pressure	PCM-3/ Bailey	0-1500	1500		PSI	5
TE-386	Temp	PCM-3/ Bailey	0-750	575	500	°F	10
PT-383	Steam Drum Pressure	PCM-3/ Bailey	0-1500	1250	950	PSI	5
TE-383	Fluid temp	PCM-3/ Bailey	0-750	575	500	°F	10
LT-311	Fluid level	PCM-3/ Bailey	-17 to +23	4	-4	inch	2
TE-301	Evaporator Salt inlet temp	PCM-3/ Bailey	0-1200	880	500	°F	2
TE-384	Salt outlet temp	PCM-3/ Bailey	0-1200	640	500	°F	2
PT-384	Salt outlet pressure	PCM-3/ Bailey	0-200			PSI	5
FT-321	Salt flow rate	PCM-3/ Bailey	0-100			KLB/hr	2

Table 3.12. SGS Instrumentation

Identifier	Description	Control Module	Display Range	Alarm Levels		Dimension	Sampling Period (sec)
				High	Low		
	Superheater						
PT-382	Salt inlet pressure	PCM-3/ Bailey	0-200	100		PSI	5
TE-382	Salt inlet temp	PCM-3/ Bailey	0-1200	1070	500	°F	5
TE-331	Steam outlet temp	PCM-3 Bailey	0-1200		910	°F	2
FT-381	Attemperator steam flow	PCM-3/ Bailey	0-2500			lb/hr	5
3-36 FT-382	SGS Cold Salt Supply	PCM-3/ Bailey	0-16			KLB/hr	5
	Steam Delivery						
PT-321	Pressure	PCM-3/ Bailey	0-1500	1150	950	PSI	2
TE-332	Temp	PCM-3/ Bailey	0-1200	990	910	°F	2
FT-311	Flow rate	PCM-3/ Bailey	0-100	12.6	3.2	KLB/hr	2
TE-387	Hot Salt Pump Bearing	PCM-3	0-500	190		°F	10
TE-388	Start-up Heater 5 Element Temp	PCM-3/ Bailey	0-1200	1100	500	°F	10

Table 3.13. SGS Control Loops

Controlled Variable	Mode	Set Point	Controller Inputs	Controller Output
Steam delivery pressure	SGS start-up	1000 psig FCV-491	Delivery pressure (PT-321) pressure set point	FCV-491 position - SGS steam flow
	Boiler following	1100 psig SP. SP	Delivery pressure (PT-321) Pressure set point (SP. SP) Steam flow (FT-311) Salt flow (FT-321)	FCV-321 position - SGS main salt flow
Steam delivery temperature	Operation	950°F SP. ST	Delivery temperature (TE-332) Temperature set point (SP. ST)	FCV-331 position - Steam attemperator flow
Steam drum level	Operation	0 in SP. DL	Drum level (LT-311) Level set point (SP. DL) Feedwater flow (FT-411) Steam flow (FT-311)	FCV-411 position - Feedwater flow
Evaporator salt inlet temperature	Operation	850°F SP. EST	Inlet temperature (TE-301) Temperature set point (SP. EST)	FCV-301 position - Cold salt flow
Boiler water temperature	Diurnal Shutdown	~ 520°F	Circulation heater outlet temperature (TE-388)	Electric immersion heater elements on/off

### 3.6 ELECTRIC POWER GENERATION SUBSYSTEM

The electric power generation subsystem converts the enthalpy in the main steam flow to electricity. The subsystem (Figure 3.7) includes the steam turbine, electric generator, electric power equipment, condenser, condensate pump and storage tank. The electrical one-line diagram is shown on Figure 3.8.

The turbine-generator set is a skid-mounted unit located at the north end of the receiver tower complex at the 80 ft. level (20 ft. below grade). This skid consists of a turbine, generator, and auxiliary equipment. The turbine is a seven-stage, single flow machine, operating at 17,400 rpm. Inlet steam conditions are rated at 940°F and 1050 psia. A single reduction gearbox reduces the turbine shaft speed to the generator speed of 1,200 rpm. The 750 kW<sub>e</sub> generator operates at 450V, and is cooled by circulating water through air cooling coils located above the generator. The turbine-generator auxiliaries include a lubricating oil pump, lube oil cooler, air ejection vacuum pump and mechanical-hydraulic governor. The allowable rate of change in load is 10 percent per minute from 30 to 100 percent of rated capacity.

A shell and tube condenser, supported by a separate frame, is located directly below the turbine. Access to the condenser is on the floor 40 ft. below ground. Condensate from the hot well of the condenser will be transferred to the deaerator when the water level in the deaerator requires makeup. Otherwise, the condensate is pumped to a storage tank. Condensate from this tank is piped back to the condenser hot well when the hot well level requires water.

Major components of the EPGS, valves, instrumentation, and control loops are described on Tables 3.14 through 3.17.




Figure 3.7. Electric Power Generation Subsystem Schematic



3-40




Figure 3.8. MSEE Electric Generator One-Line Diagram

Table 3.14  
Electric Power Generation Subsystem Components

Component	Description	Function	Nominal Operating Condition
Turbine	<ul style="list-style-type: none"> <li>- Axial flow condensing type</li> <li>- 7 stage</li> </ul>	<ul style="list-style-type: none"> <li>- Expand steam to drive electric generator</li> </ul>	<ul style="list-style-type: none"> <li>- 940°F 1050 psig throttle steam</li> <li>- 133°F 2.5 psia exhaust steam</li> <li>- 7800 lb/hr steam flow</li> <li>- 17,443 RPM</li> <li>- 1000 HP</li> </ul>
Electric generator	<ul style="list-style-type: none"> <li>- AC generator</li> <li>- 450 volt, 3 phase</li> <li>- 1200 RPM</li> <li>- Solid state excitor</li> </ul>	<ul style="list-style-type: none"> <li>- Generate electric power</li> </ul>	<ul style="list-style-type: none"> <li>- 750 kW<sub>e</sub> (rating)</li> <li>- 600 kW<sub>e</sub> (maximum in MSEE)</li> <li>- 0.8 power factor rating</li> </ul>
Condenser	<ul style="list-style-type: none"> <li>- Crossflow shell and tube heat exchanger</li> <li>- Rectangular shell (condensate)</li> <li>- 438 tubes, 5/8-in. dia. 7-1/2 ft long (glycol/water coolant)</li> <li>- Cylindrical hot well</li> </ul>	<ul style="list-style-type: none"> <li>- Condense turbine exhaust steam</li> <li>- Provide turbine exhaust vacuum</li> </ul>	<ul style="list-style-type: none"> <li>- 2.5 psia saturated steam inlet</li> <li>- 133°F condensate outlet</li> <li>- 7800 lb/hr steam/water flow</li> <li>- 1200 GPM glycol/water coolant flow</li> </ul>
Condensate pump	<ul style="list-style-type: none"> <li>- Turbine type</li> <li>- 2 stage</li> <li>- 20 HP driver</li> </ul>	<ul style="list-style-type: none"> <li>- Pump condensate from hot well to deaerator</li> </ul>	<ul style="list-style-type: none"> <li>- 133°F water</li> <li>- 260 psi head (mfg rating)</li> <li>- 18 GPM (mfg rating)</li> </ul>

3-41

Table 3.14  
Electric Power Generation Subsystem Components

Component	Description	Function	Nominal Operating Condition
Air exhaust pump	- Nash vacuum pump - 5 HP driver	- Provide condenser vacuum	- 5 in Hg condenser pressure (ABS) - 75 CFM (mfg. rating)
Electric oil pump	- Viking gear pump	- Provide bearing oil pressure during turbine start-up and shutdown (turbine-driven pump provides oil pressure during operation)	- Off during operation
Cooling tower pump	-Aurora centrifugal pump	- Provide coolant circulation through oil cooler	- 35 psi head (mfg. rating) - 120 GPM (mfg. rating)
Wet cooling tower	-Fan forced wet cooler -1/2 HP fan motor	- Reject oil coolant heat	- 110°F coolant outlet temp

Table 3.15  
EPGS REMOTE OPERATED VALVES

VALVES	MANUFACTURER	SIZE	TYPE	FAIL POSITION	FUNCTION	LOCATION
FCV-501	Valtek	2"	SV	FC	Turbine Steam Isolation	TWR Level 80 North Turbine Northeast Corner
FCV-511	Asco	1/2"	SV	FC	Hotwell Overflow	TWR Level 60 North Condenser Platform Northwest
FCV-512	Asco	3/4"	SV	FC	Hotwell Make-up	TWR Level 80 Northeast Condensate Storage Tank
FCV-521	Masoneilan	2"	CV	FO	Oil Cooler Water Flow Control	TWR Level 80 North Turbine/Generator Overhead
FCV-541	Asco	3/4"	SV	FC	Condenser Storage Tank Make-up	TWR Level 80 Northeast Condensate Storage Tank
FCV-551	Asco	1/2"	SV	FC	Condenser Recirculation	TWR Level 60 North Condenser Platform Northwest
TVM	GE w/auma Actuator	1 1/2"	CV	FC	Turbine Steam Supply Throttle	Turbine North Side
SNM	GE	--	CV	--	Turbine Sync Speed Control	Turbine Center
Fcv-561	ASCO	1/2"	SV	FO	Close throttle valve in emergency trip (dumps hydraulic oil)	Turbine

TABLE 3.17. EPGs INSTRUMENTATION

IDENTIFIER	DESCRIPTION	CONTROL MODULE	DISPLAY RANGE	ALARM HIGH	LEVELS LOW	DIMENSION	SAMPLING PERIOD (sec)
Turbine							
PT-581	Steam Supply Pressure	PCM 2	0-1500		800	PSI	5
PT-582	Steam Seal Pressure	PCM 2	0-1500			PSI	5
TE-581	Exhaust Temp	PCM 2	0-500			°F	5
TT-583	Steam Supply Temp	PCM 2	0-1200	990	800	°F	5
TT-501	Outboard Bearing Oil Temp	PCM 2	0-500	170	110	°F	5
TT-502	Inboard Bearing Oil Temp	PCM 2	0-500	170	110	°F	5
TE-503	Gear Outboard Bearing Oil Temp	PCM 2	0-500	170	110	°F	5
AZT-581	Vibration	PCM 2	0-100	100		PCT (0-5 g)	5
Generator							
JT-581	Power	PCM 2	0-960			kw	5
ET-581	Voltage	PCM 2	0-600	480	450	Volt	5
IT-581	Current	PCM 2	0-1200			Amp	5
PFT-581	Power Factor	PCM 2	0-1.0	1.0	0.85	PCT	5
VT-581	VARS	PCM 2	0-960			KVA	5
ST-582	Speed	PCM 2	0-1500	1270		rpm	5
ST-581	Frequency	PCM 2	0-100	60	40	PCT (55-65 Hz)	5
TT-510	Stator Winding 1 Temp	PCM 2	0-500	260		°F	5
TT-511	Stator Winding 2 Temp	PCM 2	0-500	260		°F	5
TT-512	Stator Winding 3 Temp	PCM 2	0-500	260		°F	5
TT-513	Stator Winding 4 Temp	PCM 2	0-500	260		°F	5
TT-514	Stator Winding 5 Temp	PCM 2	0-500	260		°F	5
TT-515	Stator Winding 6 Temp	PCM 2	0-500	260		°F	5
TE-508	Cooling Air Outlet Temp	PCM 2	0-500	100		°F	5
TT-507	Outboard Bearing Oil	PCM 2	0-500	170	110	°F	5
TE-505	Gear Outboard Bearing Oil Temp	PCM 2	0-500	170	110	°F	5
TE-506	Gear Inboard Bearing Oil Temp	PCM 2	0-500	170	110	°F	5
PT-502	Condenser Pressure	PCM 2	0-30	15		In Hg	5
PT-583	Condensate Pump Discharge Pressure	PCM 2	0-400	300	240	PSI	5
LT-511	Hot Well Level	PCM 2	0-15	16	8	Inch	2
TE-582	Cooling Tower Pump Discharge Temp	PCM 2	0-500	100	40	°F	5
PT-531	Oil Pump Discharge Pressure	PDM 2	0-200	100	55	PSI	5
TT-521	Bearing Oil Supply Temp	PCM 2	0-500	140	100	°F	2
PT-501	Bearing Oil Supply Press.	PCM 2	0-50	40	10	PSI	5

Table 3-17  
EPGS Control Loops

Controlled Variable	Mode	Set Point	Controller Inputs	Controller Output
Condenser hot well level	Remote operation (TCP. MS on) (EN.HLC on)	9 in min 14 in max	Hot well level (LT-511)	FCV-512 open/close - makeup FCV-511 open/close - dump
Condensate storage tank level	Operation	12 in min 30 in max	Storage tank level (LS-541)	FCV-541 open/close - supply from cycle fill pump  FCV-542 open/close - CMUP Stand pipe air overpressure
Turbine/generator oil temperature	Remote operation	125°F FCV-521	Oil temperature (TT-521)	FCV-521 position - cooling water flow

### 3.7 HEAT REJECTION AND FEEDWATER SUBSYSTEM

The heat rejection and feedwater subsystem rejects waste heat to the atmosphere, pressurizes and heats the condensate to the final feedwater temperature. The subsystem (Figure 3.9) includes the cooling towers, circulating water pump, deaerator, spray water heat exchanger, spray water pump, feedwater pump, feedwater heater, demineralizers, chemical feeders, water analyzers, and condensate makeup pump.

The cooling towers consist of six forced-draft, finned-tube water-to-air heat exchangers. They originally were designed as Freon condensers for refrigeration systems.

The deaerator is used as a direct contact feedwater heater and deaerator and to reject steam generated by the SGS. It is a horizontal, cylindrical pressure vessel, designed to operate at 250 psia and 400°F. It includes a steam header with mixing spargers near the bottom of the tank, water spray nozzles across the top, and two immersion electric heaters. Feedwater, stored in the deaerator, is heated by steam from a branch off the SGS mainline to the turbine. The feedwater is circulated by a spray water pump at 400 gpm from the bottom of the deaerator to the spray nozzles in the vapor space at the top of the deaerator where the water condenses the steam and is thereby heated. Condensate from the turbine condenser, blended into this spray water, is also heated to 400°F and deaerated.

The feedwater heater is a vertical, cylindrical pressure vessel with an internal steam condensing coil. Feedwater from the deaerator is heated on the tube side as steam from a branch of the SGS mainline condenses on the shell side. The saturated liquid from the coil is cascaded down to the deaerator through a steam trap. Main steam is used for feedwater heating in the feedwater heater and the deaerator because there are no external extraction points on the turbine.

Major components, valves, instrumentation, and control loops are described on Tables 3.18 through 3.21.

3-47




Figure 3.9 . Heat Rejection and Feedwater Subsystem Schematic



Table 3.18  
Heat Rejection and Feedwater Subsystem Components

Component	Description	Function	Nominal Operating Condition
Feedwater heater	<ul style="list-style-type: none"> <li>- Shell and coiled tube counter-flow heat exchanger</li> <li>- 35 in ID 2.5 in thick carbon steel shell (feedwater)</li> <li>- 4 ft 8 in overall height</li> <li>- 30 coiled tubes 0.500 in. dia. 43 ft long (steam)</li> </ul>	<ul style="list-style-type: none"> <li>- Raise feedwater temperature to SGS inlet condition</li> </ul>	<ul style="list-style-type: none"> <li>- 950°F superheated steam inlet</li> <li>- 545°F saturated liquid outlet</li> <li>- 2150 lb/hr steam flow rate</li> <li>- 401°F feedwater inlet</li> <li>- 550°F feedwater outlet</li> <li>- 11,582 lb/hr feedwater flow rate</li> <li>- 0.59 MW heat transfer</li> </ul>
Deaerator	<ul style="list-style-type: none"> <li>- Horizontal tank</li> <li>- 5 ft ID</li> <li>- 12 ft long</li> <li>- Contains 15 submerged mixing nozzles, 1 overhead spray nozzle, 2 147-kW electric immersion heaters</li> </ul>	<ul style="list-style-type: none"> <li>- Degasify condensate</li> <li>- Heat condensate for delivery to feedwater heater</li> <li>- Provide alternate steam dump when turbine is not operating</li> </ul>	<ul style="list-style-type: none"> <li>- 401°F</li> <li>- 250 psi</li> <li>- 0.63 MW heat transfer</li> </ul>
Spray water heat exchanger	<ul style="list-style-type: none"> <li>- Shell and tube heat exchanger</li> <li>- 24 in. dia. shell</li> </ul>	<ul style="list-style-type: none"> <li>- Reject excess heat from deaerator when utilized as alternate steam dump</li> </ul>	<ul style="list-style-type: none"> <li>- No flow from deaerator during normal operation</li> </ul>

Table 3.18  
Heat Rejection and Feedwater Subsystem Components - 2

Component	Description	Function	Nominal Operating Condition
Feedwater pump	<ul style="list-style-type: none"> <li>- High speed centrifugal type</li> <li>- 18,770 pump RPM</li> <li>- 150 HP driver</li> </ul>	<ul style="list-style-type: none"> <li>- Provide high pressure feedwater to the steam generator (through the feedwater heater)</li> </ul>	<ul style="list-style-type: none"> <li>- Inlet: 250 psi, 401°F water</li> <li>- 1450 psi head (mfg rating)</li> <li>- 60 GPM (mfg rating)</li> </ul>
Spray water pump	<ul style="list-style-type: none"> <li>- Vertical turbine type</li> <li>- 3 stage</li> <li>- 7-1/2 HP driver</li> </ul>	<ul style="list-style-type: none"> <li>- Provide circulation from deaerator to spray water heat exchanger and/or its bypass and return to deaerator overhead spray nozzle</li> </ul>	<ul style="list-style-type: none"> <li>- 401°F</li> <li>- 26 psi head (mfg rating)</li> <li>- 300 GPM (mfg rating)</li> </ul>
Cooling water pump	<ul style="list-style-type: none"> <li>- Centrifugal type</li> <li>- 40 HP driver</li> </ul>	<ul style="list-style-type: none"> <li>- Provide glycol/water circulation for spray water heat exchanger - cooling tower - condenser circuit</li> </ul>	<ul style="list-style-type: none"> <li>- 132°F glycol/water</li> <li>- 40 psi head</li> <li>- 1200 GPM</li> </ul>
Cooling towers	<ul style="list-style-type: none"> <li>- 6 units</li> <li>- Forced draft, finned-tube, glycol/water-to-air heat exchangers</li> </ul>	<ul style="list-style-type: none"> <li>- Reject waste heat to atmosphere</li> </ul>	<ul style="list-style-type: none"> <li>- 94°F air</li> <li>- 132°F glycol/water inlet</li> <li>- 120°F glycol/water outlet</li> <li>- 2.4 MW heat rejection</li> </ul>

3-49

Table 3.19  
HRFS REMOTE OPERATED VALVES

VALVE	MANUFACTURER	SIZE	TYPE	FAIL POSITION	FUNCTION	LOCATION
FCV-401	Fisher	2"	CV	F0	Feedwater Pump Pressure Control	Southwest of Deaerator
FCV-411	Kieley-Mueller	2"	CV	FC	Feedwater Flow Control	SGS Skid Northeast
FCV-421	Kieley-Mueller	2"	CV	F0	Feedwater Heater Temperature Control	Above Feedwater Heater
FCV-431	Kieley-Mueller	2"	CV	FC	Main Steam Pressure Control	Southwest of Deaerator
FCV-432	Kieley-Mueller	3"-3 way	CV	To SWHX	Deaerator Pressure Control	Between Deaerator and Spray Water Heat Exchanger
FCV-471	Valtek	1"	CV	FC	Condensate Control to Deaerator	Above North Door to Spray Water Pump Room
FCV-483	Atkomatic	1"	SV	--	Deaerator Vent Block	Above Deaerator
FCV-484	Atkomatic	1/4"	SV	--	Deaerator Vent Bypass	Above Deaerator
FCV-485	ASCO	2"	SV	--	Demineralized Water Storage Tank Fill	Above Culligan Beds
FCV-491	Kieley-Mueller	2"	CV	FC	SGS Steam Delivery Control During Start-Up	North End of SGS Skid

2-50

TABLE 3.20. HRFS INSTRUMENTATION

IDENTIFIER	DESCRIPTION	CONTROL MODULE	DISPLAY RANGE	ALARM HIGH	LEVELS LOW	DIMENSION	SAMPLING PERIOD (sec)
Main Steam							
PT-431	Pressure	PCM 2	0-1500	1200	900	PSI	2
TE-483	Temp	PCM 2	0-1200	990	850	Inch	10
Deaerator							
PT-432	Pressure	PCM 2	0-400	250	200	PSI	2
TE-451	Fluid Temp	PCM 2	0-500	400	300	°F	2
TE-481	Steam Temp	PCM 2	0-500	400	300	°F	10
LT-471	Fluid Level	PCM 2	0-30	30	10	Inch	2
Spray Water							
PT-482	Pressure	PCM 2	0-400	300	200	PSI	5
FT-482	Flow Rate	PCM 2	0-160			KLB/hr	5
TE-482	Temp	PCM 2	0-500	445		°F	10
FT-481	Feed/Spray Water Flow Rate	PCM 2	0-160			KLB/hr	5
Feedwater							
PT-481	FWP Supply Pressure	PCM 2	0-400		170	PSI	5
PT-401	FWP Discharge Pressure	PCM 2	0-1500	1400	900	PSI	2
PT-484	FWP Coolant Pressure	PCM 2	0-100			PSI	5
PT-483	FWH Outlet Pressure	PCM 2	0-1500	1230	1180	PSI	5
FT-411	Flow Rate	PCM 2/	0-160 Bailey			KLB/hr	2
FT-421	FWH Outlet Temp	PCM 2	0-750	600	400	°F	2
Cooling Water							
TE-484	SWHX Inlet Temp	PCM 2	0-500	130		°F	10
TE-486	Tower Outlet Temp	PCM 2/	0-500	110	32	°F	10

Table 3.21. HRFS Control Loops

Controlled Variable	Mode	Set Point	Controller Inputs	Controller Output
Feedwater temp.	Operation	520° 540°F FCV-421	Feedwater temperature (TE-421) Temperature set point	FCV-421 position - Feedwater heater Steam supply flow
Feedwater pressure	Operation	1250 psig FCV-401	Feedwater pressure (PT-401) Pressure set point	FCV-401 position - FWP recirculation flow
Steam delivery pressure	Manual salt flow GSTAT off	1080 psig PT-431	Delivery pressure (PT-431) Pressure set point	FCV-431 position - Deaerator steam dump
Deaerator pressure	Operation - Desuperheating GSTAT off	233 psig PT-432	Deaerator pressure (PT-432) Pressure set point	FCV-432 position - Deaerator dump to SWMX
	Boiler following GSTAT on	233 psig PT-432	Deaerator pressure (PT-432) Pressure set point	FCV-431 position - Deaerator steam supply
Deaerator temp.	Start-up	390°F DTC 451 DTC 452	Deaerator temperature (TE-451) Temperature set point	DTC-451/452 on/off - Electric heater control
Deaerator level	Operation	15 in <i>controls deaerator level</i> FY-472 (14 in backup during turbine operation)	Deaerator level (LT-471) Level set point	FY-472 condensate - Makeup pump stroke position
	Turbine Operation	15 in FCV-471	Deaerator level (LT-471) Level set point	FCV-471 position - Turbine condensate return from hot well

3-52

*DEAERATOR  
OPERATION  
FY-472*

### 3.8 SYSTEM TRIPS

#### 3.8.1 Equipment Protection Subsystem

The Equipment Protection Subsystem (EPS) is a hard-wired system using dedicated sensors and is designed to save the MSEE in the event of any potentially unsafe condition. Subsequent to the EPS placing the system in a "safe" condition, operator action is required to shut the system down or to change into any other mode. The trip list for the EPS, including actions taken by the EPS and subsequently to be taken by the operator, are shown on Table 3.22, subdivided by subsystem.

#### 3.8.2 Turbine/Generator Trips

Trips built into the turbine/generator are given on Table 3.2.3. Definitions and guidelines are given below.

##### A. Definitions

1. Turbine Trip - Immediate turbine steam shutoff - manual or auto.
2. Turbine Shutdown - Gradual turbine steam shutoff - manual.
3. Generator Trip - Generator circuit breaker opened - manual or auto.

##### B. Steam reactions to trips

1. Anticipated - Steam control maintained manually or auto.
2. Upset - Reliance on auto steam control - SGS salt flow will stop and HRFS will attempt to desuperheat steam. Probable HRFS and SGS safety valve lifting if upset is uncontrolled.

C. Trip interlocks

1. A generator breaker trip always initiates a turbine SVC trip (auxiliary relay 32x closes FCV-501) and an EPST TR-586 (32x).
2. A generator breaker trip always initiates a turbine T.V. reset (auxiliary relay 32x resets T.V. closed) w/ZT-581 '0' open.
3. A turbine T.V. reset and an EPS 2 & 3 reset will reopen FCV-501 unless manually closed (or tripped).

D. All auto trips should be carefully reviewed - determine the cause of the trip and correct the problem before resuming operations.

E. Fail-safe follow-through guidelines

These guidelines present items of concern to fail-safe the EPGS upon a major component failure, after a trip that did not function, or to back up an auto trip. Intimate familiarity with these guidelines is mandatory before EPGS operation to insure safe operation, both from a personnel and equipment standpoint.

1. Three items are of major concern to fail-safe the EPGS and MSEE operating systems:
  - a. Steam over-pressurization
  - b. Turbine trip
  - c. Generator trip
2. Steam system reactions to turbine trips:
  - a. Over-pressurization
  - b. Possible HRFS/D-D & SGS/steam drum safety valve lifting
  - c. Desuperheating by HRFS/FCV-431 switchover to steam control to dump steam to D/D
  - d. FCV-432 D/D heat dump through SWHX and dry cooling tower

3. Turbine tripping is redundant-designed and may be fully utilized with these four trips:

- a. Actuate ET emergency trip FCV-561 (oil trip)
- b. Open generator breaker with breaker C.S. (electric trip)
- c. Actuate EPS T-G trip button from control room (EPS backup)
- d. Manually close throttle valve with hand wheel (manual)

4. Turbine-generator trip verification:

- a. ST-582 speed decreasing
- b. PT-532 hydraulic oil pressure decreasing (T.V. trip)
- c. PT-581 steam pressure drops to zero (FCV-501 trip)
- d. Generator breaker open - green light on

NOTE

EOP operation is not mandatory upon a turbine trip since the shaft driven oil pump provides adequate oil flow for turbine coast down.

5. Generator trips are redundant-designed with turbine trips. Be aware that:

- a. EPGS UPS provides emergency backup C/B trip power
- b. Exciter voltage shutdown local disconnect switch shuts down all of the generator electrical power.



TABLE 3.22. EQUIPMENT PROTECTION SYSTEM  
RECEIVER SUBSYSTEM TRIPS

TRIP IDENTIFIER	TRIP CONDITION	INSTRUMENT IDENTIFIER	TRIP LEVEL	ACTION REQUIRED
--	Operator Manual Trip	--	N/A	EPS - Defocus Heliostats
TR-181	Receiver Salt Outlet Temp High	TE-102A	1080°F	Operator - Control Receiver From The EMCON Console
TR-184	Receiver Tube Temp High During Hot Salt Production	TE-140A and TE-102A	925°F >750°F	
TR-187	Loss of Receiver Door Open Signal	ZSH-DR	Contact Open	
TR-182	Boost Pump Pressure Low During Hot Salt Production	PT-180A and TE-102A	250 PSIG >750°F	EPS - Defocus Heliostats - Close FCV-151 After Time Delay
TR-183	Receiver Salt Inlet Pressure Low During Hot Salt Production	PT-181A and TE-102A	8 PSIG >750°F	Operator - Shutdown Receiver from EMCON Console
TR-185 Heliostats	Hot Surge Tank Level High	LF-161A or TE-184A	80 In 300°F	EPS - Defocus - Close FCV-101 and FCV-102 After Time Delay  Operator - Shutdown Receiver From EMCON Console

TABLE 3.22. EQUIPMENT PROTECTION SYSTEM  
 RECEIVER SUBSYSTEM TRIPS  
 (Continued)

TRIP IDENTIFIER	TRIP CONDITION	INSTRUMENT IDENTIFIER	TRIP LEVEL	ACTION REQUIRED
TR-186	Boost Pump Sump Level High	TE-181A	400°F	EPS <ul style="list-style-type: none"> <li>- Defocus Heliostats</li> <li>- Time Delay</li> <li>- Close FCV-151</li> <li>- Turn Off Cold Salt Boost Pump</li> <li>- Turn Off Hot Salt Pump</li> </ul> EMCON (Automatic) <ul style="list-style-type: none"> <li>- Maintain Control of Receiver and HRFS</li> </ul> Operator <ul style="list-style-type: none"> <li>- Shut Down the Plant From the EMCON Console</li> </ul>

TABLE 3.22. EQUIPMENT PROTECTION SYSTEM  
THERMAL STORAGE SUBSYSTEM TRIPS  
(Continued)

TRIP IDENTIFIER	TRIP CONDITION	INSTRUMENT IDENTIFIER	TRIP LEVEL	ACTION REQUIRED
TR-281	Hot Salt Sump Level High	LT-221A or TE-231A	40 In  300°F	<p>EPS</p> <ul style="list-style-type: none"> <li>- Close Sump Insolation Valve FCV-231</li> </ul> <p>Operator</p> <ul style="list-style-type: none"> <li>- Allow Time for Hot Salt Pump Operations To Bring Sump Level Down</li> <li>- Shut down SGS, HRFS, and EPGS From EMCON Console</li> </ul>
TR-282	Cold Salt Sump Level High	LT-201A or TE-211A	55 In  350°F	<p>EPS</p> <ul style="list-style-type: none"> <li>- Close Sump Insolation Valve FCV-211</li> <li>- Defocus Heliostats</li> </ul> <p>Operator</p> <ul style="list-style-type: none"> <li>- Allow Time for Cold Salt Pump Operations To Bring Sump Level Down</li> <li>- Shut down the Plant From The EMCON Console</li> </ul>

TABLE 3.22. EQUIPMENT PROTECTION SYSTEM  
 STEAM GENERATOR SUBSYSTEM TRIPS  
 (Continued)

TRIP IDENTIFIER	TRIP CONDITION	INSTRUMENT IDENTIFIER	TRIP LEVEL	ACTION REQUIRED
TR-381	Steam Drum Level Low	LT-311A	-10 In	EPS - Close FCV-501 - Open Generator Circuit Breaker - Turn Off FWP (Drum Level High only)  EMCON (Automatic) - Dump Steam To Deaerator - Maintain Control of HRFS  Network 90 - Shut Off Salt Flow (Close FCV-301, 341, and 351) - Turn Off BWCP (Drum Level Low only)  Operator - Shut Down SGS, HRFS, and EPGS From EMCON Console
TR-383	Steam Drum Level High and Water Hot	LT-311A and TE-383A	+17 In >250°F	Network 90 - Shut Off Salt Flow (Close FCV-301, 341, and 351) - Turn Off BWCP (Drum Level Low only)  Operator - Shut Down SGS, HRFS, and EPGS From EMCON Console
TR-382	Boiler Water Circulation Pump Failure	Motor Current Sensor	Off	EPS - Close FCV-501 - Open Generator Circuit Breaker  EMCON (automatic) - Dump Steam to Deaerator - Maintain control of HRFS  Network 90 - Shut Off Salt Flow (Close FCV-501, 341, and 351)  Operator - Shut down SGS, HRFS, and EPGS from EMCON console

TABLE 3.22. EQUIPMENT PROTECTION SYSTEM  
EPGS TRIPS  
(Continued)

TRIP IDENTIFIER	TRIP CONDITION	INSTRUMENT IDENTIFIER	TRIP LEVEL	ACTION REQUIRED
	Turbine Overspeed	OST	1320 RPM Generator	EPS - Close FCV-501 Open Generator Circuit Breaker
	Turbine Back Pressure High	TBPT	5 PSIG	
TR-584	Generator Bearing Temp High	TS-501A	180°F	EMCON (Automatic) - Dump Steam to Deaerator - Maintain Control of HRFS
TR-585	Generator Cooling Air Temp High	TS-502A	122°F	Operator - Control System From EMCON Console - Reduce Steam Flow
TR-586	Generator Circuit Breaker Trip		-Manual -Low/high Voltage -Low/high frequency	- Shut Down If Necessary
TR-587	Turbine Vibration High	AZT-581	5g	
TR-588	Steam Energy Low	TE-332 or PT-581A	750°F 770 PSI	
TR-583	Turbine Oil Pressure	PS-501A (LUBE) or PS-531A (HYDR)	6 PSI 50 PSI	
TR-582	Manual T/G Emergency Trip	Control Room PB	Operator Initiate	

TABLE 3.22. EQUIPMENT PROTECTION SYSTEM  
 MASTER CONTROL SUBSYSTEM TRIPS  
 (Continued)

TRIP CONDITION	ACTION REQUIRED
PCM 1 Microcomputer Failure	EPS
- Loss of Receiver Displays	- Defocus Heliostats
- Loss of Salt Auto Flow Control	- Close FCV-151 After Time Delay
- Loss of Cold Surge Tank Auto Level Control	Operator
	- Control Receiver from PCM 1
	- Drain Receiver If Necessary
PCM 2 Microcomputer Failure	EPS
- Loss of HRFS and EPGS Displays	- Turn Off Hot Salt Pump
- Loss of Feedback Control Loops	- Close FCV-301, FCV-341, and FCV-351
	- Turn Off FWP
	- Close FCV-501 and FCV-491 After Steam Pressure Drops
	- Open Generator Circuit Breaker
	- Turn Off Condensate Pump
	Operator
	- Shut Down SGS From Console
	- Shut Down HRFS and EPGS From PCM 2
PCM 3 Microcomputer Failure	EPS
- Loss of TSS Displays	- Defocus Heliostats
- Loss of Feedback Control Loops	- Time Delay
- Loss of SGS Displays	- Close FCV-211
	- Close FCV-231
	- Turn Off Hot and Cold Salt Pumps
	- Turn Off Cold Salt Boost Pump
	- Close FCV-151
	- Close FCV-501
	- Open Generator Circuit Breaker
	EMCON (Automatic)
	- Dump Steam To Deaerator
	- Maintain Control of HRFS
	Network 90 (Automatic)
	- Interlocks Will Close FCV-301, FCV-341, and FCV-351
	Operator
	- Shut Down SGS From Network 90 Console
	- Shut Down Receiver, HRFS, and EPGS from EMCON Console

TABLE 3.22. EQUIPMENT PROTECTION SYSTEM  
 MASTER CONTROL SUBSYSTEM TRIPS  
 (Continued)

TRIP CONDITION	ACTION REQUIRED
Simultaneous Failure of PCM 1, 2, and 3 Microcomputers - Loss of All Subsystem Control	EPS - Defocus Heliostats - Time Delay - Close FCV-211
CCM Microcomputer Failure - Loss of PCM/Host Computer Communication Lin - Loss of Console Displays - Loss of Console Control Capability - Loss of Sequencing Operations Involving More Than One PCM	- Close FCV-231 - Turn Off Hot and Cold Salt Pumps - Turn Off Cold Salt Boost Pump - Close FCV-151 - Turn off FWP - Close FCV-501 and FCV-491 After Steam Pressure Drops - Open Generator Circuit Breaker - Turn Off Condensate Pump
Operator Remote Manual Trip	Operator - Shut Down the Subsystems From PCM 1, 2, and 3 and Network 90
EMCON Host Computer Failure	PCMs and CCM Continue To Operate and Control The Plant  Operator - Shut Down The Subsystems From PCM 1, 2, and 3

Table 3.23. TURBINE/GENERATOR TRIP LIST

MODE	DESCRIPTION	INITIATION
Manual	MGBT - Manual generator breaker trip	Breaker switch opened at local or remote generator control panel
Manual	ET - Emergency trip	ET "on" at EMCON console or local trip button actuated
Manual/auto	SVC - Stop valve closure	Close FCV-501
Manual/auto	OST - Overspeed trip	Local OST button
Manual	MTVC - Manual throttle valve closure	Close throttle valve (TVM)
Auto	GBT - Generator breaker trip	a. Reverse power b. Ground fault c. Overcurrent



A tabulation of data describing the MSEE system is given on Table 3.1. A more detailed description of the MSEE subsystems is contained in the following subsections.

### 3.1 COLLECTOR SUBSYSTEM

The collector subsystem redirects, concentrates, and focuses solar radiation onto the tower-mounted receiver. The subsystem, which is already in place at the CRTF, consists of 221 two-axis tracking heliostats located north of the receiver tower, and its control system. Under optimum insolation and heliostat conditions, the heliostat field can concentrate approximately  $5 \text{ MW}_t$  onto the receiver.

Each heliostat has 25 individual mirror facets totaling  $37.2 \text{ m}^2$  ( $400 \text{ ft}^2$ ) of reflective surface. The facets are mounted on a structure and individually adjusted to provide a concentration ratio of 25 to 1 on the receiver. The structure has motor-driven azimuth and elevation gimbals, which allow it to track the sun during the day.

The heliostats are operated from the control room by the CRTF collector control system. (The CRTF collector control system is separate from the experiment master control subsystem.) The CRTF collector control system analyzes heliostat operating commands from a number of programmed test sequences or from the facility heliostat operator. Control signals are distributed to the heliostats through four heliostat array controllers and four heliostat interface modules. Each heliostat receives azimuth and elevation pointing information once every second and responds with its own status. Commands and data transmitted to the individual heliostats are received and executed by the heliostat control electronics. The electronics keep the drive motor power at the proper level until the gimbal axis encoders indicate that the desired position has been reached.

Table 3.1  
MSEE Data

- Location -- CRTF; on Kirtland Air Force Base, Albuquerque, NM
- Heliostat Field -- Existing field of 221 heliostats each with 400 ft<sup>2</sup> of mirror surface.
- Tower -- Existing concrete tower, 200 ft. high with internal lifting module
- Master control -- EMCON D-2 distributed digital control system with central consoles; separate equipment protection system.
- Receiver -- Refurbished from previous Subsystem Research Experiment.
- o Rating: 5 MW<sub>th</sub>
  - o Salt temperatures: in - 590°F; out - 1000°F (1050°F with propane heater)
  - o Configuration: cavity with door
  - o Absorber: single panel of 3/4 in Incoloy 800 tubes (18 passes, 16 tubes per pass)
  - o Peak flux: 630 kW/m<sup>2</sup> (200,000 Btu/hr - ft<sup>2</sup>)
- Thermal Storage -- Existing from previous Subsystem Research Experiment
- o Rating: 5.8 MW<sub>th</sub> Hr when operating between 590°F and 1000°F
  - o Type: 2-tank
    - Hot tank, internal insulation
    - Cold tank, external insulation
- Steam Generator -- Supplied by Babcock and Wilcox
- o Type: Forced recirculation
  - o 2 units: evaporator and superheater (both U-tube, U-shell) with steam drum separator
  - o Rating: 11,000 lb/hr of steam at 940°F and 1100 psi (3.13 MW<sub>th</sub>)
  - o Prototypical of commercial design
- Turbine Generator -- GE rebuilt unit
- o Marine turbine
  - o 750 kW<sub>e</sub> rating (500 kW<sub>e</sub> under nominal operating conditions)
- Heat Rejection and Feedwater System -- existing at CRTF
- o Feedwater treatment only
  - o 20,000 gallon demineralized water storage
  - o Dry cooling, 7 MW<sub>th</sub> capacity
  - o Spray water heat exchanger to reject heat when turbine not in use or tripped off line

## 3.2 MASTER CONTROL SUBSYSTEM

The master control subsystem (Figure 3.3) consists of an EMCON-D2 for system control and a equipment protection system. A Bailey network 90-system is used to directly control the SGS. Commands and set points are provided by the EMCON master control subsystem to the Network 90 for SGS operation and control. The equipment protection system is an independent hardwired relay shutdown system. These relay trip devices will shut down the receiver or the power generation ends of the MSEE when critical parameters reach preset limit values. These relay units are independent of the EMCON and network 90 control systems. Additionally, an Accurex Data Logger is used to collect and display all the temperature measurements relating to the heat tracing and data instrumentation.

### 3.2.1 EMCON System

The EMCON-D2 is a distributed digital control system consisting of two operator consoles, a host computer with its peripheral hardware, a communication control module, and three process control modules distributed among the subsystems. Two EMCON-D2 operator consoles are located in the CRTF main control room. The host computer is an existing DEC PDP 11/34 unit located in the control room. This computer links the operator with the process control modules, and analyzes data from the control modules for presentation on the operator consoles. The peripheral equipment includes two disk drives, an alarm system, and a data analysis system.

A communication control module links the host computer with the three field-located, process control modules. Each process control module is a small digital computer capable of monitoring a number of instrumentation points, and responding with a number of process control signals. Communications between the control modules and host computer are primarily limited to direct operator commands from the console and critical operating information from the subsystems for console display. This distributed control system reduces the number of instrumentation and control links between the subsystems and control room.

The process control module consists of a digital computer control unit, a multiplexer, an analog-to-digital converter, and a digital-to-analog converter. Analog signals from the process instrumentation are converted to

**DATA ACQUISITION**  
HP 2645A


**DATA DISPLAY SCREENS**  
HP 2645A

**MSEE OPERATION CONTROL**

**HELIOSTAT CONTROL**

**HELIOSTAT OPERATOR CONSOLE**

**ACUREX HEAT TRACE MONITOR**



3-7

Figure 3.3 Master Control Subsystem

digital signals, selected in rotation by the multiplexer, and analyzed by the control unit. The module responds with an appropriate digital control signal which is passed through the multiplexer and sent to the appropriate controller. Each process control module is capable of monitoring 30 analog signals per second, monitoring 95 thermocouples, generating 20 analog control signals, and controlling over 100 on-off switches.

One process control module (PCM 1), located below the receiver in the tower elevator, is dedicated to the control of the receiver. A second module, (PCM 2) located at the base of the tower, controls the heat rejection and electric power generation subsystem. The third module, (PCM 3), located in the control building adjacent to the salt storage tanks, is used to control the thermal storage subsystem and to command the Network 90 controlled steam generation subsystem.

The receiver subsystem PCM will modulate the salt flow rate to the receiver to maintain, as closely as possible, a constant outlet temperature of 1000°F. Individual thermocouples are located on the receiver to measure intermediate salt temperatures. From this information, the control module estimates the flux on the receiver, and feed-forward a signal to the salt control valves at the receiver inlet. The control module also controls the receiver start-up and shutdown purge and drain valves.

Control of the thermal storage subsystem involves the operation of the two salt downcomer flow control valves, cold salt pumps, salt storage tanks and piping heat tracing, and the propane-fired salt heater. The downcomer throttling valves are controlled by the receiver control system to maintain a constant level in the receiver hot surge tank. Salt equipment heat trace temperatures are monitored continuously by the Acurex Data Logger. The propane-fired salt heater is operated intermittently, under manual control, during subsystem checkouts.

Automatic control of the heat rejection and electric power generation subsystem involves the control of the steam and condensate flows to the deaerator, steam flow to the feedwater heater, and the operation of the cooling water, spray water condensate, and feedwater pumps. The EPGS condenser

temperature, level and pressure are monitored by the master control subsystem. The deaerator temperature is maintained by controlling the steam flow from the main steam header. The final feedwater temperature is maintained by controlling the main steam flow to the feedwater heater.

Automatic control of the steam generation subsystem primarily involves the control of steam pressure, steam temperature, drum water level, and the evaporator salt inlet temperature through the network 90 control system. The water level in the drum is controlled by modulating the control valve downstream of the feedwater pump. Control of the main steam pressure is accomplished by modulating the salt flow control valve downstream of the evaporator. Steam temperature is controlled using an attemperator to mix steam from the steam drum with the output of the superheater. The evaporator salt inlet temperature is controlled by monitoring the inlet salt temperature, and modulating the cold salt control valve at the mixing tee between the superheater and evaporator.

### 3.2.2 Network 90 System

The Bailey Network 90 Control System consists of two units, one process control unit (PCU) and one operation interface unit (OIU).

The PCU architecture is based on two key modules, the Controller Module (COM) and the Logic Master. Together, these modules provide a mix of both modulating and sequential control functions including: base, cascade, or ratio PID control, high/low and rate limiters, engineering units conversion, general function generator, square root, summation, multiplication, lead/lag, and transfer select, or, and, not, time delay, and several others. The controller module can service up to four analog and three digital inputs and two analog and four digital outputs. The COM also provides A/D and D/A conversion, alarm limit checking (absolute and deviation) and notification, point quality checking and interlocking.

The Operator Interface Unit (OIU) provides the high level operator interface for the Network 90 system. The OIU consists of a color CRT-based table-top console, with functional keyboard, mass storage device, and console driver electronics.

In operation, the unit performs the system information display and control requirements. The OIU console includes a CRT keyboard and pushbutton hardware for process overview, alarm indicating, loop control, trending, tuning and configuration functions.

The OIU uses microprocessor, memory and I/O modules to support system functions. It furnishes monitoring, supervisory, recording and display capability at centralized or distributed locations, along with engineering functions.

### 3.2.3 Data Acquisition

The DAS utilizes both the EMCON-D2 and an HP-1000. EMCON collects the data and HP-1000 stores and displays data. Data collected by the EMCON system is transmitted to the HP-1000 system on a terminal-to-terminal data link. The tag list for the data to be collected is in a file of 180 tags, which are divided into 6 groups of 30 tags. One group of 30 is transmitted every 10 seconds, giving a total update rate of once a minute. The data are then time tagged with day of the year, hour, minute, second, millisecond. Then the data are stored in a data file and/or displayed on one of six CRTs in a graphical form. Also, the data are transmitted in integer format, not floating point, but they are in engineering units. The data files are divided into eight-hour blocks, so if a test runs longer than eight hours, another eight-hour block is assigned to that test's file. Normally an 8-hour data block is stored in 19 tracks out of a maximum usable 1000 tracks.

The live data can be displayed on the 6 CRTs with 3 tags per screen, a time scale of 3 hours 20 minutes, and a Y-scale displayed of the first tag's display range. The other two tags are displayed using their respective ranges, but the scales are not shown on the plot. When the plot is full the plot scrolls left dropping the oldest 1/4 of the time scale data. This leaves 1/4 of the plot blank for new data. These plots can have hard copies made, but not automatically. The print is done by manual switch selection of each screen and a copy page switch.

Recovery of stored data can be done whenever live data files are not being made. These plots have a slightly different format, three being a maximum of five tags per plot, and the Y scale shown is that of the last tags range. These plots are not displayed on a CRT, but directly generated on the printer/plotter.

### 3.3 RECEIVER SUBSYSTEM

The receiver subsystem (Figure 3.4) captures the insolation redirected from the heliostat field and converts it to thermal energy in the molten salt. The subsystem consists of the receiver absorber panel, cavity enclosure with one vertical aperture door, insulation, heat tracing, cold surge tank, booster pump, hot surge tank, overflow tank, instrumentation, and control valves. The receiver is located at the top of the CRTF tower.

The receiver was tested in a previous subsystem research experiment. Since the initial experiment, the receiver has been refurbished. This refurbishment included instrumentation and control system modifications, minor structural and piping changes, and the replacement of the two original horizontal cavity doors with one vertical aperture door.

The receiver absorber is a single panel with 18 vertical passes having 16 tubes per pass. The tubes are Incoloy 800 with 19 mm (0.75 in.) outside diameter. Purge and drain valves are provided for each pair of passes.

The receiver surge tanks are designed to dampen changes in the salt flow rate and to maintain salt flow through the receiver in the event of a cold salt pump outage. The cold surge tank is pressurized with facility-supplied instrument air to supply the necessary head to force the salt through the receiver in the event of a pump outage, and to provide a surge volume within the tank. The hot surge tank operates at atmospheric pressure, and is vented to an adjacent overflow tank in the event of a control problem in the salt downcomer throttle valve.

The cold salt booster pump takes its suction from the discharge of the cold salt pump and provides the necessary head for the salt as it travels up the tower and through the receiver.

The cold salt line to the receiver starts at the booster pump, rises to the top of the hot storage tank, traverses the distance from the storage tanks to the receiver tower on an elevated pipe bridge, enters the tower, and runs up the east side of the tower in an existing pipe chase to the receiver. The hot salt line leaves the hot surge tank and traverses to the pipe chase. The hot salt downcomer carries the salt to the level of the pipe bridge. The hot salt line traverses the bridge, ending in a control valve which throttles the flow



to the hot storage tank. The salt piping is inclined between the storage tanks and the tower to ensure that the piping system will completely drain. The salt piping is electrically heat traced and insulated with calcium silicate and aluminum sheathing.

The receiver components are listed on Table 3.2; valves are described on Table 3.3; instrumentation is listed on Table 3.4; and control loops are described on Table 3.5.




Figure 3.4. Receiver Subsystem

Table 3.2  
Receiver Subsystem Components

Component	Description	Function	Nominal Operating Condition
Receiver	<ul style="list-style-type: none"> <li>- 18 ft wide x 13 ft high panel</li> <li>- 18 serpentine passes Incoloy 800 tubes</li> <li>- 16 tubes per pass</li> <li>- 3/4 in. dia. tubes</li> </ul>	<ul style="list-style-type: none"> <li>- Heat molten salt with solar energy from heliostat field</li> </ul>	<ul style="list-style-type: none"> <li>- 590°F inlet salt</li> <li>- 1050°F outlet salt</li> <li>- 96,867 lb/hr</li> <li>- 5 MW rating</li> </ul>
Cold salt booster sump	<ul style="list-style-type: none"> <li>- Carbon steel cylindrical tank</li> </ul>	<ul style="list-style-type: none"> <li>- Reservoir for cold salt pump</li> </ul>	<ul style="list-style-type: none"> <li>- 590°F salt</li> <li>- Atmospheric pressure</li> </ul>
Cold salt booster pump	<ul style="list-style-type: none"> <li>- Vertical cantilever type</li> </ul>	<ul style="list-style-type: none"> <li>- Supply additional head to outlet of cold salt pump to provide salt circulation through receiver</li> </ul>	<ul style="list-style-type: none"> <li>- 590°F salt</li> <li>- 96,867 lb/hr</li> </ul>
Cold surge tank	<ul style="list-style-type: none"> <li>- Carbon steel cylindrical tank</li> <li>- 3 ft. dia.</li> <li>- 7 ft. high</li> </ul>	<ul style="list-style-type: none"> <li>- Dampen changes in salt flow rate</li> <li>- Provide emergency salt flow through receiver until solar flux can be removed in the event of pump outage</li> </ul>	<ul style="list-style-type: none"> <li>- Pressurized to 125 psi</li> </ul>
Hot surge tank	<ul style="list-style-type: none"> <li>- Stainless steel cylindrical tank</li> <li>- 2 ft. dia.</li> <li>- 7 ft. high</li> </ul>	<ul style="list-style-type: none"> <li>- Dampen changes in salt flow rate</li> </ul>	<ul style="list-style-type: none"> <li>- Atmospheric pressure</li> </ul>

Table 3.3

## RECEIVER SUBSYSTEM REMOTE OPERATED VALVES

VALVE	MANUFACTURER	SIZE	TYPE	FAIL POSITION	FUNCTION	LOCATION
FCV-101 FCV-102	Valtek	2"	CV	FO	Receiver Flow Control	Near Receiver Lower West Corner
FCV-151	Valtek	2"	CV	FC	Receiver Fill Control Cold Surge Level Control	Above Hot Tank
FCV-161	Valtek	2"	CV	FO	Hot Surge Tank Level Control	Above Hot Tank
FCV-162	Valtek	2"	CV	FC	Hot Surge Tank Level Control (Receiver)	Above Hot Tank
FCV-180 thru FCV-189	Kieley-Mueller	1 1/2"	SV	FC	Receiver Fill and Drain	Below Receiver
FCV-190 thru FCV-198	Kieley-Mueller	1 1/2"	SV	FC	Receiver Purge	Above Receiver
FCV-199	Kieley-Mueller	2"	SV ↑ <i>shutoff valve (also called isolation valve)</i>	FC	Allow Downcomer Backflow During Receiver Fill and Permit Drainage to Cold Storage Tank During Shutdown	Above Hot Tank

CV - Control Valve  
SV - Shutoff Valve  
FO - Fail Open  
FC - Fail Close

Table 3.4

## Receiver Subsystem Instrumentation

Identifier	Description	Control Module	Display Range	Alarm Levels		Dimension	Sampling Period (sec)
				High	Low		
PT-180	Boost Pump Discharge pressure - goes to 310 psi	PCM 3	0-400	350	275	PSI	2
TE-180	Bearing temp not measured at 100% works	PCM 3	0-500	190		°F	10
TE-181	Sump vent temp normally 200-220°	PCM 3	0-1200	350		°F	10
LT-161	Hot surge tank Level normal operation is 20", during	PCM 3	0-100	70	15	inch	2
TE-183	Salt temp normally 1050°F during operation	PCM 1	0-1200	1070	500	°F	10
TE-184	Vent temp normally 100-1150°F	PCM 1	0-1200	400		°F	10
LT-151	Cold surge tank Level normally 30-40" during normal operation	PCM 1	0-100	90	10	inch	10
TE-182	Salt temp	PCM 1	0-1200	750	500	°F	10
PT-182	Pressure normally 150 PSI	PCM 1	0-200	180	10	PSI	10
TE-161	Downcomer outlet temp	PCM 3	0-1200	1070	500	°F	2
Sun	Solar insolation - not in a 90°F, represents power level of sun  Not being tank is vented to atmosphere, therefore it is not pressurized	PCM 3	0-1000			W/M <sup>2</sup>	5

Table 3.4

## Receiver Subsystem Instrumentation

Identifier	Description	Control Module	Display Range	Alarm Levels		Dimension	Sampling Period (sec)
				High	Low		
	Receiver						
PT-181	Inlet pressure <i>-directly related to FT-101 (8.81319, FT-101 should be 30)</i>	PCM 1	0-200	125	10	PSI	10
FT-101	Salt flow rate	PCM 1	0-100	100		KLB/hr	
TE-101	Salt inlet temp <i>not being input now, when called by the calculated valve</i>	PCM 1	0-1200	650	500	°F	2
TE-102	Salt outlet temp	PCM 1	0-1200	1060	500	°F	2
TE-103	Back tube-pass #1 outlet	PCM 1	0-1200	640	500	°F	2
TE-104	Back tube-pass #2 outlet	PCM 1	0-1200	665	500	°F	2
TE-105	Back tube-pass #3 outlet	PCM 1	0-1200	690	500	°F	2
TE-106	Back tube-pass #4 outlet	PCM 1	0-1200	720	500	°F	2
TE-107	Back tube-pass #5 outlet	PCM 1	0-1200	750	500	°F	2
TE-108	Back tube-pass #6 outlet	PCM 1	0-1200	780	500	°F	2
TE-109	Back tube-pass #7 outlet	PCM 1	0-1200	810	500	°F	2
TE-110	Back tube-pass #8 outlet	PCM 1	0-1200	835	500	°F	2
TE-111	Back tube-pass #9 outlet	PCM 1	0-1200	865	500	°F	2
TE-112	Back tube-pass #10 outlet	PCM 1	0-1200	890	500	°F	2
TE-113	Back tube-pass #11 outlet	PCM 1	0-1200	920	500	°F	2

Table 3.4  
Receiver Subsystem Instrumentation

Identifier	Description	Control Module	Display Range	Alarm Levels		Dimension	Sampling Period (sec)
				High	Low		
	Receiver (cont.)						
TE-114	Back tube-pass #11 outlet	PCM 1	0-1200	950	500	°F	2
TE-115	Back tube-pass #12 outlet	PCM 1	0-1200	975	500	°F	2
TE-116	Back tube-pass #13 outlet	PCM 1	0-1200	990	500	°F	2
TE-117	Back tube-pass #14 outlet	PCM 1	0-1200	1010	500	°F	2
TE-118	Back tube-pass #15 outlet	PCM 1	0-1200	1030	500	°F	2
3-18 TE-119	Back tube-pass #16 outlet	PCM 1	0-1200	1050	500	°F	2
TE-120	Back tube-pass #17 outlet	PCM 1	0-1200	1070	500	°F	2
TE-131	Back tube-pass #1 upper	PCM 1	0-1200	645	500	°F	10
TE-132	Back tube-pass #5 upper	PCM 1	0-1200	745	500	°F	10
TE-133	Back tube-pass #8 upper	PCM 1	0-1200	815	500	°F	10
TE-134	Back tube-pass #11 upper	PCM 1	0-1200	915	500	°F	10
TE-135	Back tube-pass #14 upper	PCM 1	0-1200	980	500	°F	10
TE-136	Back tube-pass #17 upper	PCM 1	0-1200	1045	500	°F	10
TE-137	Back tube-pass #2 middle	PCM 1	0-1200	680	500	°F	10

Table 3.4

## Receiver Subsystem Instrumentation

Identifier	Description	Control Module	Display Range	Alarm Levels		Dimension	Sampling Period (sec)
				High	Low		
	Receiver (cont.)						
TE-138	Back tube-pass #6 middle	PCM 1	0-1200	735	500	°F	10
TE-139	Back tube-pass #8 middle	PCM 1	0-1200	825	500	°F	10
TE-140	Back tube-pass #11 middle	PCM 1	0-1200	905	500	°F	10
TE-141	Back tube-pass #14 middle	PCM 1	0-1200	990	500	°F	10
TE-142	Back tube-pass #17 middle	PCM 1	0-1200	1045	500	°F	10
TE-143	Back tube-pass #1 bottom	PCM 1	0-1200	660	500	°F	10
TE-144	Back tube-pass #5 bottom	PCM 1	0-1200	725	500	°F	10
TE-145	Back tube-pass #8 bottom	PCM 1	0-1200	830	500	°F	10
TE-146	Back tube-pass #11 bottom	PCM 1	0-1200	895	500	°F	10
TE-147	Back tube-pass #14 bottom	PCM 1	0-1200	985	500	°F	10
TE-148	Back tube-pass #17 bottom	PCM 1	0-1200	1035	500	°F	10
TE-185	Header-pass #2 outlet	PCM 1	0-1200	665	500	°F	10
TE-186	Header-pass #3 outlet	PCM 1	0-1200	690	500	°F	10



Table 3.4  
Receiver Subsystem Instrumentation

Identifier	Description	Control Module	Display Range	Alarm Levels		Dimension	Sampling Period (sec)
				High	Low		
	Receiver (cont.)						
TE-187	Header-pass #4 outlet	PCM 1	0-1200	720	500	°F	10
TE-188	Header-pass #5 outlet	PCM 1	0-1200	750	500	°F	10
TE-189	Header-pass #6 outlet	PCM 1	0-1200	780	500	°F	10
TE-190	Header-pass #7 outlet	PCM 1	0-1200	810	500	°F	10
TE-191	Header-pass #8 outlet	PCM 1	0-1200	835	500	°F	10
TE-192	Header-pass #9 outlet	PCM 1	0-1200	865	500	°F	10
TE-193	Header-pass #12 outlet	PCM 1	0-1200	950	500	°F	10
TE-194	Header-pass #13 outlet	PCM 1	0-1200	975	500	°F	10
TE-195	Header-pass #14 outlet	PCM 1	0-1200	990	500	°F	10
TE-196	Header-pass #15 outlet	PCM 1	0-1200	1010	500	°F	10
TE-197	Header-pass #16 outlet	PCM 1	0-1200	1030	500	°F	10
TE-198	Header-pass #17 outlet	PCM 1	0-1200	1050	500	°F	10

3-20

Table 3.5  
Receiver Subsystem Control Loops

Controlled Variable	Mode	Set Point	Controller Inputs	Controller Output
Receiver salt flow	Constant flow (start-up & shutdown with receiver control algorithm off scan Constant Outlet Temperature (Receiver control algorithm on))	30 KLB/hr FD-101  1000°F SP. SALT	Flow set point (FD-101) Measured flow (FT-101)  Temperature set point (SP. SALT) Outlet temperature (TE-102) Inlet temperature (TE-101) Salt flow (FT-101) Receiver back tube temperatures (TE-103 thru TE-120)	FCV-101/102 position  FCV-101/102 position
Hot surge tank level	Operation	20 in FCV-161 FCV-162	Surge tank level (LT-161) Level set point	FCV-161 or FCV-162 position (selection based on salt temperature)
Receiving storage tank selection	Operation	750°F	Downcomer salt temperature (TE-161)	TE-161 < 750°F Cold storage tank selected  TE-161 > 750°F Hot storage tank selected
Cold surge tank level	Operation	~85" LT-151	Cold surge tank level (LT-151) Level set point	FCV-151 position

3-21

when TE161 reaches 750°F control goes from FCV161 & FCV162 to only FCV161 (FCV162 closes because you want the salt to go into hot storage tank)

FCV151 is in cascade with LT151

### 3.4 THERMAL STORAGE SUBSYSTEM

The thermal storage subsystem provides a cold salt source for the receiver for daytime operation, and a hot salt source for the steam generator for day and early evening operation. The TSS can also furnish a source of thermal energy for overnight freeze protection of the receiver, steam generator, and salt piping and for early morning plant start-up. The subsystem includes the hot and cold salt storage tanks, propane-fired salt heater, cold salt pump and cold salt sump. The subsystem schematic is shown on Figure 3.15. Major components are described on Table 3.6; valves are listed on Table 3.7; instrumentation is described on Table 3.8; and control loops are given on Table 3.9.

The salt pump is of a vertical cantilever design. The impeller and casing are suspended below the liquid level in a sump; the bearings are located above the liquid level and do not contact the salt.

The hot salt tank employs a unique design. To allow the use of carbon steel in the structural portions of the tank, an internal refractory insulation is used to limit the temperature of the walls, roof, and floor. A waffled Incoloy liner separates the salt and the internal insulation, and the tank foundation is cooled with circulating water to limit the floor temperature. The outside of the tank is insulated in the conventional manner with calcium silicate and aluminum sheathing. The cold salt tank is similar in design to the hot tank except that it does not require the internal insulation and liner due to its lower operating temperature.

3-23




Figure 3- 5. Thermal Storage Subsystem Schematic

Table 3.6  
Thermal Storage Subsystem Components

Component	Description	Function	Nominal Operating Condition
Cold salt storage tank	<ul style="list-style-type: none"> <li>- Carbon steel cylindrical tank</li> <li>- 12.3 ft. dia.</li> <li>- 12.3 ft. high</li> <li>- 15 in fibrous external insulation</li> </ul>	<ul style="list-style-type: none"> <li>- Cold salt storage</li> </ul>	<ul style="list-style-type: none"> <li>- 590°F salt</li> </ul>
Hot salt storage tank	<ul style="list-style-type: none"> <li>- Carbon steel cylindrical shell</li> <li>- 12.3 ft. dia. stainless steel liner</li> <li>- 23.6 ft. high</li> <li>- 13-1/2 in. insulating firebrick between shell and liner</li> <li>- 2 in. fibrous external insulation</li> </ul>	<ul style="list-style-type: none"> <li>- Hot salt storage</li> </ul>	<ul style="list-style-type: none"> <li>- 1050°F salt</li> <li>- Approx. 7 MW<sub>t</sub> hr storage capacity</li> </ul>
Cold salt sump	<ul style="list-style-type: none"> <li>- Carbon steel cylindrical tank</li> <li>- 59 in. dia.</li> <li>- 66 in. deep</li> </ul>	<ul style="list-style-type: none"> <li>- Pump reservoir</li> </ul>	<ul style="list-style-type: none"> <li>- 590°F salt</li> <li>- Atmospheric pressure</li> </ul>
Cold salt pump	<ul style="list-style-type: none"> <li>- Vertical cantilever type</li> <li>- 60 H.P. driver</li> </ul>	<ul style="list-style-type: none"> <li>- Pump salt from cold storage tank to cold salt booster pump, SGS, or propane heater</li> </ul>	<ul style="list-style-type: none"> <li>- 590°F salt</li> <li>- 96,867 lb/hr</li> </ul>

3-24

Table 3.6  
Thermal Storage Subsystem Components - 2

Component	Description	Function	Nominal Operating Condition
Hot salt sump	<ul style="list-style-type: none"> <li>- Stainless steel cylindrical tank</li> <li>- 48 in. dia.</li> <li>- 49 in. deep</li> </ul>	<ul style="list-style-type: none"> <li>- Reservoir for hot salt pump</li> </ul>	<ul style="list-style-type: none"> <li>- 1050°F salt</li> <li>- Atmospheric pressure</li> </ul>
Hot salt pump	<ul style="list-style-type: none"> <li>- Vertical cantilever type</li> <li>- 7-1/2 HP driver</li> </ul>	<ul style="list-style-type: none"> <li>- Provide hot salt circulation through STS</li> </ul>	<ul style="list-style-type: none"> <li>- 1050°F salt</li> <li>- 64,680 lb/hr</li> </ul>
Propane heater	<ul style="list-style-type: none"> <li>- 3 MW propane fired heater</li> <li>- 9 ft. dia. shell</li> <li>- 24 ft. high</li> <li>- One stainless steel heating coil, 2.12 in. dia., 1640 ft. long</li> </ul>	<ul style="list-style-type: none"> <li>- Provide auxiliary salt heating capability</li> </ul>	<ul style="list-style-type: none"> <li>- 59,900 lb/hr salt</li> <li>- 590°F inlet</li> <li>- 1050°F outlet</li> </ul>

3-25

Table 3.7

## THERMAL STORAGE SUBSYSTEM REMOTE OPERATED VALVES

VALVE	MANUFACTURER	SIZE	TYPE	FAIL POSITION	FUNCTION	LOCATION
FCV-201	Valtek	3"	CV	FC	Cold Sump Level Control	Cold Storage Tank Base South Side
FCV-211	Kieley-Mueller	3"	SV	FC	Cold Sump Isolation	Pump House North Side West End
FCV-221	Valtek	3"	CV	FC	Hot Sump Level Control	Hot Storage Tank Southwest Side
FCV-231	Kieley-Mueller	3"	SV	FC	Hot Sump Isolation	Outside Pumhouse Northeast Corner
FCV-241	Valtek	2"	CV	FC	Propane Heater Flow Control	Line to Propane Heater East of FCV-231
FCV-242	Valtek	1 1/2"	SV	FC	Propane Heater Isolation	Top of Hot Tank

Table 3.8  
Thermal Storage Subsystem Instrumentation

Identifier	Description	Control Module	Display Range	Alarm Levels		Dimension	Sampling Period (sec)
				High	Low		
	Cold Storage Tank						
LT-281	Level	PCM 3	0-150	134	15	inch	10
TE-281	Lower temp	PCM 3	0-1200	700	500	°F	10
TE-282	Middle temp	PCM 3	0-1200	700	500	°F	10
TE-283	Upper temp	PCM 3	0-1200	700	500	°F	10
	Hot storage tank						
LT-291	Level	PCM 3	0-200	190	10	inch	10
TE-291	Lower temp	PCM 3	0-1200	1070	500	°F	10
TE-292	Middle temp	PCM 3	0-1200	1070	500	°F	10
TE-293	Upper temp	PCM 3	0-1200	1070	500	°F	10
	Cold salt pump						
LT-201	Sump level	PCM 3	0-60	60	15	inch	2
TE-286	Bearing temp	PCM 3	0-500	190		°F	10
TE-211	Vent temp	PCM 3	0-1200	400		°F	2
	Hot Salt Pump						
LT-221	Sump level	PCM 3	0-48	41	15	inch	2
TE-231	Vent temp	PCM 3	0-1200	400		°F	2



Table 3.9

## Thermal Storage Subsystem Control Loops

Controlled Variable	Mode	Set Point	Controller Inputs	Controller Output
Cold sump level	Operation	23 in FCV-201 (45 in fill)	Sump level (LT-201) Level set point	FCV-201 position - Flow from cold storage tank
Hot sump level	Operation	20 in FCV-221	Sump level (LT-221) Level set point	FCV-221 position - Flow from hot storage tank

### 3.5 STEAM GENERATION SUBSYSTEM

The steam generation subsystem transfers sensible heat from the molten salt to produce superheated steam for the turbine-generator. The subsystem schematic is shown on Figure 3.6. The subsystem includes an evaporator, steam drum, boiler recirculation pump, superheater, and attemperator.

The evaporator and superheater are U-tubes, U-shell heat exchangers, with low pressure salt on the shell side and high-pressure water and steam on the tube side. This shell and tube configuration has been selected to minimize thermal stresses, due to differential expansion, in the tubes and tubesheets.

A conventional steam drum, located above the evaporator, separates water droplets from the saturated steam before the latter enters the superheater, and receives feedwater from the feedwater heater. A forced recirculation design was selected, since it is preferred for power plants requiring daily start-up and shutdown.

The superheater outlet steam can be attemperated by mixing with a small amount of saturated steam from the drum. The salt flow from the superheater to the evaporator is also attemperated to 850°F, when necessary, by mixing with salt flow from the cold tank. This allows chrome-moly piping and fittings, rather than stainless steel, to be used in the evaporator.

Warmup of the steam generation subsystem is accomplished by isolating the subsystem and preheating with the subsystem's electrical heater.

Major subsystem components, valves, instrumentation, and control loops are described on Tables 3.10 through 3.13.

3-30




Figure 3.6 . Steam Generation Subsystem Schematic

Table 3.10. Steam Generation Subsystem Components

Component	Description	Function	Nominal Operating Condition
Evaporator	<ul style="list-style-type: none"> <li>- U-tube/U-shell counterflow heat exchanger</li> <li>- 8 in. dia. chrome - moly shell (salt)</li> <li>- 27 chrome-moly tubes 0.875 in. dia. 68 ft avg. length (water)</li> </ul>	<ul style="list-style-type: none"> <li>- Evaporate subcooled water to produce saturated steam/water mixture</li> </ul>	<ul style="list-style-type: none"> <li>- 850°F salt inlet</li> <li>- 590°F salt outlet</li> <li>- 78,550 lb/hr salt flow rate</li> <li>- Subcooled water inlet</li> <li>- 567°F, 1200 psi saturated steam/water outlet</li> <li>- 2.15 MW rating</li> </ul>
Superheater	<ul style="list-style-type: none"> <li>- U-tube/U-shell counterflow heat exchanger</li> <li>- 6 in. dia. stainless steel shell (salt)</li> <li>- 23 stainless steel tubes 0.500 in. dia. 33 ft. avg. length (steam)</li> </ul>	<ul style="list-style-type: none"> <li>- Heat saturated steam to superheat condition</li> </ul>	<ul style="list-style-type: none"> <li>- 1050°F salt inlet</li> <li>- 906°F salt outlet</li> <li>- 64,680 lb/hr salt flow rate</li> <li>- 567°F 1175 psi saturated steam inlet</li> <li>- 1000°F. 1100 psi superheated vapor outlet</li> <li>- 10,530 lb/hr steam flow rate</li> <li>- 0.98 MW rating</li> </ul>
Steam Drum	<ul style="list-style-type: none"> <li>- Cylindrical pressure vessel with elliptical heads</li> <li>- 24 in ID</li> <li>- 6 ft 10 in overall height</li> <li>- 2 in thick carbon steel</li> <li>- Contains primary cyclone steam separator and primary &amp; secondary steam scrubbers</li> </ul>	<ul style="list-style-type: none"> <li>- Separate steam/water mixture exiting evaporator</li> <li>- Supply saturated steam to superheater</li> <li>- Provide feedwater surge volume</li> </ul>	<ul style="list-style-type: none"> <li>- 567°F</li> <li>- 1200 psi</li> </ul>

3-31

Table 3.10. Steam Generation Subsystem Components - 2

Component	Description	Function	Nominal Operating Condition
Boiler water circulation pump	<ul style="list-style-type: none"> <li>- Canned centrifugal type</li> <li>- 5 HP driver</li> </ul>	<ul style="list-style-type: none"> <li>- Provide circulation of subcooled water from the steam drum to evaporator. Maintain high recirculation rate over full range of operating conditions.</li> </ul>	<ul style="list-style-type: none"> <li>- 560°F</li> <li>- 119 GPM</li> <li>- 111 ft. head</li> </ul>
Start-up heater	<ul style="list-style-type: none"> <li>- Chamber type electric heater</li> <li>- 3 40-kW heating elements</li> <li>- 2 15-kW heating elements</li> </ul>	<ul style="list-style-type: none"> <li>- Raise temperature and pressure of water during cold start-up to avoid salt freeze-up in evaporator</li> <li>- Heat boiler water to maintain temperature and pressure of water/steam system during diurnal hold</li> </ul>	<ul style="list-style-type: none"> <li>- 150 kW during start-up</li> <li>- Cycled during diurnal hold</li> <li>- Bypassed during normal operation</li> </ul>
Steam attemperator	<ul style="list-style-type: none"> <li>- Mixing tee</li> </ul>	<ul style="list-style-type: none"> <li>- Mix saturated steam from steam drum with superheated steam from superheater to control steam delivery temperature to turbine</li> </ul>	<ul style="list-style-type: none"> <li>- 1053 lb/hr dry saturated steam at 567°F</li> <li>- 10,529 lb/hr superheated steam at 1000°F 1100 psi</li> <li>- 11,582 lb/hr delivery steam at 950°F 1100 psi</li> </ul>
Salt attemperator (evaporator inlet)	<ul style="list-style-type: none"> <li>- Mixing tee</li> </ul>	<ul style="list-style-type: none"> <li>- Mix cold salt with superheater outlet salt to limit evaporator inlet salt temperature to 850°F because of Cr-Mo construction</li> </ul>	<ul style="list-style-type: none"> <li>- 64,680 lb/hr at 906°F</li> <li>- 13,870 lb/hr at 590°F</li> <li>- 78,550 lb/hr at 850°F supplied to evaporator</li> </ul>

3-32

Table 3.10. Steam Generation Subsystem Components - 3

Component	Description	Function	Nominal Operating Condition
Salt start-up attemperator (superheater inlet)	<ul style="list-style-type: none"> <li>- Mixing tee</li> </ul>	<ul style="list-style-type: none"> <li>- Mix cold salt with hot salt from hot tank to provide a controlled temperature increase of salt entering superheater during start-up</li> </ul>	<ul style="list-style-type: none"> <li>- Full flow of cold salt at start-up</li> <li>- No cold salt flow during operation</li> </ul>
Heat tracing	<ul style="list-style-type: none"> <li>- Electrical heating element</li> <li>- Inconel sheath</li> </ul>	<ul style="list-style-type: none"> <li>- Maintain heat exchangers and salt piping above the freezing point of salt</li> <li>- Provide freeze protection of feedwater piping and instrumentation during shutdown</li> </ul>	<ul style="list-style-type: none"> <li>- Temperature monitored by thermocouples</li> <li>- Cycle as required</li> </ul>

Table 3. 11  
SGS REMOTE OPERATED VALVES

VALVE	MANUFACTURER	SIZE	TYPE	FAIL POSITION	FUNCTION	LOCATION
FCV-301	Valtek	1"	CV	FO	Evaporator Salt Temperature Control and Cold Salt Fill	SGS Skid West Side South End
FCV-321	Valtek	2"	CV	FO	Main Salt Flow Control	SGS Skid South End
FCV-331	Fisher	1"	CV	FO	Steam Attemperator Temperature Control	SGS Skid North Side Steam Drum
FCV-341	Valtek	1"	CV	FC	Main Salt Fill	SGS Skid West Side Middle
FCV-351	Valtek	2"	CV	FO	Hot Salt Flow Control	Outside Pumphouse Northeast Corner
FCV-381	Kieley-Mueller	1"	SV	FC	Evaporator Salt Drain	SGS Skid West Side Middle
FCV-382	Kieley-Mueller	1"	SV	FC	Superheater Salt Drain	SGS Skid West Side Below Steam Drum
FCV-383	Dresser	4"	SV	FO	Evaporator Water Supply	SGS Skid Southeast Corner
FCV-384	Valtek	2"	SV	FO	Start-up Heater Supply	SGS Skid Below FCV-383

Table 3.12. SGS Instrumentation

Identifier	Description	Control Module	Display Range	Alarm Levels		Dimension	Sampling Period (sec)
				High	Low		
PT-386	Feedwater Pressure	PCM-3/ Bailey	0-1500	1500		PSI	5
TE-386	Temp	PCM-3/ Bailey	0-750	575	500	°F	10
PT-383	Steam Drum Pressure	PCM-3/ Bailey	0-1500	1250	950	PSI	5
TE-383	Fluid temp	PCM-3/ Bailey	0-750	575	500	°F	10
LT-311	Fluid level	PCM-3/ Bailey	-17 to +23	4	-4	inch	2
TE-301	Evaporator Salt inlet temp	PCM-3/ Bailey	0-1200	880	500	°F	2
TE-384	Salt outlet temp	PCM-3/ Bailey	0-1200	640	500	°F	2
PT-384	Salt outlet pressure	PCM-3/ Bailey	0-200			PSI	5
FT-321	Salt flow rate	PCM-3/ Bailey	0-100			KLB/hr	2



Table 3.12. SGS Instrumentation

Identifier	Description	Control Module	Display Range	Alarm Levels		Dimension	Sampling Period (sec)
				High	Low		
	Superheater						
PT-382	Salt inlet pressure	PCM-3/ Bailey	0-200	100		PSI	5
TE-382	Salt inlet temp	PCM-3/ Bailey	0-1200	1070	500	°F	5
TE-331	Steam outlet temp	PCM-3 Bailey	0-1200		910	°F	2
FT-381	Attemperator steam flow	PCM-3/ Bailey	0-2500			lb/hr	5
3-36 FT-382	SGS Cold Salt Supply	PCM-3/ Bailey	0-16			KLB/hr	5
	Steam Delivery						
PT-321	Pressure	PCM-3/ Bailey	0-1500	1150	950	PSI	2
TE-332	Temp	PCM-3/ Bailey	0-1200	990	910	°F	2
FT-311	Flow rate	PCM-3/ Bailey	0-100	12.6	3.2	KLB/hr	2
TE-387	Hot Salt Pump Bearing	PCM-3	0-500	190		°F	10
TE-388	Start-up Heater 5 Element Temp	PCM-3/ Bailey	0-1200	1100	500	°F	10

Table 3.13. SGS Control Loops

Controlled Variable	Mode	Set Point	Controller Inputs	Controller Output
Steam delivery pressure	SGS start-up	1000 psig FCV-491	Delivery pressure (PT-321) pressure set point	FCV-491 position - SGS steam flow
	Boiler following	1100 psig SP. SP	Delivery pressure (PT-321) Pressure set point (SP. SP) Steam flow (FT-311) Salt flow (FT-321)	FCV-321 position - SGS main salt flow
Steam delivery temperature	Operation	950°F SP. ST	Delivery temperature (TE-332) Temperature set point (SP. ST)	FCV-331 position - Steam attemperator flow
Steam drum level	Operation	0 in SP. DL	Drum level (LT-311) Level set point (SP. DL) Feedwater flow (FT-411) Steam flow (FT-311)	FCV-411 position - Feedwater flow
Evaporator salt inlet temperature	Operation	850°F SP. EST	Inlet temperature (TE-301) Temperature set point (SP. EST)	FCV-301 position - Cold salt flow
Boiler water temperature	Diurnal Shutdown	~ 520°F	Circulation heater outlet temperature (TE-388)	Electric immersion heater elements on/off

### 3.6 ELECTRIC POWER GENERATION SUBSYSTEM

The electric power generation subsystem converts the enthalpy in the main steam flow to electricity. The subsystem (Figure 3.7) includes the steam turbine, electric generator, electric power equipment, condenser, condensate pump and storage tank. The electrical one-line diagram is shown on Figure 3.8.

The turbine-generator set is a skid-mounted unit located at the north end of the receiver tower complex at the 80 ft. level (20 ft. below grade). This skid consists of a turbine, generator, and auxiliary equipment. The turbine is a seven-stage, single flow machine, operating at 17,400 rpm. Inlet steam conditions are rated at 940°F and 1050 psia. A single reduction gearbox reduces the turbine shaft speed to the generator speed of 1,200 rpm. The 750 kW<sub>e</sub> generator operates at 450V, and is cooled by circulating water through air cooling coils located above the generator. The turbine-generator auxiliaries include a lubricating oil pump, lube oil cooler, air ejection vacuum pump and mechanical-hydraulic governor. The allowable rate of change in load is 10 percent per minute from 30 to 100 percent of rated capacity.

A shell and tube condenser, supported by a separate frame, is located directly below the turbine. Access to the condenser is on the floor 40 ft. below ground. Condensate from the hot well of the condenser will be transferred to the deaerator when the water level in the deaerator requires makeup. Otherwise, the condensate is pumped to a storage tank. Condensate from this tank is piped back to the condenser hot well when the hot well level requires water.

Major components of the EPGS, valves, instrumentation, and control loops are described on Tables 3.14 through 3.17.




Figure 3.7. Electric Power Generation Subsystem Schematic

3-40




Figure 3.8. MSEE Electric Generator One-Line Diagram

Table 3.14  
Electric Power Generation Subsystem Components

Component	Description	Function	Nominal Operating Condition
Turbine	<ul style="list-style-type: none"> <li>- Axial flow condensing type</li> <li>- 7 stage</li> </ul>	<ul style="list-style-type: none"> <li>- Expand steam to drive electric generator</li> </ul>	<ul style="list-style-type: none"> <li>- 940°F 1050 psig throttle steam</li> <li>- 133°F 2.5 psia exhaust steam</li> <li>- 7800 lb/hr steam flow</li> <li>- 17,443 RPM</li> <li>- 1000 HP</li> </ul>
Electric generator	<ul style="list-style-type: none"> <li>- AC generator</li> <li>- 450 volt, 3 phase</li> <li>- 1200 RPM</li> <li>- Solid state excitor</li> </ul>	<ul style="list-style-type: none"> <li>- Generate electric power</li> </ul>	<ul style="list-style-type: none"> <li>- 750 kW<sub>e</sub> (rating)</li> <li>- 600 kW<sub>e</sub> (maximum in MSEE)</li> <li>- 0.8 power factor rating</li> </ul>
Condenser	<ul style="list-style-type: none"> <li>- Crossflow shell and tube heat exchanger</li> <li>- Rectangular shell (condensate)</li> <li>- 438 tubes, 5/8-in. dia. 7-1/2 ft long (glycol/water coolant)</li> <li>- Cylindrical hot well</li> </ul>	<ul style="list-style-type: none"> <li>- Condense turbine exhaust steam</li> <li>- Provide turbine exhaust vacuum</li> </ul>	<ul style="list-style-type: none"> <li>- 2.5 psia saturated steam inlet</li> <li>- 133°F condensate outlet</li> <li>- 7800 lb/hr steam/water flow</li> <li>- 1200 GPM glycol/water coolant flow</li> </ul>
Condensate pump	<ul style="list-style-type: none"> <li>- Turbine type</li> <li>- 2 stage</li> <li>- 20 HP driver</li> </ul>	<ul style="list-style-type: none"> <li>- Pump condensate from hot well to deaerator</li> </ul>	<ul style="list-style-type: none"> <li>- 133°F water</li> <li>- 260 psi head (mfg rating)</li> <li>- 18 GPM (mfg rating)</li> </ul>

3-41

Table 3.14  
Electric Power Generation Subsystem Components

Component	Description	Function	Nominal Operating Condition
Air exhaust pump	<ul style="list-style-type: none"> <li>- Nash vacuum pump</li> <li>- 5 HP driver</li> </ul>	<ul style="list-style-type: none"> <li>- Provide condenser vacuum</li> </ul>	<ul style="list-style-type: none"> <li>- 5 in Hg condenser pressure (ABS)</li> <li>- 75 CFM (mfg. rating)</li> </ul>
Electric oil pump	<ul style="list-style-type: none"> <li>- Viking gear pump</li> </ul>	<ul style="list-style-type: none"> <li>- Provide bearing oil pressure during turbine start-up and shutdown (turbine-driven pump provides oil pressure during operation)</li> </ul>	<ul style="list-style-type: none"> <li>- Off during operation</li> </ul>
Cooling tower pump	<ul style="list-style-type: none"> <li>-Aurora centrifugal pump</li> </ul>	<ul style="list-style-type: none"> <li>- Provide coolant circulation through oil cooler</li> </ul>	<ul style="list-style-type: none"> <li>- 35 psi head (mfg. rating)</li> <li>- 120 GPM (mfg. rating)</li> </ul>
Wet cooling tower	<ul style="list-style-type: none"> <li>-Fan forced wet cooler</li> <li>-1/2 HP fan motor</li> </ul>	<ul style="list-style-type: none"> <li>- Reject oil coolant heat</li> </ul>	<ul style="list-style-type: none"> <li>- 110°F coolant outlet temp</li> </ul>

Table 3.15  
EPGS REMOTE OPERATED VALVES

VALVES	MANUFACTURER	SIZE	TYPE	FAIL POSITION	FUNCTION	LOCATION
FCV-501	Valtek	2"	SV	FC	Turbine Steam Isolation	TWR Level 80 North Turbine Northeast Corner
FCV-511	Asco	1/2"	SV	FC	Hotwell Overflow	TWR Level 60 North Condenser Platform Northwest
FCV-512	Asco	3/4"	SV	FC	Hotwell Make-up	TWR Level 80 Northeast Condensate Storage Tank
FCV-521	Masoneilan	2"	CV	FO	Oil Cooler Water Flow Control	TWR Level 80 North Turbine/Generator Overhead
FCV-541	Asco	3/4"	SV	FC	Condenser Storage Tank Make-up	TWR Level 80 Northeast Condensate Storage Tank
FCV-551	Asco	1/2"	SV	FC	Condenser Recirculation	TWR Level 60 North Condenser Platform Northwest
TVM	GE w/auma Actuator	1 1/2"	CV	FC	Turbine Steam Supply Throttle	Turbine North Side
SNM	GE	--	CV	--	Turbine Sync Speed Control	Turbine Center
Fcv-561	ASCO	1/2"	SV	FO	Close throttle valve in emergency trip (dumps hydraulic oil)	Turbine



TABLE 3.17. EPGs INSTRUMENTATION

IDENTIFIER	DESCRIPTION	CONTROL MODULE	DISPLAY RANGE	ALARM HIGH	LEVELS LOW	DIMENSION	SAMPLING PERIOD (sec)
Turbine							
PT-581	Steam Supply Pressure	PCM 2	0-1500		800	PSI	5
PT-582	Steam Seal Pressure	PCM 2	0-1500			PSI	5
TE-581	Exhaust Temp	PCM 2	0-500			°F	5
TT-583	Steam Supply Temp	PCM 2	0-1200	990	800	°F	5
TT-501	Outboard Bearing Oil Temp	PCM 2	0-500	170	110	°F	5
TT-502	Inboard Bearing Oil Temp	PCM 2	0-500	170	110	°F	5
TE-503	Gear Outboard Bearing Oil Temp	PCM 2	0-500	170	110	°F	5
AZT-581	Vibration	PCM 2	0-100	100		PCT (0-5 g)	5
Generator							
JT-581	Power	PCM 2	0-960			kw	5
ET-581	Voltage	PCM 2	0-600	480	450	Volt	5
IT-581	Current	PCM 2	0-1200			Amp	5
PFT-581	Power Factor	PCM 2	0-1.0	1.0	0.85	PCT	5
VT-581	VARs	PCM 2	0-960			KVA	5
ST-582	Speed	PCM 2	0-1500	1270		rpm	5
ST-581	Frequency	PCM 2	0-100	60	40	PCT (55-65 Hz)	5
TT-510	Stator Winding 1 Temp	PCM 2	0-500	260		°F	5
TT-511	Stator Winding 2 Temp	PCM 2	0-500	260		°F	5
TT-512	Stator Winding 3 Temp	PCM 2	0-500	260		°F	5
TT-513	Stator Winding 4 Temp	PCM 2	0-500	260		°F	5
TT-514	Stator Winding 5 Temp	PCM 2	0-500	260		°F	5
TT-515	Stator Winding 6 Temp	PCM 2	0-500	260		°F	5
TE-508	Cooling Air Outlet Temp	PCM 2	0-500	100		°F	5
TT-507	Outboard Bearing Oil	PCM 2	0-500	170	110	°F	5
TE-505	Gear Outboard Bearing Oil Temp	PCM 2	0-500	170	110	°F	5
TE-506	Gear Inboard Bearing Oil Temp	PCM 2	0-500	170	110	°F	5
PT-502	Condenser Pressure	PCM 2	0-30	15		In Hg	5
PT-583	Condensate Pump Discharge Pressure	PCM 2	0-400	300	240	PSI	5
LT-511	Hot Well Level	PCM 2	0-15	16	8	Inch	2
TE-582	Cooling Tower Pump Discharge Temp	PCM 2	0-500	100	40	°F	5
PT-531	Oil Pump Discharge Pressure	PDM 2	0-200	100	55	PSI	5
TT-521	Bearing Oil Supply Temp	PCM 2	0-500	140	100	°F	2
PT-501	Bearing Oil Supply Press.	PCM 2	0-50	40	10	PSI	5

Table 3-17  
EPGS Control Loops

Controlled Variable	Mode	Set Point	Controller Inputs	Controller Output
Condenser hot well level	Remote operation (TCP. MS on) (EN.HLC on)	9 in min 14 in max	Hot well level (LT-511)	FCV-512 open/close - makeup FCV-511 open/close - dump
Condensate storage tank level	Operation	12 in min 30 in max	Storage tank level (LS-541)	FCV-541 open/close - supply from cycle fill pump  FCV-542 open/close - CMUP Stand pipe air overpressure
Turbine/generator oil temperature	Remote operation	125°F FCV-521	Oil temperature (TT-521)	FCV-521 position - cooling water flow

### 3.7 HEAT REJECTION AND FEEDWATER SUBSYSTEM

The heat rejection and feedwater subsystem rejects waste heat to the atmosphere, pressurizes and heats the condensate to the final feedwater temperature. The subsystem (Figure 3.9) includes the cooling towers, circulating water pump, deaerator, spray water heat exchanger, spray water pump, feedwater pump, feedwater heater, demineralizers, chemical feeders, water analyzers, and condensate makeup pump.

The cooling towers consist of six forced-draft, finned-tube water-to-air heat exchangers. They originally were designed as Freon condensers for refrigeration systems.

The deaerator is used as a direct contact feedwater heater and deaerator and to reject steam generated by the SGS. It is a horizontal, cylindrical pressure vessel, designed to operate at 250 psia and 400°F. It includes a steam header with mixing spargers near the bottom of the tank, water spray nozzles across the top, and two immersion electric heaters. Feedwater, stored in the deaerator, is heated by steam from a branch off the SGS mainline to the turbine. The feedwater is circulated by a spray water pump at 400 gpm from the bottom of the deaerator to the spray nozzles in the vapor space at the top of the deaerator where the water condenses the steam and is thereby heated. Condensate from the turbine condenser, blended into this spray water, is also heated to 400°F and deaerated.

The feedwater heater is a vertical, cylindrical pressure vessel with an internal steam condensing coil. Feedwater from the deaerator is heated on the tube side as steam from a branch of the SGS mainline condenses on the shell side. The saturated liquid from the coil is cascaded down to the deaerator through a steam trap. Main steam is used for feedwater heating in the feedwater heater and the deaerator because there are no external extraction points on the turbine.

Major components, valves, instrumentation, and control loops are described on Tables 3.18 through 3.21.

3-47




Figure 3.9 . Heat Rejection and Feedwater Subsystem Schematic

Table 3.18  
Heat Rejection and Feedwater Subsystem Components

Component	Description	Function	Nominal Operating Condition
Feedwater heater	<ul style="list-style-type: none"> <li>- Shell and coiled tube counter-flow heat exchanger</li> <li>- 35 in ID 2.5 in thick carbon steel shell (feedwater)</li> <li>- 4 ft 8 in overall height</li> <li>- 30 coiled tubes 0.500 in. dia. 43 ft long (steam)</li> </ul>	<ul style="list-style-type: none"> <li>- Raise feedwater temperature to SGS inlet condition</li> </ul>	<ul style="list-style-type: none"> <li>- 950°F superheated steam inlet</li> <li>- 545°F saturated liquid outlet</li> <li>- 2150 lb/hr steam flow rate</li> <li>- 401°F feedwater inlet</li> <li>- 550°F feedwater outlet</li> <li>- 11,582 lb/hr feedwater flow rate</li> <li>- 0.59 MW heat transfer</li> </ul>
Deaerator	<ul style="list-style-type: none"> <li>- Horizontal tank</li> <li>- 5 ft ID</li> <li>- 12 ft long</li> <li>- Contains 15 submerged mixing nozzles, 1 overhead spray nozzle, 2 147-kW electric immersion heaters</li> </ul>	<ul style="list-style-type: none"> <li>- Degasify condensate</li> <li>- Heat condensate for delivery to feedwater heater</li> <li>- Provide alternate steam dump when turbine is not operating</li> </ul>	<ul style="list-style-type: none"> <li>- 401°F</li> <li>- 250 psi</li> <li>- 0.63 MW heat transfer</li> </ul>
Spray water heat exchanger	<ul style="list-style-type: none"> <li>- Shell and tube heat exchanger</li> <li>- 24 in. dia. shell</li> </ul>	<ul style="list-style-type: none"> <li>- Reject excess heat from deaerator when utilized as alternate steam dump</li> </ul>	<ul style="list-style-type: none"> <li>- No flow from deaerator during normal operation</li> </ul>

Table 3.18  
Heat Rejection and Feedwater Subsystem Components - 2

Component	Description	Function	Nominal Operating Condition
Feedwater pump	<ul style="list-style-type: none"> <li>- High speed centrifugal type</li> <li>- 18,770 pump RPM</li> <li>- 150 HP driver</li> </ul>	<ul style="list-style-type: none"> <li>- Provide high pressure feedwater to the steam generator (through the feedwater heater)</li> </ul>	<ul style="list-style-type: none"> <li>- Inlet: 250 psi, 401°F water</li> <li>- 1450 psi head (mfg rating)</li> <li>- 60 GPM (mfg rating)</li> </ul>
Spray water pump	<ul style="list-style-type: none"> <li>- Vertical turbine type</li> <li>- 3 stage</li> <li>- 7-1/2 HP driver</li> </ul>	<ul style="list-style-type: none"> <li>- Provide circulation from deaerator to spray water heat exchanger and/or its bypass and return to deaerator overhead spray nozzle</li> </ul>	<ul style="list-style-type: none"> <li>- 401°F</li> <li>- 26 psi head (mfg rating)</li> <li>- 300 GPM (mfg rating)</li> </ul>
Cooling water pump	<ul style="list-style-type: none"> <li>- Centrifugal type</li> <li>- 40 HP driver</li> </ul>	<ul style="list-style-type: none"> <li>- Provide glycol/water circulation for spray water heat exchanger - cooling tower - condenser circuit</li> </ul>	<ul style="list-style-type: none"> <li>- 132°F glycol/water</li> <li>- 40 psi head</li> <li>- 1200 GPM</li> </ul>
Cooling towers	<ul style="list-style-type: none"> <li>- 6 units</li> <li>- Forced draft, finned-tube, glycol/water-to-air heat exchangers</li> </ul>	<ul style="list-style-type: none"> <li>- Reject waste heat to atmosphere</li> </ul>	<ul style="list-style-type: none"> <li>- 94°F air</li> <li>- 132°F glycol/water inlet</li> <li>- 120°F glycol/water outlet</li> <li>- 2.4 MW heat rejection</li> </ul>

3-49

Table 3.19  
HRFS REMOTE OPERATED VALVES

VALVE	MANUFACTURER	SIZE	TYPE	FAIL POSITION	FUNCTION	LOCATION
FCV-401	Fisher	2"	CV	F0	Feedwater Pump Pressure Control	Southwest of Deaerator
FCV-411	Kieley-Mueller	2"	CV	FC	Feedwater Flow Control	SGS Skid Northeast
FCV-421	Kieley-Mueller	2"	CV	F0	Feedwater Heater Temperature Control	Above Feedwater Heater
FCV-431	Kieley-Mueller	2"	CV	FC	Main Steam Pressure Control	Southwest of Deaerator
FCV-432	Kieley-Mueller	3"-3 way	CV	To SWHX	Deaerator Pressure Control	Between Deaerator and Spray Water Heat Exchanger
FCV-471	Valtek	1"	CV	FC	Condensate Control to Deaerator	Above North Door to Spray Water Pump Room
FCV-483	Atkomatic	1"	SV	--	Deaerator Vent Block	Above Deaerator
FCV-484	Atkomatic	1/4"	SV	--	Deaerator Vent Bypass	Above Deaerator
FCV-485	ASCO	2"	SV	--	Demineralized Water Storage Tank Fill	Above Culligan Beds
FCV-491	Kieley-Mueller	2"	CV	FC	SGS Steam Delivery Control During Start-Up	North End of SGS Skid

2-50

TABLE 3.20. HRFS INSTRUMENTATION

IDENTIFIER	DESCRIPTION	CONTROL MODULE	DISPLAY RANGE	ALARM HIGH	ALARM LOW	DIMENSION	SAMPLING PERIOD (sec)
Main Steam							
PT-431	Pressure	PCM 2	0-1500	1200	900	PSI	2
TE-483	Temp	PCM 2	0-1200	990	850	Inch	10
Deaerator							
PT-432	Pressure	PCM 2	0-400	250	200	PSI	2
TE-451	Fluid Temp	PCM 2	0-500	400	300	°F	2
TE-481	Steam Temp	PCM 2	0-500	400	300	°F	10
LT-471	Fluid Level	PCM 2	0-30	30	10	Inch	2
Spray Water							
PT-482	Pressure	PCM 2	0-400	300	200	PSI	5
FT-482	Flow Rate	PCM 2	0-160			KLB/hr	5
TE-482	Temp	PCM 2	0-500	445		°F	10
FT-481	Feed/Spray Water Flow Rate	PCM 2	0-160			KLB/hr	5
Feedwater							
PT-481	FWP Supply Pressure	PCM 2	0-400		170	PSI	5
PT-401	FWP Discharge Pressure	PCM 2	0-1500	1400	900	PSI	2
PT-484	FWP Coolant Pressure	PCM 2	0-100			PSI	5
PT-483	FWH Outlet Pressure	PCM 2	0-1500	1230	1180	PSI	5
FT-411	Flow Rate	PCM 2/	0-160 Bailey			KLB/hr	2
FT-421	FWH Outlet Temp	PCM 2	0-750	600	400	°F	2
Cooling Water							
TE-484	SWHX Inlet Temp	PCM 2	0-500	130		°F	10
TE-486	Tower Outlet Temp	PCM 2/	0-500	110	32	°F	10



Table 3.21. HRFS Control Loops

Controlled Variable	Mode	Set Point	Controller Inputs	Controller Output
Feedwater temp.	Operation	520° 540°F FCV-421	Feedwater temperature (TE-421) Temperature set point	FCV-421 position - Feedwater heater Steam supply flow
Feedwater pressure	Operation	1250 psig FCV-401	Feedwater pressure (PT-401) Pressure set point	FCV-401 position - FWP recirculation flow
Steam delivery pressure	Manual salt flow GSTAT off	1080 psig PT-431	Delivery pressure (PT-431) Pressure set point	FCV-431 position - Deaerator steam dump
Deaerator pressure	Operation - Desuperheating GSTAT off	233 psig PT-432	Deaerator pressure (PT-432) Pressure set point	FCV-432 position - Deaerator dump to SWMX
	Boiler following GSTAT on	233 psig PT-432	Deaerator pressure (PT-432) Pressure set point	FCV-431 position - Deaerator steam supply
Deaerator temp.	Start-up	390°F DTC 451 DTC 452	Deaerator temperature (TE-451) Temperature set point	DTC-451/452 on/off - Electric heater control
Deaerator level	Operation	15 in <i>controls deaerator level</i> FY-472 (14 in backup during turbine operation)	Deaerator level (LT-471) Level set point	FY-472 condensate - Makeup pump stroke position
	Turbine Operation	15 in FCV-471	Deaerator level (LT-471) Level set point	FCV-471 position - Turbine condensate return from hot well

3-52

*DEAERATOR  
OPERATION  
FY-472*

### 3.8 SYSTEM TRIPS

#### 3.8.1 Equipment Protection Subsystem

The Equipment Protection Subsystem (EPS) is a hard-wired system using dedicated sensors and is designed to save the MSEE in the event of any potentially unsafe condition. Subsequent to the EPS placing the system in a "safe" condition, operator action is required to shut the system down or to change into any other mode. The trip list for the EPS, including actions taken by the EPS and subsequently to be taken by the operator, are shown on Table 3.22, subdivided by subsystem.

#### 3.8.2 Turbine/Generator Trips

Trips built into the turbine/generator are given on Table 3.2.3. Definitions and guidelines are given below.

##### A. Definitions

1. Turbine Trip - Immediate turbine steam shutoff - manual or auto.
2. Turbine Shutdown - Gradual turbine steam shutoff - manual.
3. Generator Trip - Generator circuit breaker opened - manual or auto.

##### B. Steam reactions to trips

1. Anticipated - Steam control maintained manually or auto.
2. Upset - Reliance on auto steam control - SGS salt flow will stop and HRFS will attempt to desuperheat steam. Probable HRFS and SGS safety valve lifting if upset is uncontrolled.

C. Trip interlocks

1. A generator breaker trip always initiates a turbine SVC trip (auxiliary relay 32x closes FCV-501) and an EPST TR-586 (32x).
2. A generator breaker trip always initiates a turbine T.V. reset (auxiliary relay 32x resets T.V. closed) w/ZT-581 '0' open.
3. A turbine T.V. reset and an EPS 2 & 3 reset will reopen FCV-501 unless manually closed (or tripped).

D. All auto trips should be carefully reviewed - determine the cause of the trip and correct the problem before resuming operations.

E. Fail-safe follow-through guidelines

These guidelines present items of concern to fail-safe the EPGS upon a major component failure, after a trip that did not function, or to back up an auto trip. Intimate familiarity with these guidelines is mandatory before EPGS operation to insure safe operation, both from a personnel and equipment standpoint.

1. Three items are of major concern to fail-safe the EPGS and MSEE operating systems:
  - a. Steam over-pressurization
  - b. Turbine trip
  - c. Generator trip
2. Steam system reactions to turbine trips:
  - a. Over-pressurization
  - b. Possible HRFS/D-D & SGS/steam drum safety valve lifting
  - c. Desuperheating by HRFS/FCV-431 switchover to steam control to dump steam to D/D
  - d. FCV-432 D/D heat dump through SWHX and dry cooling tower

3. Turbine tripping is redundant-designed and may be fully utilized with these four trips:

- a. Actuate ET emergency trip FCV-561 (oil trip)
- b. Open generator breaker with breaker C.S. (electric trip)
- c. Actuate EPS T-G trip button from control room (EPS backup)
- d. Manually close throttle valve with hand wheel (manual)

4. Turbine-generator trip verification:

- a. ST-582 speed decreasing
- b. PT-532 hydraulic oil pressure decreasing (T.V. trip)
- c. PT-581 steam pressure drops to zero (FCV-501 trip)
- d. Generator breaker open - green light on

NOTE

EOP operation is not mandatory upon a turbine trip since the shaft driven oil pump provides adequate oil flow for turbine coast down.

5. Generator trips are redundant-designed with turbine trips. Be aware that:

- a. EPGS UPS provides emergency backup C/B trip power
- b. Exciter voltage shutdown local disconnect switch shuts down all of the generator electrical power.

TABLE 3.22. EQUIPMENT PROTECTION SYSTEM  
RECEIVER SUBSYSTEM TRIPS

TRIP IDENTIFIER	TRIP CONDITION	INSTRUMENT IDENTIFIER	TRIP LEVEL	ACTION REQUIRED
--	Operator Manual Trip	--	N/A	EPS - Defocus Heliostats
TR-181	Receiver Salt Outlet Temp High	TE-102A	1080°F	Operator - Control Receiver From The EMCON Console
TR-184	Receiver Tube Temp High During Hot Salt Production	TE-140A and TE-102A	925°F >750°F	
TR-187	Loss of Receiver Door Open Signal	ZSH-DR	Contact Open	
TR-182	Boost Pump Pressure Low During Hot Salt Production	PT-180A and TE-102A	250 PSIG >750°F	EPS - Defocus Heliostats - Close FCV-151 After Time Delay
TR-183	Receiver Salt Inlet Pressure Low During Hot Salt Production	PT-181A and TE-102A	8 PSIG >750°F	Operator - Shutdown Receiver from EMCON Console
TR-185 Heliostats	Hot Surge Tank Level High	LF-161A or TE-184A	80 In 300°F	EPS - Defocus - Close FCV-101 and FCV-102 After Time Delay  Operator - Shutdown Receiver From EMCON Console

TABLE 3.22. EQUIPMENT PROTECTION SYSTEM  
 RECEIVER SUBSYSTEM TRIPS  
 (Continued)

TRIP IDENTIFIER	TRIP CONDITION	INSTRUMENT IDENTIFIER	TRIP LEVEL	ACTION REQUIRED
TR-186	Boost Pump Sump Level High	TE-181A	400°F	EPS - Defocus Heliostats - Time Delay - Close FCV-151 - Turn Off Cold Salt Boost Pump - Turn Off Hot Salt Pump  EMCON (Automatic) - Maintain Control of Receiver and HRFS  Operator - Shut Down the Plant From the EMCON Console

TABLE 3.22. EQUIPMENT PROTECTION SYSTEM  
 THERMAL STORAGE SUBSYSTEM TRIPS  
 (Continued)

TRIP IDENTIFIER	TRIP CONDITION	INSTRUMENT IDENTIFIER	TRIP LEVEL	ACTION REQUIRED
TR-281	Hot Salt Sump Level High	LT-221A or TE-231A	40 In  300°F	EPS - Close Sump Insolation Valve FCV-231  Operator - Allow Time for Hot Salt Pump Operations To Bring Sump Level Down - Shut down SGS, HRFS, and EPGS From EMCON Console
TR-282	Cold Salt Sump Level High	LT-201A or TE-211A	55 In  350°F	EPS - Close Sump Insolation Valve FCV-211 - Defocus Heliostats  Operator - Allow Time for Cold Salt Pump Operations To Bring Sump Level Down - Shut down the Plant From The EMCON Console

TABLE 3.22. EQUIPMENT PROTECTION SYSTEM  
 STEAM GENERATOR SUBSYSTEM TRIPS  
 (Continued)

TRIP IDENTIFIER	TRIP CONDITION	INSTRUMENT IDENTIFIER	TRIP LEVEL	ACTION REQUIRED
TR-381	Steam Drum Level Low	LT-311A	-10 In	EPS - Close FCV-501 - Open Generator Circuit Breaker - Turn Off FWP (Drum Level High only)  EMCON (Automatic) - Dump Steam To Deaerator - Maintain Control of HRFS  Network 90 - Shut Off Salt Flow (Close FCV-301, 341, and 351) - Turn Off BWCP (Drum Level Low only)  Operator - Shut Down SGS, HRFS, and EPGS From EMCON Console
TR-383	Steam Drum Level High and Water Hot	LT-311A and TE-383A	+17 In >250°F	Network 90 - Shut Off Salt Flow (Close FCV-301, 341, and 351) - Turn Off BWCP (Drum Level Low only)  Operator - Shut Down SGS, HRFS, and EPGS From EMCON Console
TR-382	Boiler Water Circulation Pump Failure	Motor Current Sensor	Off	EPS - Close FCV-501 - Open Generator Circuit Breaker  EMCON (automatic) - Dump Steam to Deaerator - Maintain control of HRFS  Network 90 - Shut Off Salt Flow (Close FCV-501, 341, and 351)  Operator - Shut down SGS, HRFS, and EPGS from EMCON console



TABLE 3.22. EQUIPMENT PROTECTION SYSTEM  
EPGS TRIPS  
(Continued)

TRIP IDENTIFIER	TRIP CONDITION	INSTRUMENT IDENTIFIER	TRIP LEVEL	ACTION REQUIRED
	Turbine Overspeed	OST	1320 RPM Generator	EPS - Close FCV-501 Open Generator Circuit Breaker
	Turbine Back Pressure High	TBPT	5 PSIG	
TR-584	Generator Bearing Temp High	TS-501A	180°F	EMCON (Automatic) - Dump Steam to Deaerator - Maintain Control of HRFS
TR-585	Generator Cooling Air Temp High	TS-502A	122°F	Operator - Control System From EMCON Console - Reduce Steam Flow
TR-586	Generator Circuit Breaker Trip		-Manual -Low/high Voltage -Low/high frequency	- Shut Down If Necessary
TR-587	Turbine Vibration High	AZT-581	5g	
TR-588	Steam Energy Low	TE-332 or PT-581A	750°F 770 PSI	
TR-583	Turbine Oil Pressure	PS-501A (LUBE) or PS-531A (HYDR)	6 PSI 50 PSI	
TR-582	Manual T/G Emergency Trip	Control Room PB	Operator Initiate	

TABLE 3.22. EQUIPMENT PROTECTION SYSTEM  
 MASTER CONTROL SUBSYSTEM TRIPS  
 (Continued)

TRIP CONDITION	ACTION REQUIRED
PCM 1 Microcomputer Failure	EPS
- Loss of Receiver Displays	- Defocus Heliostats
- Loss of Salt Auto Flow Control	- Close FCV-151 After Time Delay
- Loss of Cold Surge Tank Auto Level Control	Operator
	- Control Receiver from PCM 1
	- Drain Receiver If Necessary
PCM 2 Microcomputer Failure	EPS
- Loss of HRFS and EPGS Displays	- Turn Off Hot Salt Pump
- Loss of Feedback Control Loops	- Close FCV-301, FCV-341, and FCV-351
	- Turn Off FWP
	- Close FCV-501 and FCV-491 After Steam Pressure Drops
	- Open Generator Circuit Breaker
	- Turn Off Condensate Pump
	Operator
	- Shut Down SGS From Console
	- Shut Down HRFS and EPGS From PCM 2
PCM 3 Microcomputer Failure	EPS
- Loss of TSS Displays	- Defocus Heliostats
- Loss of Feedback Control Loops	- Time Delay
- Loss of SGS Displays	- Close FCV-211
	- Close FCV-231
	- Turn Off Hot and Cold Salt Pumps
	- Turn Off Cold Salt Boost Pump
	- Close FCV-151
	- Close FCV-501
	- Open Generator Circuit Breaker
	EMCON (Automatic)
	- Dump Steam To Deaerator
	- Maintain Control of HRFS
	Network 90 (Automatic)
	- Interlocks Will Close FCV-301, FCV-341, and FCV-351
	Operator
	- Shut Down SGS From Network 90 Console
	- Shut Down Receiver, HRFS, and EPGS from EMCON Console

TABLE 3.22. EQUIPMENT PROTECTION SYSTEM  
 MASTER CONTROL SUBSYSTEM TRIPS  
 (Continued)

TRIP CONDITION	ACTION REQUIRED
Simultaneous Failure of PCM 1, 2, and 3 Microcomputers - Loss of All Subsystem Control	EPS - Defocus Heliostats - Time Delay - Close FCV-211
CCM Microcomputer Failure - Loss of PCM/Host Computer Communication Lin - Loss of Console Displays - Loss of Console Control Capability - Loss of Sequencing Operations Involving More Than One PCM	- Close FCV-231 - Turn Off Hot and Cold Salt Pumps - Turn Off Cold Salt Boost Pump - Close FCV-151 - Turn off FWP - Close FCV-501 and FCV-491 After Steam Pressure Drops - Open Generator Circuit Breaker - Turn Off Condensate Pump
Operator Remote Manual Trip	Operator - Shut Down the Subsystems From PCM 1, 2, and 3 and Network 90
EMCON Host Computer Failure	PCMs and CCM Continue To Operate and Control The Plant  Operator - Shut Down The Subsystems From PCM 1, 2, and 3

Table 3.23. TURBINE/GENERATOR TRIP LIST

MODE	DESCRIPTION	INITIATION
Manual	MGBT - Manual generator breaker trip	Breaker switch opened at local or remote generator control panel
Manual	ET - Emergency trip	ET "on" at EMCON console or local trip button actuated
Manual/auto	SVC - Stop valve closure	Close FCV-501
Manual/auto	OST - Overspeed trip	Local OST button
Manual	MTVC - Manual throttle valve closure	Close throttle valve (TVM)
Auto	GBT - Generator breaker trip	a. Reverse power b. Ground fault c. Overcurrent



## Section 4 CONSOLE OPERATION

A detailed description of the MSEE control system and its operation is contained in this section. The subsystem architecture and functional description was given in Section 3.2.

### 4.1 EMCON CONSOLE DISPLAY SCREEN

The EMCON color console provides a variety of displays arranged in a hierarchy of system level, subsystem level, group level, and individual point level. For the operation of MSEE the console displays used most often include system and subsystem level color graphic displays, 4 over 4 group displays, 22 line group displays and the single loop displays. An example of each of these types of displays is shown in Figures 4.1 through 4.5.

The graphic displays are used primarily to observe the status of the entire system or an individual subsystem, particularly to locate trouble areas in the operation. The group level 4 over 4 and 22 line displays are used to observe process variables and to operate controls in a particular area within the system. The single loop display is used to analyze the behavior of an individual process variable and to perform tuning of controls.

The lower left-hand corner of the screen is called the KEYBOARD ECHO AREA. It is here where the keys are displayed as they are hit. Keys are usually displayed in GREEN. Error messages are printed in the keyboard echo area in RED.

The lower right-hand corner of the screen is used to display the current time and date. When the Console KEYLOCK is UNLOCKED (Console Unprotected), the time and date are displayed in RED. When the Keylock is LOCKED, the time and date are displayed in YELLOW.


The remainder of the screen (46 lines high by 80 columns wide) is available for the various displays.

The status of each point (tag name) determines the color in which it is displayed:

- 1. WHITE - OFF-LINE
- 2. GREEN - NORMAL
- 3. BLUE - OFF SCAN, BAD SENSOR, or I/O ERROR
- 4. RED - LOW or HIGH ABSOLUTE ALARM, RATE-of-CHANGE ALARM
- 5. YELLOW - DEVIATION ALARM

Figure 4.1. System Graphics

4-3









Figure 4.3. 4 over 4 Group



4-5

COPY

Figure 4.4 22 Line Group

01	FCV100	0. FSI	RCVR	BOILER	FLOW	CONTROL	H	100.0	L	0.0	PCM	1
02	FCV101	.2PCT	XXX RCVR	SALT	FLOW	CONTRL	H	100.0	L	.0	PCM	1
03	FCV102	.1PCT	XXX RCVR	SALT	FLOW	CONTRL	H	100.0	L	.0	PCM	1
04	FCV151	.0PCT	XXX RCVR	COLD	SURGE	TANK	H	100.0	L	.0	PCM	1
05	FCV161	.8IN	XXX RCVR	DWNCMR	HOT	TANK	H	70.0	L	15.0	PCM	3
06	FCV162	.8IN	XXX RCVR	DWNCMR	COLD	TANK	H	70.0	L	15.0	PCM	3
07	FCV201	29.8IN	XXX TSS	COLD	SUMP	LEVEL	H	60.0	L	15.0	PCM	3
08	FCV199	0. OFF	RCVR	DRAIN	FILL	ISOLAT					PCM	3
09	FCV171	0. OFF	RCVR	CTANK	AIR	SUPPLY					PCM	1
10	ZSH199	1. ON	XXX RCVR	DRAIN	FILL	ISOLAT					PCM	3
11	ZSL199	0. OFF	XXX RCVR	DRAIN	FILL	ISOLAT					PCM	3
12	OPN.211	0. OFF	TSS	COLD	SUMP	ISOLAT					PCM	3
13	CLS.211	0. OFF	TSS	COLD	SUMP	ISOLAT					PCM	3
14	ZSH211	0. OFF	XXX TSS	COLD	SUMP	ISOLAT					PCM	3
15	ZSL211	1. ON	XXX TSS	COLD	SUMP	ISOLAT					PCM	3
16	DR. OPN	0. OFF	RCVR	CAVITY	DOOR	OPEN					PCM	1
17	DR. CLS	0. OFF	RCVR	CAVITY	DOOR	CLOSE					PCM	1
18	ZSHDR	0. OFF	XXX RCVR	CAVITY	DOOR	OPEN					PCM	1
19	ZSLDR	1. ON	XXX RCVR	CAVITY	DOOR	CLOSED					PCM	1
20	LT281	50.2IN	XXX TSS	COLD	TANK	LEVEL	H	134.0	L	15.0	PCM	3
21	LT291	108.2IN	XXX TSS	HOT	TANK	LEVEL	H	190.0	L	10.0	PCM	3
22	PS281	1. ON	TSS	SGS	AIR	SUPPLY					PCM	3


COPY

Figure 4.5. Single Loop

01 FCV431	
- -	PV .0
- -	SP .0
- - -	PCT
- -	CASC
- - -	PIV
C - - - -	OUTPUT 0. %
HRFS	STEAM
CONTRL	

H	100.0	
L	.0	
DISPLAY	.0	100.0
EGU RANGE	.0	100.0 PCT
PRO BAND	.0	
RATE	0.	
RESET	2.	
GAP	0.	
LOW DEV	50.	
HIGH DEV	50.	

4-7



COPY

GROUP 30  
27-JUL-84 10:27:52

## 4.2 THE EMCON CONSOLE KEYBOARD

Figure 4.6 shows the keyboard layout.

### Error Protection and Recovery

The Color Console keyboard is logically constructed to protect the operator from performing nonsense functions. For example, it will not allow the operator to change the setpoint of a contact input bit (because contacts have no setpoints!). If the operator tries to perform a nonsense operation, "WRONG KEY" will be displayed in the Keyboard Echo Area. However, the operator DOES NOT have to hit an "Error Clear" key when an error is encountered. He simply re-enters the correct keys. Likewise, if he makes a typing error, hitting <CLEAR ENTRY> will erase what he has typed and all he has to do is retype the line.

Functionally, the keyboard has several areas:

1. DATA ENTRY - This area contains the NUMBER pad and ALPHABET for bringing points onto the display, entering numeric values, etc.
2. DISPLAY SELECTION - This area contains keys that select the various display modes of the screen.
3. TUNING - This part of the keyboard is used (usually by the process engineer) for tuning control loops. It is usually under keylock (password) protection.
4. OPERATION - This part of the keyboard is used by the process operator for running the process. For example, it places loops in Auto or Manual status, changes Setpoints, etc.
5. SELECTION - (optional). These keys select one of the eight controllers on the screen for tuning purposes.




Figure 4.6. EMCON Console Keyboard Layout

There are two types of keys:

Fixed Definition - These are keys that are always legal to hit. They are limited to:

1. DISPLAY KEYS - To change the display format of the screen.
2. CLEAR ENTRY - To erase typing errors and clear previous keyboard entries.

Variable Definition - These keys may be legal or illegal or may perform different functions depending on the display mode of the screen and the type of point that is Selected. These keys are limited to:

1. DATA ENTRY KEYS - For entering point names and data values.
2. POINT MODIFY KEYS - For selecting the tuning parameter to be changed.
3. ALARM SILENCE/ACKNOWLEDGE KEYS - To Silence and Acknowledge Alarms.
4. SELECT KEYS - For Selecting a line to change.

#### 4.3 USE OF CONSOLE DISPLAYS

##### 4.3.1 Bringing a Point onto the Display

NOTE: A single keystroke is designated by being enclosed in angle brackets < >. On the console itself, these brackets are NOT shown.

The Color Console allows the operator to bring a point or several points onto the display in three ways:

1. GROUPS - by indicating which pre-defined group of points is to be displayed. Table 4.1 lists the pre-defined groups. To display one of these groups, press the <GROUP> key followed by the group number. For example,

<GROUP> <0> <2>

will bring group 2, receiver and thermal storage subsystem controls, onto the screen. Most of the pre-defined groups will initially be displayed in the 22 line format.

2. INDIVIDUALLY - by entering the tag name. When calling a point up at random, using the individual method, press the ENTER key after typing the tag name in order to bring the point onto the display. For example,

<F><T><1><0><1><ENTER>

will bring "FT-101" onto the screen.

3. JOGGING - using the "JOG UP" or "JOG DOWN" keys, the user may "step through" the data base either forward or backward.

Table 4.1. MSEE Group List

<u>Group Number</u>	<u>Group Name</u>
01	RS controls with drain and purge valves
02	RS and TSS controls
03	RS and TSS instrumentation
04	TSS pump house
05	TSS storage tanks for propane heater operations
06	RS back tube temp
07	RS header temp
08	RS drain micros
09	RS purge micros
10	RS pass temp
11	Critical instrument readings
12	RS fill and drain sequence
13	SGS operation
14	SGS operations
15	SGS instrumentation
16	SGS heater control
17	SGS valve micros
18	HRFS controls
19	HRFS pump controls
20	HRFS cooling fan controls
21	Turbine operations
22	Turbine operations
23	Generator operations
26	EPS trips
27	EPS trips



#### 4.3.2 Display of an Individually Entered Point

Once the point name is entered, the system will look up the name in the point name table. If it is NOT found, "NOT DEFINED" will be printed in RED in the Echo Area.

If the point name IS found, the point will be displayed:

1. At the TOP of the screen in Standard (22-line) mode.
2. In the TOP LEFT controller faceplate in a 4 over 4 mode.
3. As the single controller in Single Controller mode.

If more points are brought onto the screen than the screen can hold, the NEW points still are displayed as described above, and the OLD points are dropped off:

1. the BOTTOM in Standard (22-line) mode,
2. the BOTTOM RIGHT in 4 over 4 mode,
3. and replaces the single controller in Single Controller mode.

#### 4.3.3 Selecting a Point

The SELECTED POINT is the single line or controller on the screen that is available for change. For example, the "SETPOINT" key will change the Setpoint of the SELECTED POINT.

The SELECTED POINT is always displayed in REVERSE VIDEO. That is, if the point's status were BAD SENSOR, it would usually be displayed in BLUE letters on a BLACK background. If it were the SELECTED POINT, it would be displayed in BLACK letters on a BLUE background.

In the 4 over 4 display, the point name and status of the SELECTED POINT are displayed in reverse video. A special display sequence will cause the selected controller to be refreshed (updated) at three times the rate of the other controllers. This provides a faster visual indication of the process, and is especially useful while tuning.

In the 22-line (standard) displays, the entire line of the SELECTED POINT is displayed in reverse video.

You may NOT select a point if graphics are displayed. The Console will remember the SELECTED POINT as you switch from one display mode to the next. For example, you may select controller #4 in 4 over 4 mode, switch to the 22-line mode, and switch back to the 4 over 4 display.

To select a point, simply hit the <SELECT> key, followed by the TWO digit controller or line number. For example,

<SELECT><0><3>

will select line #3 of a 22-line display or controller #3 of a 4 over 4 display.

If the line number is illegal for that particular display (for example, trying to select faceplate #9 on a 4 over 4 display) WRONG KEY will be printed in the Echo Area.

Another method available is the use of individual select keys numbered 1 through 8 on the upper panel. These allow the selection of one of eight faceplates or lines with a single keystroke. Simply press the key on the upper panel (not the Number Pad) to select the desired controller.

#### 4.3.4 Clearing the Screen

In order to erase the screen completely, press <CLEAR CRT>. This also erases the display list and, therefore, you cannot flip back to the previous display.

#### 4.3.5 4 Over 4 Display

To convert the current display to a 4 over 4 display, press <Cont 4-Over-4>. Eight controller faceplates will appear on the screen, and they will be filled in, left-to-right and top-to-bottom, with the first eight points at the top of the screen if the previous display was Standard 22 line.

If the Selected Point on the previous display was between lines one and eight, that point will remain selected. If the Selected Point was out of that range, Controller #1 (the top-left corner) will automatically be selected. The Selected Controller has the upper part of the faceplate, containing the point name and status in Reverse Video. Unacknowledged alarms will have a blinking status.

When in Controller Mode, the Console will refresh the Selected Point at three times the rate of the other points. This gives a faster visual response to operator and process changes.

Each controller faceplate is divided into three areas: upper, middle, and lower.

The upper box contains:

1. Two yellow digits corresponding to the controller number (used for SELECT)
2. The Point name color-coded according to status,
3. The Point status characters, also color-coded. The Point status characters are as follows:

BLANK	-	Normal
H	-	High absolute alarm
L	-	Low absolute alarm
B	-	Bad sensor
O	-	Off scan
*	-	Off line
X	-	Off alarm

As explained earlier, the Point name and Status are displayed in reverse video if the controller is the Selected Controller.

The lower box contains:

1. The four words that comprise the Point Descriptors.

The middle box contains:

1. A green vertical bar that graphically corresponds to the process measurement.
2. Two red vertical bars on either side of the measurement bar that graphically corresponds to the process setpoint.
3. A green horizontal bar that graphically corresponds to the controller output. If the controller is a velocity type and the feedback sensor is bad, a blue horizontal bar appears for the controller output. If a feedback sensor is not specified when the data base is generated, the controller output bar will not appear.
4. The numeric Engineering Units value of the process measurement, prefixed by the letters:

1. "SP" if the controller is a PID controller (with Setpoint)
2. "CL" if the controller is a Calculation block, in which case the value corresponds to the calculation result, in percent, of EGU of PV.
3. The Engineering Units tag or label
4. The Controller type:
  1. AIN for Analog Inputs, scan-only
  2. CIB for Contact inputs
  3. LOB for Latching Contact Outputs
  4. PIV for Velocity-mode PID based on error
  5. PID for Positional-mode PID based on error
  6. CAL for Calculation.
  7. SSL for Signal Select/Limiter
  8. NLV for Non-Linear, Velocity PID based on error
5. The Controller Auto/Manual/Cascade/LOCL status.
6. The numeric value of the output being calculated by the control algorithm, displayed in percent. The direction of value movement is depicted by the "O" and "C" at each end of the output bar.

Some of the items mentioned above may not be displayed on a particular controller, based on the point type and controller type (if any exists).

If the point goes off line (the communications link fails), the bars will disappear and the point name will be displayed in white. When the point returns on line, the controller will be re-drawn.

#### 4.3.6 Single Loop Display

The Single Loop display presents detailed information in a split-screen presentation. The single loop display always presents the SELECTED point. After selecting a point on the screen (from the 22 line or 4 over 4 displays), press <SINGLE LOOP> to view the selected point in Single Loop format.

The upper half of the screen is presented in two quarters:

1. The left quarter contains a single controller faceplate display, containing information as described in the preceding section.
2. The right quarter contains the numeric values of the tuning parameters associated with the point on display. The tuning parameters that are displayed depend on the type of point and control block (if any) that is on the display. These may include:
  1. The high absolute alarm limit
  2. The low absolute alarm limit
  3. The engineering units range
  4. The display range (if scale expansion is used)
  5. Proportional band constant (PB)
  6. Reset time (integral)
  7. Rate time (derivative)
  8. High and Low Deviation Limits

Some of these tuning parameters may be changed from the operator's console keyboard.

The bottom half of the screen is used for a real-time trend of the measurement of the point. The Y-axis is labeled in Engineering Units. The X-axis is the time base. The left margin is the time when the display is first called up, the right margin will be reached after approximately twelve minutes. The graph is plotted, much like a pen recorder, with a sample of the measurement being displayed every five seconds. When the right-hand margin is reached, the screen is erased and the display re-starts at the left margin.

A feature of this display is that the value is plotted in the color of the point status. For example, if the point is "Normal", the dots will be drawn in green. As the point enters its High Absolute Alarm area, the dots will change to red.

If no point is selected when the <SINGLE LOOP> key is hit (for example, when the screen is clear) "OFF LINE" will be displayed in the Keyboard Echo Area. If the point goes off line while on display, the faceplate will be blanked, as in the 4-Over-4 display, and the graph will turn white.

After the Single display mode is selected, other points may be called up at random by entering the Tag name. The screen will be erased and the new point will then be displayed.

You may return to the previous display from the Single display by simply pressing one of the display mode keys.

#### 4.3.7 Standard 22-Line Display

To enter the Standard display mode, press <22-Line>. If a point display was already on the screen (for example, 4-Over-4, or Single) the display will be converted to the 22-line format. If the screen was clear, the Console will wait for points to be called up by entering the tag names.

The Standard display presents:

1. A yellow, two-digit line number
2. The Tag Name
3. The measurement, in Engineering Units
4. The engineering Units label
5. The Point status (blinking if unacknowledged)
6. The four Point Descriptor words
7. The High and Low, Alarm Limits (if applicable)
8. The PCM number where the point is located.

The Selected point is displayed in reverse video, and each line is color-coded according to its status. As points are added to the screen, by entering the tag name or Jogging Up or Down, these points are displayed at the TOP of the screen, and the other points move down and eventually off the bottom of the screen. The 22-line display shows the maximum number of points that may be contained on the screen. Therefore, you may notice for example, that when changing from a 4-Over-4 display to 22-Line, more than eight lines will be on the screen. This feature allows you to group points in such a way that the top eight points are control points, and the bottom fourteen may be used for other points.

#### 4.3.8 Graphic Displays

The graphic displays are called up by pressing the <GRAPHICS> key followed by the number of the desired graphic and the <ENTER> key. For example, <GRAPHIC> <9><9><1><ENTER> will display the MSEE overall system graphic. The available graphic displays are:



990	Receiver Panel Warm Up Temperatures
991	MSEE Overall
992	Receiver Subsystem
993	Thermal Storage Subsystem
994	Steam Generator Subsystem
995	Heat Rejection and Feedwater Subsystem
996	Electric Power Generation Subsystem

The <CLEAR CRT> key must be pressed before the display can be changed. The graphics displays are for observing operations only and cannot be used for control.

#### 4.4 CONTROL

##### 4.4.1 Change Keys, Tuning Keys, Modify Keys

The operator's console supports a full set of keys that modify the characteristics of a loop on line. These keys perform immediate changes to the live point, but they do not effect any changes on the Host disk image of the control data base.

The MODIFY keys are divided into two categories: Process Operator functions and Process Engineer functions.

The Process Operator functions are those normally necessary for the daily operation of the plant. They may be performed by anyone at any time and can be likened to the functions available on the front panel of a typical analog controller. These keys include:

1. Switch to Automatic Control, <AUTO>
2. Switch to Manual Control, <MAN>
3. Change Set point, <SET POINT>
4. Change Output, <OUTPUT>
5. Change Analog or Contact Value, <VALUE>

The Process Engineer functions are those used to change the characteristics of the control operation being performed. These changes must be done under keylock (Password) protection and therefore, are not immediately accessible to the operator.

These functions are parallel to those contained inside an analog controller, where the controller must be removed from its case in order to be changed. These keys include:

1. Change High Alarm LIMIT, <HIGH>
2. Change Low Alarm Limit, <LOW>
3. Change Rate-Of-Change Alarm Limit, <RATE of CHG>
4. Change Deviation Alarm Limits, <DEV>
5. Change Scan Status, <SCAN>
6. Change Host Alarm Status, <ALARM>
7. Change Rate (Derivative), <RATE>
8. Change Reset (Integral), <RESET>

9. Change Proportional Band, <PROP BAND>
10. Change Bias, <RATE>
11. Change Lag Time, <GAIN>
12. Change Ramp Time, <PROP BAND>
13. Change Gap, <GAP>

#### 4.4.2 Success/Error Messages

If the Modify occurs successfully (is accepted by the remote computer)

\*DONE\*

will be printed (in green).

If the Modify function fails as a result of a communications link problem,

\*COMM LINK ERR\*

will be printed in red.

Other operator messages are discussed in their appropriate section.

#### 4.4.3 Switch To Automatic Control, <AUTO>

In the case of a contact output, pressing <AUTO> will prevent the contact from being turned on or off with the <VALUE> key.

If the selected point is an analog input with a control block attached, pressing <AUTO> will put the output of that block in automatic or cascade mode.

In all other cases, the <AUTO> key is illegal and will print "WRONG KEY" if hit.

#### 4.4.4 Switch To Manual Control, <MANL>

For a contact output, pressing <MANL> will allow the value of the contact to be changed using the <VALUE>.

For an analog input with a control block attached, pressing <MANL> will place the block in manual mode and allow the output of the control block to be changed using the <OUTPUT> key.

For all other blocks, <MANL> is illegal and will print "WRONG KEY" if hit.

#### 4.4.5 Setpoints

##### The SETPOINT Key

The <SETPOINT> key, from its name, indicates that it will modify the setpoint of any block that has a setpoint.

When the key is pressed, it will print the name of the parameter that it is changing.

If the selected analog point does not have a changeable setpoint field, "NO TUNING" will be printed in red when the key is hit. Digital points will respond with "WRONG KEY".

Note also that the setpoint key is legal only for the 4-Over-4 and Single Controller display. If pressed for any other display, "WRONG KEY" will be printed.

### Changing Setpoint -

If the selected point has a 3-term PID block (or one of its variations) attached, the <SETPOINT> key will modify the setpoint of the loop. It will print "SETPOINT" when the key is hit, followed by the current setpoint, in engineering units. For example,

SETPOINT 73.05

The operator may enter the new setpoint, in engineering units, followed by <ENTER>. If he does not wish to enter a new value, he may simply hit <ENTER> and no change will occur.

If the value was entered correctly, "\*DONE\*" will be printed.

If the value was typed incorrectly or if the value was outside the engineering units range, "CONVERT ERR" will be printed in red. The operator must try again, starting with pressing the <SETPOINT> key.

### Cascaded Setpoints -

In some cases, the setpoint of the slave (or downstream) loop will be determined by the output of a master (or upstream) loop. For example, suppose the downstream loop is selected and the cascade is closed ("CASC" is displayed on the controller). When the <SETPOINT> key is hit, you will see:

WARNING: CASCADE CLOSED.

The operator may still enter a new value, but it will be replaced by the new upstream setpoint when the upstream block is scanned.

To change the downstream setpoint, the operator should put the upstream block in "MANUAL" to open the cascade. He may then:

1. Change the "OUTPUT" of the upstream block, thereby changing the downstream setpoint. This can be done only if the upstream block a PID-Type block.
2. Change the "SETPOINT" of the downstream block, using the <SETPT> key. The warning message will not be shown.

#### Jogging Setpoints -

After pressing the <SETPOINT> key, the "INCREMENT /ON" DECREMENT/OFF" (up-arrow and down-arrow etchings, respectively) are defined to increase or decrease the setpoint by one percent of the full engineering units range each time they are hit. This is similar to holding a Bat-Handle to RAMP a setpoint.

For example:

<SETPOINT><INC-ON><INC-ON>

will increase the setpoint by two percent of full range. The change occurs each time the key is pressed; holding the <INC-ON> key down, for example, will not cause a continuing increase.

The setpoint value will not increase past 100 percent of full Engineering Units range nor decrease below zero percent.

#### 4.4.6 Positional Output Commands

##### The OUTPUT Key

The <OUTPUT> key changes the output of a control block. When the <OUTPUT> key is pressed, one of the following prompts are given: "Positional Output" or "Incremental Output". Positional output requires the entry to be the absolute position between 0 and 100 percent. Incremental output requires the entry to be incremented or decremented from its current position. Entry range from -100 to 100%.

If the controller is in "AUTO" or "CASC" mode, then the output is being calculated by the controller's algorithm and is not changeable with the output key. An attempt to do so will cause

\*BLOCK IN AUTO\*

to be printed in RED.

Therefore, you must set the controller in manual mode using the <MAN> key.

The <OUTPUT> key is only valid for displays where controller output is shown (4-over-4 and single controller). If <OUTPUT> is struck on any other display, "WRONG KEY" will be printed.

If the selected block does not have a control block or if its control block does not have a changeable output, "NO OUTPUT" will be displayed when <OUTPUT> is hit.

#### Entering A New Output Value

After pressing the <OUTPUT> key, the operator may change the output by entering a new numeric value followed by <ENTER>. For positional output, the value is the absolute position between 0.0 and 100.0 percent of full output from 35 percent to 60 percent, the operator strikes:

<OUTPUT><6><0><ENTER>

For incremental output, the entry would be:

<OUTPUT><2><5><ENTER>

### Jogging Outputs

Once the <OUTPUT> key is hit, the "INCREMENT/ON" (UPARROW) and "DECREMENT/OFF" (DOWNARROW) keys are defined to change the current output by one percent each time they are hit.

To decrease the output by 3 percent for example, the operator hits:

<OUTPUT><DEC-OFF><DEC-OFF><DEC-OFF>

The output will not decrease below zero, nor increase above 100 percent of output range.

#### 4.4.7 Digital Output Commands

##### The <VALUE> key

The <VALUE> key is used for changing the value of a contact output (on/off or open/close commands).

If the selected point is a contact output, pressing the <VALUE> key will set the keyboard such that:

1. Pressing <INCREMENT/ON> will turn the contact on (set its value to 1)
2. Pressing <DECREMENT/OFF> will turn the contact off (set its value to 0).

For example, to turn a contact on, hit

<VALUE><INC-ON>



You can now immediately turn the contact off by striking <DEC-OFF> without having to strike the <VALUE> key, for example:

<VALUE><INC-ON><DEC-OFF>

The contact output must be in MANUAL mode to change its output using the <VALUE> key.

#### 4.5 MISCELLANEOUS KEYS

##### 4.5.1 Print Key

When the console has a standard 22 line display on the screen, the operator may press this key to have the display duplicated on the operator tracking typer. This is not an exact copy but a remake of the display by the tracking program. When all packets have been sent to the tracking program, the console will tell the operator that the task has been completed by displaying '\*DONE\*' in the keyboard echo area. The typing may continue depending on the speed of the typer.

For example:

<PRINT> \*DONE\*

##### 4.5.2 COPY Key


This key is for the copying of the CRT screen to the hard copy graphics printer. When this key is pressed, the console will echo 'COPY' at which time the screen will freeze until the copying process is finished. When the screen becomes unfrozen and the copying is done, the console will display in the echo area '\*DONE\*' indicating that the copying process is complete.

For example:

<COPY> \*DONE\*

#### 4.6 BAILEY NETWORK 90 CONSOLE

The Bailey Network 90 keyboard is shown in Figure 4.7. The Network 90 is used primarily as a display during SGS operation. Two displays are illustrated on Figures 4.8 & 4.9. Only one operational command is made from this system. Hence, full console operation will not be covered in this program.



Keyboard Layout

Figure 4.7

05APR84 THURSDAY 958-1 DRUM LEVEL-FLOW

S12

15:13:25

FCV-411 FEED WATER

% — 10.0

— 0.01 — 0.01

— -7.0

CASC 82% LOCAL

ZT-411 POS FEEDBACK FW

\*

SP-411 MANUAL CONTROL

-0.1 %

L

MAN-411 FEED WATER EMCON

OFF

LT-311 DRUM LEVEL

-0.01 "H2O

TE-393 STM DRUM FLUID TEMP

563. DEG F

PT-386 FEEDWATER PRESS

1184. PSIG

FT-311 MAIN STM FLOW

7.36 KLB/HR

SP-DL SET PNT FROM EMCON

0.004 "H2O

TE-386 FEED WATER TEMP

440. DEG F

L

PT-383 STM DRUM PRESS

1177. PSIG

FT-411 FEED WATER FLOW

7.29 KLB/HR

SP-FWF FW FLOW SET POINT

7.50 KLB/HR

EHAC AUTO DRUM PRES CONT

ON

OFF

MAN-EHAC EMCON CONTROL

ON

Figure 4.8

Bailey Network 90 Status Display

4-31

05APR84 THURSDAY

ASSIGNABLE TRENDS

S12

15:22:18




Figure 4.9  
Bailey Network 90 Trend Display



Section 5  
TRAINING MATERIAL

This section contains exercises to be conducted as part of the training and operating program.

5.1 PRE-OPERATIONAL CONTROL ROOM EXERCISES

5.1.1 EMCON Console Introduction

Part 1 - Display Familiarization

	<u>KEY</u>	<u>SECTION</u>	<u>COMPLETED</u>
1) Choose and call up a group from the group list	GROUP	4.3.1	_____
2) Place the group into a 4 over 4 display	cont 4 over 4	4.3.5	_____
3) Select a point		4.3.3	_____
a) Using the select key	SELECT		
b) Using the individual select keys	UPPER PANEL 1 - 8		

Part 1 - Display Familiarization (continued)

	<u>KEY</u>	<u>SECTION</u>	<u>COMPLETED</u>
4) Place the selected point into a single loop display	SINGLE LOOP	4.3.6	_____
5) Return to the 22 line display	22 LINE	4.3.7	_____
6) Call up an individual point by entering the point name	ENTER	4.3.1	_____
7) Call up each of the system and subsystem graphic displays. Press "CLEAR CRT" key when completed	GRAPHIC	4.3.8	_____
8) Change a groups 4 over 4 display	PAGE		_____
a) Call up group 14 (note position of FCV-431)			
b) Place the group into a 4 over 4 display			
c) Press "PAGE" key twice (note display changes)			
d) Return to 22 line display (note position of FCV-431)			
9) Print a 22 line display	PRINT	4.5.1	_____
10) Copy a 4 over 4 display	COPY	4.5.2	_____



Part 2 - Control

	<u>KEY</u>	<u>SECTION</u>	<u>COMPLETED</u>
1) Change a valve position	OUTPUT	4.4.6	_____
a) Call up group 14 and include FCV-421 in a 4 over 4 display			
b) Select FCV-421			
c) Place in manual control	MAN	4.4.4	
d) Change valve position to 40% open by entering the proper value	ENTER		
e) Change the valve position by using the "UPARROW" and "DOWNARROW" keys	Δ ▽		
f) Close the valve (0%)			
g) Return valve to auto position			
2) Change a setpoint	SET POINT	4.4.5	_____
a) Call up group 14 and include FCV-432 in a 4 over 4 display			
b) Select FCV-432			
c) Change the set point to 200 PSI by entering the value			

Part 2 - Control

	<u>KEY</u>	<u>SECTION</u>	<u>COMPLETED</u>
d) Change the set point using the "UPARROW" and "DOWNARROW" keys			
e) Change the set point to 233 PSI			
3) Turn on a pump	VALUE	4.4.7	_____
a) Call up group 19 and select CFP.EN (cycle fill pump enable)			
b) Turn CFP.EN on	Δ		
c) Select CFP			
d) Turn CFP on			
e) Verify ZSHCFP "on"			
f) Turn pump off	∇		
g) Verify ZSHCFP "off"			
h) Turn CFP.EN off			

Part 2 - Control

	<u>KEY</u>	<u>SECTION</u>	<u>COMPLETED</u>
4) Open receiver cavity door	VALUE	4.4.7	_____
a) Call up group 02			
b) Verify DR.CLS "off" (cavity door close)			
c) Verify DR.OPN "off" (cavity door open)			
d) Verify ZSHDR "off" (door open micro)			
e) Turn DR.OPN "on" and observe door on video monitor			
f) When ZSHDR indicates that door is fully open imme- diately turn DR.OPN "off"			
5) Close receiver cavity door	VALUE	4.4.7	_____
a) Verify DR.CLS "off"			
b) Verify DR.OPN "off"			
c) Verify ZSLDR "off"			
d) Turn DR.CLS "on"			
e) When ZSLDR indicates that door is fully closed, immediately turn DR.CLS "off"			

### 5.1.2 Acurex Data System Familiarization

1. The Acurex data is displayed on page 02. If this page is not displayed on the display screen, use the "PAGE FWD" or "PAGE BACK" key as required to change to this page.
2. Check the receiver purge and drain valve temperatures and verify that all are above 480°F.
  - a. Determine the channel numbers corresponding to the purge and drain valve thermocouples (see Rs heat trace instrumentation list).
  - b. Use the arrows on the keypad to move the cursor to the top channel number on the display screen.
  - c. Key in the first channel in the series of channels that you wish to display and press the "ENTER" key.
  - d. Repeat step c to check the remaining purge and drain valve temperatures.
3. Check FCV-101 and FCV-102 temperatures and verify that they are above 480°F.
4. Check channels 100-142. Note the thermocouple locations on the instrumentation list. Record any temperatures less than 480°F along with the corresponding channel.

5.1.3 Receiver Subsystem Instrumentation and Control

Completed

1. Review group 1 and locate the instrumentation and valve tag names on the P&ID.
2. Repeat step 1 for group 2.
3. Repeat step 1 for group 3.
4. Manual control of a cascaded valve from an upstream control block.
  - a) On Acurex verify that FCV-151 temperature is above 480°F. Verified: \_\_\_\_\_
  - b) Place FCV-151 in cascade. (Group 2)
  - c) Place LT-151 in manual and output the valve that will position FCV-151 25% open.
  - d) Close FCV-151 and return LT-151 to auto.
5. Manual control of a cascaded valve from the downstream control block.
  - a) Place LT-151 in manual.
  - b) With FCV-151 in auto, change the set point to position the valve 25% open.
  - c) Return FCV-151 to closed position.
  - d) Return LT-151 to auto; note FCV-151 change to cascade.

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

CB

CB

6. Manual valve control

CB

- a) Place FCV-151 in manual.
- b) Output the proper value to position the valve 25% open.
- c) Return FCV-151 to cascade.

7. Change the salt outlet temperature set point

CB

Note: The receiver control algorithm would have to be "ON SCAN" to control the outlet temperature. However for this exercise, RCA will remain off.

- a) Change SP.SALT to 1000°F.
- b) Change SP.SALT to 750°F.

8. Constant receiver flow

- a) On Acurex verify that FCV-101 and FCV-102 temperatures are above 480°F. Verified: \_\_\_\_\_
- b) Place FCV-101 and FCV-102 in cascade.
- c) Change FD-101 set point to 40 KLB/hr (<sup>RCA</sup>FD-10 must be off scan).
- d) Return FD-101 set point to 30 KLB/hr.
- e) Return FCV-101 and FCV-102 to manual control.

CB

5.1.4 Thermal Storage Subsystem Instrumentation and Control

Completed

1. Review group 4 and locate the instrumentation and valve tag names on the P&ID. \_\_\_\_\_
2. Repeat step 1 for group 5. \_\_\_\_\_
3. Complete the following table.

Day \_\_\_\_\_ Time \_\_\_\_\_

Description	Tag Name	Value
Hot storage tank level		
Cold storage tank level		
Hot sump level		
Cold sump level		
Cold storage tank bottom temp		
Hot sump temp (Acurex)		
Cold sump temp (Acurex)		

4. How is the set point changed for the hot and cold sump levels?

5.1.5 SGS Instrumentation and Control

Completed

1. Review group 13 and locate the instrumentation and valve tag names on the P&ID. \_\_\_\_\_
2. Repeat step 1 for group 14.
3. Repeat step 1 for group 15.
4. Manual control of a Network 90 controlled valve. \_\_\_\_\_
  - a) On Acurex verify that FCV-321 temperature is above 480°F. Verified: \_\_\_\_\_
  - b) Turn/verify MAN.321 on. (Group 13)
  - c) Change SP.321 setpoint to position the valve 25% open.
  - d) Change SP.321 setpoint to close the valve.  
*e) Change setpoint to fully open valve (50.4 to 1100)*
5. Automatic control of a Network 90 controlled valve. \_\_\_\_\_
  - a) Turn MAN. 321 off.
  - b) FCV-321 will now control the main steam pressure to SP.SP setpoint. Change this setpoint to 1075 PSI.
  - c) Change SP.SP setpoint to 1100 PSI.
  - d) Return MAN.321 to on.



Completed

6. Control of a Network 90 controlled isolation valve. \_\_\_\_\_

a) On Acurex verify that FCV-381 and FCV-382  
temperatures are above 480°F. Verified: \_\_\_\_\_

b) FCV-381 and FCV-382 are controlled together. (Group 13)

c) Turn FCV38182 on to open the valves.

d) Check micros to verify valves open (Group 17).

e) Turn FCV38182 off to close FCV-381 and FCV-382.

f) Turn MAN.38182 off.

7. Change the position of FCV-331 using step, 4 as  
a guide. Return the valve position to 10% open  
when finished. \_\_\_\_\_

5.2.2 Receiver Steady State Operation

Description

- o Operate receiver with heliostats on target to heat cold salt and charge the hot salt storage tank.

Objectives

- o Introduce the operator to hot salt production
- o Calculate receiver power output
- o Determine collector/receiver efficiency

Initial System Conditions

- o RS2- Receiver drained with trace heat on
- o RSS2- Hot and cold salt tanks warm and ready for operation with hot tank level less than 20 inches.
- o SGS not applicable
- o EPGS not applicable

Procedure

1. Advise data system operator to load system data package.

2. Advise data system operator to display the following on the data display screens:

LT-281	Cold storage tank level
LT-291	Hot storage tank level
TE-101	Receiver inlet salt temp
TE-102	Receiver outlet salt temp
TE-291	Hot storage tank temp
FT-101	Receiver salt flow rate

3. Confirm receiver technician is completing receiver pretest checklist (ROP #1).

4. Confirm thermal storage technician is completing TSS pretest checklist (TOP #1).

Completed

---

---

Procedure

Completed

- 5. Complete control room pretest checklist (COP #1) Sections I - VI. \_\_\_\_\_
  
- 6. Fill receiver and establish serpentine flow with receiver in solar charging configuration, SP.SALT at 750°F, and warm up heliostats on target (ROP #2). \_\_\_\_\_
  
- 7. Increase heliostat field in increments of 12-1/2% until salt flow rate exceeds 60 KLB/hr. \_\_\_\_\_
  
- 8. Increase SP.SALT to 850°F. Stabilize and confirm salt outlet temperature and flow switchover to hot tank. \_\_\_\_\_
  
- 9 Complete Table 5.1 after stabilizing at each of the noted operating conditions. Calculate the power and efficiency for each case as follows. \_\_\_\_\_

- o Direct insolation power

$$P_D \text{ (watts)} = A \times N \times (\text{sun})$$

where: A = heliostat mirror surface area = 37.2m<sub>2</sub>  
N = number of heliostats on target  
Sun = solar insolation in W/M<sub>2</sub>

- o Receiver power output

$$P_R = C_p m \Delta T$$

$$P_R \text{ (watts)} = 108 \text{ (FT-101)} [(TE-102) - (TE-101)]$$

where: FT-101 = salt flow rate in KLB/hr

TE-102 = receiver outlet salt temp in °F

TE-101 = receiver inlet salt temp in °F

o CS/RS efficiency

$$\eta = \frac{P_R}{P_D}$$

Procedure

Completed

10. Scram heliostats and set receiver flow demand to 30 KLB/hr. Confirm flow switchback to cold tank at 700°F.

\_\_\_\_\_

11. Shut down receiver (ROP #3).

\_\_\_\_\_

Table 5.1. Receiver Steady State Operation

Operating Conditions		Data						Calculate		
SP. SALT	Heliostat Field (pct)	Number of Heliostats on Target	Time of Day	Solar Insolation (Sun)	Salt Inlet Temp (TE-101)	Salt Outlet Temp (TE-102)	Flow Rate (FT-101)	Direct Insolation Power	Receiver Power Output	CS/RS Efficiency
850	50%									
900	50%									
850	75%									
900	75%									
950	75%									
900	100%									
950	100%									
1000	100%									

5-17

	<u>Begin</u>	<u>End</u>
Ambient Air Temp	_____	_____
Relative Humidity	_____	_____
Barometric Pressure	_____	_____
Wind Speed	_____	_____
Wind Direction	_____	_____

### 5.2.3 Receiver Operation with Simulated Clouds

#### Description

- o During receiver loop operation, simulate passing clouds by ramping heliostats on and off of the receiver.

#### Objectives

- o Demonstrate receiver operation through simulated cloud passage.
- o Familiarize operator with receiver control algorithm.

#### Initial System Conditions

- o RS2 - Receiver drained with trace heat on
- o TSS2 Hot and cold salt tanks warm and ready for operation with hot tank level less than 20 inches
- o SGS not applicable
- o EPGS not applicable

#### Procedure

#### Completed

1. Advise data system operator to load receiver data package. \_\_\_\_\_
2. Advise data system operator to display the following on the data display screens: \_\_\_\_\_  
  
LT-281 Cold storage tank level  
LT-291 Hot storage tank level  
TE-102 Receiver outlet salt temp  
FT-101 Receiver salt flow rate
3. Confirm receiver technician is completing receiver pretest checklist (ROP #1) \_\_\_\_\_
4. Confirm thermal storage technician is completing TSS pretest checklist (TOP #1) \_\_\_\_\_

- 5 Complete control room pretest checklist  
(COP #1) Sections I - VI. \_\_\_\_\_
  
- 6 Fill receiver, establish serpentine flow with  
receiver in solar charging configuration SP.SALT  
at 900°F, and 25 percent of the heliostats on  
target. \_\_\_\_\_
  
7. Complete Table 5.2 for each of the noted  
transient cases. Allow receiver to stabilize  
before each case. \_\_\_\_\_
  
8. Shut down receiver (ROP #3). \_\_\_\_\_

Doc. 1843U

Table 5.2. Receiver Operation with Simulated Clouds

Initial Conditions		Heliostat Transient			Data			
SP.SALT	Heliostat Field (Pct)	Final Heliostat Field (Pct)	Heliostat Increment (Pct)	Time Increment (Sec)	Time of First Heliostat Command	Salt Inlet Temp (TE-101)	Initial Salt Outlet Temp (TE-1012)	Maximum Salt Outlet Temp (TE-102)
900	25	75	12 1/2	60				
900	25	75	25	60				
900	25	75	25	30				
900	25	75	50	-				
950	50	100	12 1/2	60				
950	50	100	25	60				
950	50	100	50	-				
1000	50	100	12 1/2	60				

5-20

	<u>Begin</u>	<u>End</u>
Ambient Air Temp	_____	_____
Relative Humidity	_____	_____
Barometric Pressure	_____	_____
Wind Speed	_____	_____
Wind Direction	_____	_____



## 5.2.4 Thermal Storage Charging with Propane Heater

### Description

- o Charge the hot salt tank using the propane heater.

### Objective

- o Familiarize operator with propane heater loop equipment and controls.

### Initial System Conditions

- o RS not applicable
- o TSS2 - Hot and cold salt tanks warm and ready for operation with cold tank level greater than 80 inches.
- o SGS not applicable
- o EPGS not applicable

Completed

### Procedure

1. Advise data system operator to load system data package.

2. Advise data system operator to display the following on the data display screens:

LT-281 Cold storage tank level

LT-291 Hot storage tank level

TE-291 Hot storage tank temp

3. Confirm thermal storage technician is completing TSS pretest checklist (TOP #1)

Completed

4. Complete control room pretest checklist (COP #1)  
Sections I - IV and VI

✓

5. Start up propane heater (TOP #2)

✓

6. Complete the following table for future reference:

*ASK Tech for this temp*

Salt Outlet Temp (Ch 142)	Stack Temp. (°F)	FCV-241 Position
<i>over shot</i> 800		
900 <del>990</del>	1100	53 <sup>2</sup> / <sub>2</sub>
1000		

8. Shut down propane heater (TOP #3)

\_\_\_\_\_

### 5.2.5 Steam Generator Steady State Operation

#### Description

- o Operate the steam generator using hot salt from storage, rejecting the steam through HRFS.

#### Objectives

- o Introduce the operator to SGS start-up and steady state and shutdown operations.
- o Familiarize the operator SGS equipment and controls.

#### Initial System Conditions

- o RS not applicable
- o TSS2 - Hot and cold salt tanks warm and ready for operation with hot tank level greater than 80 inches and cold tank level greater than 30 inches.
- o SGS2- SGS warm and salt drained (diurnal shutdown).
- o EPGS not available

#### Procedure

#### Completed

1. Advise data system operator to load system data package. \_\_\_\_\_
2. Advise data system operator to display the following on the data display screens: \_\_\_\_\_

Procedure

Completed

- LT-281 Cold storage tank level
- LT-291 Hot storage tank level
- FT-321 SGS salt flow rate
- FT-311 Steam flow rate
- TE-382 Superheater salt inlet temp
- TE-332 Main steam temp

3. Confirm thermal storage technician is completing TSS pretest checklist (TOP #1).
4. Confirm steam generator technician is completing SGS pretest checklist (SOP #1).
5. Complete control room pretest checklist (COP #1) Sections I - IV, VI, VII and Section VIII if not previously completed. \_\_\_\_\_
6. Start up SGS and establish approximately 3 KLB/hr steam flow in boiler following mode (SOP #2). \_\_\_\_\_
7. Increase the steam demand by manually ramping FCV-431 open to simulate turbine loading. Stabilize at each of the steam load conditions listed in the following table and complete the table for future reference.

Nominal Steam Load (KLB/hr)	Actual Steam Flow (FT-311)	FCV-431 Commanded Position (Pct)	Salt Flow (FT-321)	FCV-321 Position (Pct)

Feedwater temp (TE-386) \_\_\_\_\_

Superheater salt inlet temp (TE-382) \_\_\_\_\_

8. Shut down SGS (SOP #3)

## 5.2.6 Operation of Full Electric Loop

### Description

- o Generate steam using hot salt from storage and supply steam to EPGs to operate turbine and generate electricity.

### Objectives

- o Introduce the operator to EPGs operations.
- o Familiarize the operator with EPGs equipment and controls.

### Initial System Conditions

- o RS not applicable
- o TSS2- Hot and cold salt tanks warm and ready for operation with hot tank level greater than 80 inches and temperature above 900°F.
- o SGS2- SGS warm and salt drained (diurnal shutdown).
- o EPGs2- EPGs pumps on (turbine standby).

### Procedure

1. Advise data system operator to load system data package.

### Completed

---

Procedure

Completed

2. Advise data system operator to display the following on the data display screen.
- 

LT-281 Cold storage tank level  
LT-291 Hot storage tank level  
FT-321 SGS salt flow rate  
FT-311 Steam flow rate  
JT-581 Generator power output  
ST-582 Generator RPM

3. Confirm thermal storage technician is completing TSS pretest checklist (TOP #1).
4. Confirm steam generator technician is completing SGS pretest checklist (SOP #1).
5. Confirm EPGS technician is completing EPGS pretest checklist (POP #1).
6. Complete control room pretest checklist (COP #1) Sections I - IV and VI - IX except Section VIII if previously completed.
- 
7. Start up SGS (SOP #2)/
8. Start up EPGS and locally synchronize generator to power grid.
- 
9. Transfer generator control to remote (control room) panel (POP #2).
-

Procedure

Completed

10. Ramp up generator load to 500 kW. Stabilize and complete the following table.

Generator output (JT-581)	_____	kW
Date/time	_____	
Turbine steam pressure (PT-581)	_____	PSI
Turbine steam temp (TT-583)	_____	°F
Main steam flow rate (FT-311)	_____	KLB/hr
Superheater salt inlet temp (TE-382)	_____	°F
Salt flow rate (FT-321)	_____	KLB/hr

11. Shut down EPGS (POP #3).
12. Shut down SGS (SOP #3).

## 5.2.8 EPGS Steady State Performance

### Description

- o Operate steam generator and turbine/generator at various steady state loads for performance evaluation.

### Objectives

- o Determine the following:
  - Turbine heat rate
  - EPGS/HRFS thermal efficiency
  - Turbine/generator efficiency

### Initial System Conditions

- o SGS steady state operation
- o HRFS steady state operation
- o EPGS steady state operation

### Procedure

1. Review the supplementary material provided at the end of this section.
2. Record the water, steam, and generator operating data on the EPGS performance worksheet (Figure 5.3).  
Note: Space is provided for three steady state operating conditions.
3. Determine the water and steam enthalpy as follows and record on the worksheet.



- Main steam ( $h_0$ ) and throttle steam ( $h_1$ )

For the steam conditions locate the intersection of the constant pressure and constant temperature lines on the Mollier Chart (Figure 5.4). Read the enthalpy on the vertical scale.

- Constant entropy exhaust steam ( $h_x$ )

Locate the throttle steam conditions on the Mollier Chart and follow a vertical line (constant entropy) from this point downward to its intersection with the exhaust pressure (PT-502) line. Read the enthalpy at this intersection.

- Saturated liquid at exhaust pressure ( $h_f$ )

$$h_f \frac{\text{BTU}}{\text{lb}} = 83.0 + 8.1 [(PT-502) - 3.0]$$

PT-502 in inches of Hg

- Condensate ( $h_2$ )

$$h_2 \frac{\text{BTU}}{\text{lb}} = (TI-582) - 32$$

TJ-582 in °F

- Feedwater ( $h_3$ )

$$h_3 \frac{\text{BTU}}{\text{lb}} = (TI-582) - 32$$

TE-386 in °F

4. Calculate the fraction of the main steam supplied to the turbine,  $X$ , and the steam flow,  $W_1$ , as shown on the worksheet.
5. Calculate the performance and efficiency as shown on the worksheet and compare to ratings.

Day \_\_\_\_\_

Case Time

1 Main steam fraction to turbine  
 2  $x = \frac{h_3 - h_2}{h_1 - h_2}$  1. \_\_\_\_\_  
 3 2. \_\_\_\_\_  
 3. \_\_\_\_\_

Heat rate (14200 BTU/kWhr rating)  
 $= \frac{W_1 (h_1 - h_f)}{P}$  1. \_\_\_\_\_  
 2. \_\_\_\_\_  
 3. \_\_\_\_\_

EPGS/HRFS thermal efficiency  
 $= \frac{3.413 P}{(FT-311)(h_1 - h_4)}$  1. \_\_\_\_\_  
 2. \_\_\_\_\_  
 3. \_\_\_\_\_

Turbine/generator efficiency (64% rating)  
 $= \frac{3.413 P}{W_1 (h_1 - h_s)}$  1. \_\_\_\_\_  
 2. \_\_\_\_\_  
 3. \_\_\_\_\_




Figure 5.3 EPGS Performance Worksheet

Doc. 1843U

5-31




Figure 5.4 Mollier Chart

## MEASURING STEAM

What are the yardsticks for steam? First if we have a fixed amount of steam in a closed space, we can measure weight or volume. Usually we measure steam flow in lb per hr. **STEAM PROPERTIES.** Certain other measurements identify the kind of steam as distinct from the amount. These are (1) temperature (2) pressure (3) quality — expressed as percent moisture or percent vapor of wet steam (4) degree of superheat — degrees F above saturation temperature (5) specific volume — cu ft per lb steam (6) enthalpy — Btu per lb (7) entropy and (8) internal energy. The two most commonly measured are temperature and pressure. With these two (plus an estimate of quality in the case of wet steam) the other properties can be read directly from steam tables. **SATURATION PAIRS.** When water is boiling, both the water and steam in contact with the water have the same temperature — called the saturation temperature. For each boiling

pressure there is only one saturation temperature and vice versa. If you know one you can find the other in the steam tables. Thus for boiling water and steam in contact, 14.7 psi abs and 212 F, 50 psi abs and 281 F, 100 psi abs and 328 F, etc. are saturation pairs.

## ENTHALPY ("HEAT") DEFINED

For reasons too long to explain here the term "heat content" is in bad repute with the steam experts. The quantities formerly known as the "heat" of liquid, "heat" of evaporation and "total heat" of steam are now technically known as the *enthalpy of the (saturated) liquid, enthalpy of evaporation, enthalpy of saturated vapor and enthalpy of the superheated vapor.*

The enthalpy of water or steam is the heat that must be added, Btu per lb, to bring it from liquid at 32 F to its present temperature, pressure and condition. Enthalpy of evaporation is the enthalpy difference between saturated liquid and dry saturated vapor.

In Table 1, for example, turn to the line for atmospheric pressure, 14.7 psi abs, corresponding to a saturation temperature of 212 F. Enthalpy of the

liquid is given as 180.0 Btu. This means that if you hold 1 lb of water at a constant pressure of 14.7 psi abs and heat it from 32 F to 212 F the heat supplied will be 180 Btu.

For low pressures and temperatures, enthalpy of water can be estimated by subtracting 32 from water temperature. (To reduce error at higher pressures, use saturation tables like those on p 91, or complete ones. For maximum accuracy, use compressed-liquid table. For example, take water at 300 F and 1000 psia. Rule of thumb shows  $300 - 32 = 268$  Btu, saturation table 269.6. Applying correction from compressed-liquid table gives true 271.4 Btu.)

The same line tabulates the enthalpy of evaporation as 970.4 Btu. This means that (at 14.7 psi abs and 212 F) it takes 970.4 Btu to convert one pound

of boiling water into dry saturated steam. If the flow of heat is reversed, as when this same steam condenses at atmospheric pressure, 970.4 Btu will flow out as each pound of dry saturated steam at 212 F is reconverted to a pound of liquid at 212 F.

Next add 180.0 and 970.4 to give 1150.4 Btu, the total heat that must be supplied to convert one pound of water at 32 F into dry saturated steam. The table lists this figure as the *enthalpy of the saturated vapor.*

If, now, the steam is taken away from the presence of the boiling water and is then heated in a superheater, its temperature will rise above the saturation temperature, and its enthalpy will increase by the amount of heat supplied per pound. Total enthalpy of superheated steam is given in Table 3.

## HELPFUL HINTS

**THROTTLING.** When steam expands without doing mechanical work, its enthalpy does not change. This type of expansion is called throttling, and occurs whenever flowing steam encounters fixed resistances such as orifices, throttling valves, pipe friction or cramped fittings. Examples of how to figure what happens when steam is throttled are shown on the next two pages, along with examples of how to use the following practical hints.

**HEATING OR COOLING WATER.** Amount of heat supplied or removed to heat or cool one pound of water is simply the

change in enthalpy. For all cases within range of everyday operation in low- and medium-pressure steam plants take enthalpy change in the water as equal to the temperature change.

**STEAM GENERATION, CONDENSATION.** Heat supplied by a steam generator to convert feedwater into steam is merely the enthalpy of the final steam minus the enthalpy of the feedwater.

Heat removed from a pound of exhaust steam by a condenser is the enthalpy of the exhaust steam minus the enthalpy of water entering the hot well. Note, however, that the exhaust steam


is almost always wet, so its enthalpy cannot be taken directly from the table.

The enthalpy of wet steam is the enthalpy of the liquid plus the dryness percent multiplied by the enthalpy of the evaporation. It can also be figured as the enthalpy of the saturated vapor minus the percent moisture multiplied by the enthalpy of evaporation.


**EFFICIENCY.** The thermal efficiency of any device is its output divided by its input. In the case of a steam generator the output is the heat required to convert the feedwater into the delivered steam. The input is the heat in the fuel.

# FIGURING TURBINE PERFORMANCE


**BASIC CYCLES** on which turbines operate affect figuring of performance factors—see text below for calculation procedures



**NONCONDENSING OR BACKPRESSURE UNIT**



**STRAIGHT CONDENSING UNIT**



**REGENERATIVE FEEDHEATING UNIT**

Turbines convert energy in steam to shaft energy. In selecting and operating them, we're always interested in how effectively this is done. Turbine performance is measured in various ways. Here are common ones:

**STEAM RATE** is amount of steam required by a turbine to produce a given unit output—usually expressed in lb per kw-hr. It is of direct practical concern in figuring boiler steam needs and performance changes of individual turbines. It has only limited value for comparing different turbines because it doesn't reflect changes in throttle pressure, as does heat rate.

**HEAT RATE** is amount of energy to produce a given unit output—usually expressed as Btu per kw-hr. Because it deals with basic heat units, it is better than steam rate for comparing turbines.

**THERMAL EFFICIENCY** is ratio of energy output to energy input. It is directly related to heat rate: thermal efficiency = 3413/heat rate. See chart.

**ENGINE EFFICIENCY** is measure of how well an actual turbine compares with an ideal one. Expanding from given throttle to exhaust conditions, a lb of steam does maximum work if expansion is at constant entropy. This ideal condition is never obtained. When actual work done by a lb of expanding steam is divided by ideal expansion

work, the resulting ratio is engine efficiency. It serves as a measure of design effectiveness.

**FOR ALL TYPES OF TURBINES:**

$$\text{Steam rate, lb per kw-hr} = \frac{\text{steam flow, lb per hr } (W_1)}{\text{generator or shaft output, kw-hr } (P)}$$

**FOR BACKPRESSURE TURBINES:**

$$\text{Heat rate, Btu per kw-hr} = \frac{W_1 (h_1 - h')}{P}$$

$h_1$  = steam enthalpy entering turbine, Btu per lb (see diagram)  
 when steam exhausts to process:  
 $h'$  = actual exhaust enthalpy, Btu per lb  
 when steam exhausts to waste:  
 $h'$  = saturated-water enthalpy at exhaust pressure, Btu per lb (see diagram)

$$\text{Engine efficiency} = \frac{3413 P}{(W_1 - W_2) (h_1 - h_2) + W_2 (h_1 - h_{2s})}$$

$W_2$  = steam leaving turbine system from glands and leaks, lb per hr  
 $h_2$  = exhaust-steam enthalpy at entropy of initial steam, Btu per lb  
 $h_{2s}$  = leakoff steam enthalpy at entropy of initial steam, Btu per lb

**FOR STRAIGHT-CONDENSING TURBINES**

$$\text{Heat rate, Btu per kw-hr} = \frac{(W_1 - W_2) (h_1 - h_2) + W_2 (h_1 - h_{2s})}{P}$$

$h_2$  = saturated-water enthalpy at exhaust pressure, Btu per lb (see diagram)  
 $h_{2s}$  = vaporization enthalpy of leakoff steam at discharge press., Btu per lb

$$\text{Engine efficiency} = \frac{3413 P}{(W_1 - W_2) (h_1 - h_2) + W_2 (h_1 - h_{2s})}$$

**FOR REGENERATIVE TURBINES:**

$$\text{Heat rate, Btu per kw-hr} = \frac{W_1 (h_1 - h_f) + (W_1 h_2 - h_2)}{P}$$

$h_f$  = enthalpy of feedwater leaving last heater, Btu per lb  
 $h_2$  = enthalpy of feedwater leaving boiler-feed pump, Btu per lb  
 $h_2$  = enthalpy of feedwater entering boiler-feed pump, Btu per lb (see diagram)  
 Engine efficiency =  $\frac{3413 P}{W_1 (h_1 - h_{2s1}) + W_2 (h_1 - h_{2s2}) + \dots + W_n (h_1 - h_{2sn}) + W_0 (h_1 - h_{2e}) + W_e (h_1 - h_{2e})}$


$W_1, W_2, W_n$  = bleed steam flows, lb per hr  
 $h_{2s1}, h_{2s2}, h_{2sn}$  = enthalpies of bleed steam at initial steam entropy, Btu per lb  
 $W_0$  = exhaust steam flow, lb per hr  
 $h_{2e}$  = exhaust steam enthalpy at initial steam entropy, Btu per lb

**FOR ALL TYPES OF TURBINES:**

$$\text{Thermal efficiency} = \frac{3413}{\text{Heat rate, Btu per kw-hr}}$$

**PERFORMANCE VARIATIONS.** Steam rate, heat rate, thermal efficiency and engine efficiency plotted against shaft or generator output in kw show turbine-performance variation with load. Common method for showing performance for automatic-extraction and mixed-pressure turbines plots total hourly steam flow against output for a range of extraction flows.

Turbine performance changes with variations in steam pressure, and temperature, exhaust pressure, makeup-water flow, etc. For methods of figuring corrections for these factors see *Test Code for Steam Turbines*, PTC 6-1949, published by ASME, 29 West 39th St., New York 18, N. Y.



**CONVERSION SCALE** permits quick transfer from thermal efficiency (percent) to heat rate (Btu per kw-hr) for usual range



SECTION 6  
MODES OF OPERATION AND TRANSITIONS

The operating modes and transitions for each subsystem are described below:

Receiver Operating Modes

- RS1 Receiver cold and drained
- RS2 Receiver drained with trace heat on
- RS3 Receiver drained with trace heat on and warm-up heliostats
- RS4 Receiver cold flow with trace heat on and warm-up heliostats
- RS5 Receiver cold flow with trace heat on, no warm-up heliostats and receiver door closed
- RS6 Receiver operation, manual with flow control
- RS7 Receiver operation, temperature control

Receiver Transitions

- o Start-up
  - RS1 to RS2 - Turn on trace heaters
  - RS2 to RS3 - Drained and warm to warm-up heliostats
  - RS3 to RS4 - Warm-up heliostats to cold flow through receiver
  - RS4 to RS5 - Cold flow through receiver with receiver door closed
  - to RS6 - To salt flow through receiver with flow control
  - to RS7 - To salt flow through receiver with temperature control
  - RS6 to RS7 - Salt flow with flow control to temperature control
- o Shutdown
  - RS7 to RS6 - Salt flow with temperature control to flow control
  - to RS5 - Salt flow with temperature control to cold flow with door closed
  - to RS2 - Salt flow with temperature control to drained with trace heat on

RS6 to RS5 - Salt flow with flow control to cold flow with door closed  
to RS2 - Salt flow with flow control to drained with trace heat on  
RS5 to RS2 - Cold flow with door closed to drained with trace heat on  
RS4 to RS2 - Cold flow with warm-up heliostats to drained with trace heat on  
RS3 to RS2 - Drained with warm-up heliostats to drained with trace heat  
RS2 to RS1 - Turn off trace heaters

#### Thermal Storage Operating Modes

TSS1 Hot tank drained and cold  
TSS2 Hot and cold salt tanks warm and ready for operation  
TSS3 Charging with propane heater

#### Thermal Storage Transitions

o Start-up TSS1 to TSS2 - Pre-test check lists to pre-conditioning hot salt tank  
TSS2 to TSS3 - Pre-test check lists to charging hot salt tank  
o Shutdown TSS3 to TSS2 - Charging hot salt tank to shutdown, salt in both tanks  
TSS2 to TSS1 - Drain hot tank

#### Steam Generator Subsystem Operating Modes

SGS1 SGS cold and drained  
SGS2 SGS warm and salt drained (diurnal shutdown)  
SGS3 SGS warm standby (cold salt flow)  
SGS4 SGS operating in boiler following mode  
SGS5 SGS operating in turbine following mode

#### Steam Generator Transitions

o Start-up SGS1 to SGS2 - Pre-test check lists, pre-heat to diurnal shutdown



SGS2 to SGS3 - Diurnal shutdown to cold salt flow  
SGS3 to SGS4 - Cold salt flow to boiler following mode  
SGS4 to SGS5 - Boiler following to turbine following mode

- o Shutdown SGS5 to SGS4 - Turbine following to boiler following mode
- SGS4 to SGS3 - Boiler following mode to cold salt flow
- SGS3 to SGS2 - Cold salt flow to diurnal shutdown
- SGS2 to SGS1 - Diurnal shutdown to drained and cold

#### Electric Power Generation Subsystem Operating Modes

EPGS1 Shutdown  
EPGS2 (Turbine standby) EPGS pumps on  
EPGS3 EPGS standby (operating - offline)  
EPGS 4 EPGS on-line (operating - synchronized)

#### Electric Power Generation Subsystem Transitions

- o Start-up EPGS 1 to EPGS 2 - Pre-test check lists, pre-op and start-up pumps
- EPGS 2 to EPGS 3 - Turbine standby to EPGS standby
- EPGS 3 to EPGS 4 - EPGS standby to on-line
  
- o Shutdown EPGS 4 to EPGS 3 - On-line to standby
- EPGS 3 to EPGS 2 - EPGS standby to turbine standby
- EPGS 2 to EPGS 1 - Turbine standby to shutdown

Valve alignments for remote-operated valves are given in Table 6.1 for pretest, operating, and post-test modes.

FIGURE 6.1 MSEE REMOTE OPERATED VALVE ALIGNMENT

VALVE	FUNCTION	PRETEST			OPERATION		POST TEST
		BASIC FULL SYSTEM	MODIFICATION TO OPERATE 1. W/O RECVR 2. W/ OR W/O PROPANE HTR	MODIFICATION TO OPERATE 1. RECVR ONLY -OR- 2. PROPANE HTR ONLY	BASIC FULL SYSTEM	MODIFICATION TO OPERATE 1. W/O RECVR -AND- 2. W/PROPANE HTR	
FCV-101	RECVR FLOW CTRL	<input type="radio"/> MAN			<input checked="" type="radio"/> CASC SR,SALT SP 1000 °F	<input type="radio"/> MAN	<input type="radio"/> MAN
FCV-102	RECVR FLOW CTRL	<input type="radio"/> MAN			<input checked="" type="radio"/> CASC SP,SALT SP 1000 °F	<input type="radio"/> MAN	<input type="radio"/> MAN
FCV-151	CST LEVEL CTRL	<input checked="" type="radio"/> MAN	<input checked="" type="radio"/> L MAN	<input checked="" type="radio"/> L MAN (W/HTR)	<input checked="" type="radio"/> CASC LT-151 SP 87"	<input checked="" type="radio"/> L MAN	<input type="radio"/> MAN
FCV-161	HST LEVEL CTRL	<input checked="" type="radio"/> AUTO SP 75"	<input checked="" type="radio"/> L MAN	<input checked="" type="radio"/> L MAN (W/HTR)	<input checked="" type="radio"/> AUTO SP 20"	<input checked="" type="radio"/> L MAN	<input type="radio"/> MAN
FCV-162	HST LEVEL CTRL	<input checked="" type="radio"/> AUTO SP 20"	<input type="radio"/> MAN	<input type="radio"/> MAN (W/HTR)	<input checked="" type="radio"/> AUTO SP 20"	<input type="radio"/> MAN	<input type="radio"/> MAN
FCV-180-189	RECVR DRAIN	<input type="radio"/>			<input checked="" type="radio"/>		<input checked="" type="radio"/>
FCV-190-198	RECVR PURGE	<input type="radio"/>			<input checked="" type="radio"/>		<input checked="" type="radio"/>
FCV-199	RECVR DRAIN & FILL	<input type="radio"/>			<input checked="" type="radio"/>		<input type="radio"/>
FCV-201	COLD SUMP LEVEL CTRL	<input checked="" type="radio"/> AUTO SP 23"			<input checked="" type="radio"/> AUTO SP 23"		<input checked="" type="radio"/> MAN
FCV-211	COLD SUMP ISOLATE	<input checked="" type="radio"/> L			<input type="radio"/>		<input checked="" type="radio"/> L
FCV-221	HOT SUMP LEVEL CTRL	<input checked="" type="radio"/> AUTO SP 20"			<input checked="" type="radio"/> AUTO SP 20"		<input checked="" type="radio"/> MAN
FCV-231	HOT SUMP ISOLATE	<input checked="" type="radio"/> L			<input type="radio"/>		<input checked="" type="radio"/> L
FCV-241	PROPANE HTR FLOW CTRL	<input checked="" type="radio"/> L			<input checked="" type="radio"/> L	<input checked="" type="radio"/> x% MAN	<input checked="" type="radio"/>
FCV-242	PROPANE HTR ISOLATE	<input checked="" type="radio"/> L	<input checked="" type="radio"/> (W/HTR)	<input checked="" type="radio"/> (W/HTR)	<input checked="" type="radio"/> L	<input type="radio"/>	<input checked="" type="radio"/>
FCV-301	EVAP SALT TEMP CTRL	<input checked="" type="radio"/> MAN ON		<input checked="" type="radio"/> L MAN ON	<input checked="" type="radio"/> MAN OFF N90 CASC		<input checked="" type="radio"/> MAN ON
FCV-321	SGS SALT FLOW CTRL	<input type="radio"/> MAN ON			<input checked="" type="radio"/> MAN OFF N90 CASC		<input type="radio"/> MAN ON
FCV-331	STEAM TEMP CTRL	<input type="radio"/> 10% MAN ON			<input checked="" type="radio"/> MAN OFF N90 CASC		<input type="radio"/> 10% MAN ON
FCV-341	SGS COLD SALT FILL CTRL	<input checked="" type="radio"/> MAN ON		<input checked="" type="radio"/> L MAN ON	<input checked="" type="radio"/> MAN ON		<input checked="" type="radio"/> MAN ON
FCV-351	SGS HOT SALT FILL CTRL	<input checked="" type="radio"/> MAN ON			<input type="radio"/> MAN ON		<input checked="" type="radio"/> MAN ON
FCV-381	EVAP SALT DRAIN	<input type="radio"/> MAN ON			<input checked="" type="radio"/> MAN ON		<input checked="" type="radio"/> MAN ON
FCV-382	SUPHTR SALT DRAIN	<input type="radio"/>			<input checked="" type="radio"/>		<input checked="" type="radio"/>
FCV-383	START-UP HTR BYPASS	<input checked="" type="radio"/> MAN ON			<input type="radio"/> MAN ON		<input checked="" type="radio"/> MAN ON
FCV-384	START-UP HTR ISOLATE	<input type="radio"/> MAN ON			<input checked="" type="radio"/> MAN ON		<input type="radio"/> MAN ON
FCV-401	FWP PRESSURE CTRL	<input checked="" type="radio"/> AUTO SP 1250			<input checked="" type="radio"/> AUTO SP 1250		<input checked="" type="radio"/> AUTO SP 1250
FCV-411	FEEDWTR FLOW CTRL	<input checked="" type="radio"/> MAN ON			<input checked="" type="radio"/> MAN OFF N90 CASC		<input checked="" type="radio"/> MAN ON
FCV-421	FWH TEMP CTRL	<input type="radio"/> AUTO SP 520 °F			<input checked="" type="radio"/> AUTO SP 520 °F		<input type="radio"/> AUTO SP 520 °F
FCV-431	DA OR STEAM PRESS CTRL	<input checked="" type="radio"/> CASC PT-431 SP 1080			<input checked="" type="radio"/> CASC PT-432 SP 233		<input checked="" type="radio"/> CASC PT-431 SP 1080
FCV-432	DA PRESSURE CTRL	<input type="radio"/> AUTO SP 233			<input checked="" type="radio"/> AUTO SP 240		<input type="radio"/> AUTO SP 233
FCV-471	DA LEVEL CTRL	<input checked="" type="radio"/> AUTO SP 0"			<input checked="" type="radio"/> AUTO SP 15"		<input checked="" type="radio"/> AUTO SP 0"
FCV-483	DA VENT NO. 1	<input type="radio"/> LOCAL			<input type="radio"/> LOCAL		<input checked="" type="radio"/> LOCAL
FCV-484	DA VENT NO. 2	<input checked="" type="radio"/> LOCAL			<input checked="" type="radio"/> LOCAL		<input checked="" type="radio"/> LOCAL
FCV-485	DEMIN WATER TANK FILL	<input checked="" type="radio"/> LOCAL			<input checked="" type="radio"/> LOCAL		<input checked="" type="radio"/> LOCAL
FCV-491	START-UP STEAM CTRL	<input checked="" type="radio"/> AUTO SP 1000			<input type="radio"/> AUTO SP 1000		<input checked="" type="radio"/> AUTO SP 1000
FCV-501	TURBINE STOP	<input checked="" type="radio"/>			<input type="radio"/>		<input checked="" type="radio"/>
FCV-511	HOT WELL OVERFLOW	<input checked="" type="radio"/>			<input checked="" type="radio"/>		<input checked="" type="radio"/>
FCV-512	HOTWELL MAKE-UP	<input checked="" type="radio"/> EN,HLC OFF (LOCAL CNTRL)			<input checked="" type="radio"/> EN,HLC ON (AUTO CNTRL)		<input checked="" type="radio"/> EN,HLC OFF (LOCAL CNTRL)
FCV-521	OIL COOLANT FLOW CTRL	<input checked="" type="radio"/> AUTO SP 120 °F			<input checked="" type="radio"/> AUTO SP 120 °F		<input checked="" type="radio"/> MAN
FCV-541	CNST MAKE-UP	<input checked="" type="radio"/> LOCAL CNTRL			LOCAL CNTRL		<input checked="" type="radio"/> LOCAL CNTRL
FCV-551	CONDENSATE RECIRC	<input checked="" type="radio"/>			<input checked="" type="radio"/>		<input checked="" type="radio"/>
FCV-561	TURBINE TRIP	<input checked="" type="radio"/> ET OFF			<input checked="" type="radio"/> ET OFF		<input checked="" type="radio"/> ET OFF
TVM	TURBINE THROTTLE	<input checked="" type="radio"/>			<input checked="" type="radio"/>		<input checked="" type="radio"/>
		<input checked="" type="radio"/> L	<input type="radio"/> OPEN	<input checked="" type="radio"/> CONTROLLING			
		↑ LOCKED	↑ OPEN	↑ CONTROLLING			
		↑ CLOSED					



# 7.1 CONSOLE OPERATING PROCEDURES

## COP #1 CONTROL ROOM PRETEST CHECKLIST

TEST DATE  
9/18/84

This Console operating procedure will be utilized to verify process control integrity prior to all tests. It is unnecessary to verify control integrity of subsystems not used (not applicable). This checklist shall be completed by the control room process console operator.

### I. Test Description \_\_\_\_\_

Start Time \_\_\_\_\_

### II. Responsible operating personnel

Primary

Backup

Test Conductor (MDAC)

Stan Saloff

HelioStat Operator

Arleen Vance

Console Operator

Evans/Nelson

Operation/Safety Engineer

John Holmes

Subsystem Technicians

RS

Jerome Griego

TSS

Matt Matthews

SGS

Matt Matthews

HRFS

Jay Holton

EPGS

Jay Holton

**COP #1 CONTROL ROOM PRETEST CHECKLIST**

O/S

**III. Safety Checklist**

**Complete this checklist for all operations.**

**1. Site occupants**

**A. Verify that all test personnel have been briefed on the scheduled test description, objectives, individual responsibilities, and expected response to emergencies**

**B. Communications established to all manned control points**

**C. Safety equipment in place:**

**1. OSHA protective gloves**

**2. Fire retardant coveralls**

**3. Hard hats/Face shields**

**4. Approved fire extinguishers**

**2. Solar only**

**A. "Test In Progress" lights on in the tower**

**B. Non-Test personnel informed and in secure location**

**C. Diesel-Generator on and frequency OK**

**D. Field monitor on call after solar start-up**

**E. Communications established**

**F. Tower top barricade up**

**G. Gates closed and posted with red lights or signs**

**H. Field clear and ready for start-up**

**3. Control Room locked**

**4. Beam up command shall be given only after above checklist is completed by O/S Engineer**



COP #1 CONTROL ROOM PRETEST CHECKLIST

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
<b>B. ACUREX START-UP CHECKLIST</b>		
Complete this checklist for all operations using salt.		
1.	Equipment powered up: a) Host chassis - Autodate Ten/50 b) Electrohome monitor c) GT-100 Terminal d) Texas Instruments 820 R0 Terminal	_____
2.	Tape Cassette loaded in host drive.	_____
3.	Recent (within 60 minutes) logout of temperatures available on T1 printer.	_____ Last Print Time
4.	Set scan rate to every 60 minutes.	_____
<b>C. AUXILIARY DATA LOGGING/DISPLAY SYSTEM</b>		
Data acquisition checklist completion optional as required.		
1.	Equipment powered up: a) H-P 1000 Cabinet b) H-P 2645 Terminal c) H-P 2621 Terminal d) Tektronix 4014 Terminal e) Tektronix 463 hard-copy unit f) (6) Display CRTs g) Versatec Video Copier h) Versatec Printer i) H-P 7925 Disc Drive	_____
2.	Disk pack installed in drive, disc drive running with "READY" lamp lit.	_____
3.	System booted: a) Correct date and time b) Transfer file IMSRP executed	_____
4.	MSPAS program executing when data logging/display is required and MSSN2 has been started on the EMCON host.	_____
5.	Following support programs available for execut: a) MSRTP b) MSPSU c) MSDSD d) MSSL1 through MSSL6 e) MSCDT	_____
6.	Label file used: _____	_____
7.	Data file used: _____	_____

**COP #1 CONTROL ROOM PRETEST CHECKLIST**

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
-------------	--------------------	---------------------

**D. NETWORK 90 SETUP CHECKLIST**

Complete this checklist for operation with SGS.

1. Verify equipment powered up and operational.

- a) Bailey PCU
- b) Operator Interface Drive Unit
- \*c) Keyboard Console
- \*d) Printer

\*These components may be turned off when not in use.

**V. RS - RECEIVER SUBSYSTEM**

Complete this checklist for operation with Receiver.

- 1. Verify acceptable limits on winds (less than 30 MPH), solar insolation (above 600 W/m<sup>2</sup>) and cloud condition (partly cloudy or clear). ✓
- 2. Verify TV cameras are on and operational. ✓
- 3. Verify the Control Room SCRAM and EPS power supplies behind Weather Monitor Panel are On and set at 24VDC. ✓
- 02 4. Open the Receiver cavity door upon the request of the RS technician for the RS pretest check. Reclose or leave open as required. (DR.OPN/CLS). \*
- 07 5. Verify Emcon RS header temperatures are above 480°F. (TE-188 inoperable). ✓ ✓
- 6. Verify the Acurex RS trace heaters are operating and the temperatures are above 480°F (Table A). NOTE EXCEPTIONS. If required, heat tracing control can be taken over locally at the module control room. ✓
- 7. Align/verify the following valve alignment; confirm valve temps are acceptable before moving. (to avoid bellows damage) Coordinate with Receiver technician. RCK 'ON' may be used to auto align these, turning itself off when complete. ✓

10 33  
Time

	<u>Valve</u>	<u>Description</u>	<u>Position</u>		
01	FCV-101	Salt flow control	Man/Open/N ✓	OPEN	6°C output
	FCV-102	Salt flow control	Man/Open/N ✓	OPEN	6°C output
	FCV-180-189	Drain valves	On/Open/N ✓		(ZSH180-189 On) 08
	FCV-190-198	Purge valves	On/Open/N ✓		(ZSH190-198 On) 09
04	CSP.EN	Enable CSP control	On ✓		
	BP.EN	Enable BP control	ON		



STEP DESCRIPTION VERIFICATION

VI. TSS - THERMAL STORAGE SUBSYSTEM

Complete this checklist for all operations using salt.

1. Verify that the Acurex TSS trace heaters are operating and the temperatures are above 480°F (Table B). NOTE EXCEPTIONS.  
If req'd heat tracing control can be controlled locally at salt storage control building.
2. If operating Propane Heater without SGS, verify that these Acurex SGS inlet trace heaters are above 480°F (Ref. Table C):

✓ 11:00  
Time

<u>Channel</u>	<u>Channel</u>	<u>Local Temp. Verific.</u>
204	255	FCV-241
205	256	Hot Tank inlet line
206	257	
	258	

3. Verify salt levels in storage tanks and sumps are commensurate with test requirements:

LT-201 Cold Sump	<u>47.3</u> in. (60" max)**@ <u>639.4</u> °F	(Acurex Chan 124,125)
LT-281 Cold Tank	<u>5.3</u> in. (40" min)* @ <u>562.9</u> °F	(Acurex Chan 110-112)
LT-221 Hot Sump	<u>7.6</u> in. (45" max)**@ <u>721.6</u> °F	(Acurex Chan 126,127)
LT-291 Hot Tank	<u>98.6</u> in. @ <u>562.9</u> °F	(Acurex Chan 134-136)

\*Minimum level req'd to maintain cold sump level during fill operations.  
\*\*Maximum levels require vent checks; advise technician.

4. Align/verify the following valves for operation with RS, with SGS, & without Propane Heater. Confirm valve temps are accept. before moving. Coordinate with thermal storage technician. TCK 'ON' may be used to auto align these, turning itself off when complete.

<u>Valve</u>	<u>Description</u>	<u>Position</u>
*FCV-151	CST Level Control	Man/Closed/N ✓
FCV-161	HST Level Control(Hot)	Man/Closed/N ✓
FCV-162	HST Level Control(Cold)	Man/Closed/N ✓
FCV-199	Bypass valve	Off/Open /N ✓
FCV-201	Cold Sump Level Control	Auto/Closed/N SP 23" ✓ (ZSH199 on)
FCV-211	Cold Sump Isol. (OPN/CLS.211)	Closed/Locked ✓ (ZSL211 on)
FCV-221	Hot Sump Level Control	Auto/Closed/N SP 20" ✓
FCV-231	Hot Sump Isol. (OPN/CLS.231)	Closed/Locked ✓ (ZSL231 on)
FCV-241	Propane Heater Inlet	Man/Closed/Locked ✓
FCV-242	Propane Heater Isolation	Off/Closed/Locked ✓ (ZSL242 on)
FCV-301	Bypass Salt Flow	Closed/N ✓ (MAN on, SP Auto 0%)
FCV-341	Cold Salt Isol.	Closed/N ✓ (MAN on, SP Auto 0%)
FCV-351	Hot Salt Isol.	Closed/N ✓ (MAN on, SP Auto 0%)
CSP.EN	Enable CSP Control	On ✓

\*Bad signal (blue) can indicate EPS closure. Clear trips and reset EPS1 & EPS3 to regain control.

COP #1 CONTROL ROOM PRETEST CHECKLIST

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
-------------	--------------------	---------------------

5. For operation with Propane Heater instead of Receiver OR for SGS alone, Modify the valve alignment of step 4 as follows:

	<u>Valve</u>	<u>Position</u>
—	FCV-151	Locked
02	FCV-161	Locked
<u>05</u>	FCV-162	Man/Open/N
	FCV-242	Neutral

6. For operation without SGS, Modify the valve alignment of step 4 as follows:

	<u>Valve</u>	<u>Position</u>
13	FCV-301	Locked
	FCV-341	Locked

04 7. Verify pump bearing temp's are less than 190°F (TE 180, 286, & 387 on EMCON) and alarms on.

VII. SGS - STEAM GENERATION SUBSYSTEM

Complete this checklist for operation with SGS.

1. Verify that the Acurex SGS trace heaters are operating and the temperatures are above 480°F (Table C). NOTE EXCEPTIONS. If required, heat tracing control can be taken over locally at the salt storage control building Acurex cabinet back.
2. Align/verify the following valve positions. Confirm valve temps are accept. before moving. Coordinate with thermal storage technician. All SGS control valve MAN signals should be On. (Emcon commands not applicable from Net 90) SCK 'ON' may be used to auto align these, turning itself off when complete.

	<u>Emcon Command</u>	<u>Valve Description</u>	<u>Position</u>
—	MAN.321 On/ SP-321 Auto 100%	Main Salt Flow	Open
	MAN.331 On/ SP-331 Auto 10%	Steam Attemp.	10% Open
13	MAN.38182 On/FCV-38182 On	Salt Drain	Open
	*MAN.384 On/ FCV-384 On	Circ Htr Supply	Open
	*MAN.383 On/ FCV-383 Off	Circ Htr Bypass	Closed
<u>04</u>	HSP.EN	Enable HSP Control	On

\*Open FCV-384 before closing FCV-383 to avoid SGS Pump and Heater Shut-off

**COP #1 CONTROL ROOM PRETEST CHECKLIST**

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
-------------	--------------------	---------------------

Complete the following steps after completing HRFS startup.  
(Presuming SGS is in Diurnal Shutdown).

- |                        |  |       |
|------------------------|--|-------|
|                        | 3. If SGS F.W. inlet pipe temp. (Acurex Channel 132) is below 200°F, increase bridge pipe feedwater temperature:   |       |
| <i>Key in group 16</i> | a) Verify D/D TE-451 is above 250°F  | _____ |
|                        | b) Advise the SGS technician to open the bridge feedwater drain HV-370, then open FCV-411 to 20% (Emcon MAN.411 on/SP Auto 20%)  | _____ |
|                        | c) Verify Acurex channel 132 increases above 200°F (Approx 5 min after opening FCV-411)  | _____ |
|                        | d. Reclose HV-370 and FCV-411  | _____ |
|                        | 4. Verify drum level LT-311 is at 0.0 inches. If drum level is below 0.0 inches; open HV-488, then open FCV-411 to 20% and fill to 0.0". Close FCV-411 and HV-488 to avoid FW leakage into drum. | _____ |
|                        | 5. Verify that the boiler water circulation pump (BWCP) <u>is</u> running (ZSHBCP). If it is <u>not</u> running:   |       |
|                        | a) Review overnight data to determine reason and correct.  |       |
|                        | b) Start BWCP  |       |
|                        | c) Start circulation heater (pulse EHAC.ON)  | _____ |
|                        | 6. If freezing ambient temperatures have been experienced, resolve any suspicious instr. transmitter readings with the SGS technician. Be skeptical of all readings until proven.                | _____ |

**COP #1 CONTROL ROOM PRETEST CHECKLIST**

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
-------------	--------------------	---------------------

**VIII. HRFS - HEAT REJECTION AND FEEDWATER SUBSYSTEM**

Complete this checklist for all water system operations.

1. Set/Verify the following control devices in the listed positions: HCK 'ON' may be used to auto align these, turning itself off when complete.

	<u>Identifier</u>	<u>Description</u>	<u>Command</u>	<u>Position</u>
call up	GSTAT	D/D Press Enable	Off	N/A
	EN.DTC451	D/D Heater 1 Enable	Off	N/A
	EN.DTC452	D/D Heater 2 Enable	Off	N/A
	DTC-451	D/D Heater 1	Auto SP 390 or 400°F	Not Enabled
	DTC-452	D/D Heater 2	Auto SP 390 or 400°F	Not Enabled
	FCV-401	FWP Press Recirc	Auto SP 1250 psf	Closed
	FCV-411	Feedwater Delivery	MAN.411 On/SP-411 AUTO 0%	Closed
	FCV-421	FWH Steam Supply	Man	Closed
18	FCV-431	D/D Steam Inlet	Auto/Casc to PT-431	Closed
	PT-431	Steam Line Press	Auto SP 1080 psf	N/A
	PT-432	D/D Press	Auto SP 233 psf	N/A
	FCV-432	SWHX Divert	Auto SP 240 psf	Open to Bypass
	FCV-471	T-G Condensate Return	Auto SP 0%	Closed
	FY-472	CMUP Stroke Positioner	Auto SP 0%	Closed
	FCV-491	SGS Steam Delivery	Auto SP 900 psf	Closed
	*FCV-501	Main Steam Stop	Off/ZSL-501 On	Closed
	*TVM	Turbine Steam	TVM.OPN Off/ZT-581 0% Open	Closed
19/20	FWP.EN/SWP.EN/CWP.EN/CMP.EN/CFP.EN/CF1.EN thru CF6.EN			On

\*Note EMCON control for these valves is disabled if TCPMS is in Total (off).

**IX. EPGS ELECTRIC POWER GENERATION SUBSYSTEM**

- 19 1. PP.EN SIGNALS ON-CTP.EN,CTF.EN,EOP:.EN,AEP.EN,  
20 CWP.EN,FCV-521 Auto SP 120, FCV-501 off, EN. HLC off,  
21 VIB.OVR on. PCK may be used to auto align these, turning itself off when complete.

1.1 Verify RGP Gen Breaker green (open) light is on.

- 21 2. Confirm correct selection of EPGS operating mode, Remote (TCPMS On) or Local (TCPMS Off).

3. Verify Generator operator has procured the Sync switch handle from the MSEE key box.

4. Disable auto hotwell level control by turning EN.HLC off.

5. Override EPS vibration trips by turning VIB.OVR on.

- 26 6. Momentarily enable EPS3.RST and EPS2.RST.

- 21 7. Verify FCV-521 Oil Cooler C.W. is in Auto with a SP of 120°F Closed. (Emcon control disabled if TCPMS is in local (off)).

T/C	DESCRIPTION	ACUREX CHANNEL	T/C	DESCRIPTION	ACUREX CHANNEL
TEH-190	Purge Valve #1	000 ✓	TEH-157	Receiver Outlet-Heater R	027 ✓
TEH-191	Purge Valve #2	001 ✓	TEH-158	Receiver Outlet-Heater R	028 ✓
TEH-192	Purge Valve #3	002 ✓	TEH-153	Hot Surge Tank Inlet-Heater N	029 ✓
TEH-193	Purge Valve #4	003 ✓	TEH-159	Hot Surge Tank Outlet-Heater N	030 ✓
TEH-194	Purge Valve #5	004 ✓	TEH-152	Cold Surge Tank Inlet-Heater O	031 ✓
TEH-195	Purge Valve #6	005 ✓	TEH-156	Cold Surge Tank-Heater O	032 ✓
TEH-196	Purge Valve #7	006 ✓	TEH-150	Receiver Inlet-Heater P	033 ✓
TEH-197	Purge Valve #8	007 ✓	TEH-151	Receiver Inlet-Heater P	034 ✓
TEH-198	Purge Valve #9	008 ✓	TEH-162	FCV-101-Heater Q	035 ✓
TEH-180	Drain Valve #1	009 ✓	TEH-163	FCV-102-Heater Q	036 ✓
TEH-181	Drain Valve #2	010	TEH-154	Drain Line-Heater T	037 ✓
TEH-182	Drain Valve #3	011	TEH-155	Drain Line-Heater T	038 ✓
TEH-183	Drain Valve #4	012	TEH-166	Hot Surge-Heater U	039 ✓
TEH-184	Drain Valve #5	013 ✓	TEH-167	Hot Surge-Heater U	040 ✓
TEH-185	Drain Valve #6	014 ✓	TEH-164	Cold Surge-Heater V	041 ✓
TEH-186	Drain Valve #7	015 (Bad)	TEH-165	Cold Surge-Heater V	042 ✓
TEH-187	Drain Valve #8	016	TEH-131	Riser-Heater H	300 ✓
TEH-188	Drain Valve #9	017 ✓	TEH-133	Riser-Heater I	301 ✓
TEH-189	Drain Valve #10	018	TEH-134	Riser-Heater I	302 ✓
TEH-160	Purge Line-Heater S	019	TEH-135	Riser-Heater J	303 ✓
TEH-161	Purge Line-Heater S	020	TEH-136	Riser-Heater J	304 ✓
TEH-176	Drain Line	021 ✓	TEH-130	Downcomer-Heater K	305 ✓
TEH-177	Drain Line	022	TEH-132	Downcomer-Heater L	306 ✓
TEH-172	Outlet of Pass #1 (Header)	023	TEH-137	Downcomer-Heater M	307 ✓
TEH-173	Pass #10	024	TEH-138	Downcomer-Heater M	308 ✓
TEH-174	Pass #11	025 ✓	TEH-139	Downcomer-Heater L	(Skip) 309
TEH-175	Pass #18	026 ✓			

TABLE A RS HEAT TRACE INSTRUMENTATION

TSS Heat Trace Instrumentation

T/C	DESCRIPTION	ACUREX CHANNEL	T/C	DESCRIPTION	ACUREX CHANNEL
TEH-218	Hot Tank Outlet	(B)100	TEH-207	Boost Pump Outlet - Heater A	122 <sup>450.4</sup>
TEH-216	FCV-211, Line X	(B)101	TEH-208	Boost Pump Outlet - Heater A	123
TEH-219	Hot Sump Outlet	(B)102	TEH-227	Cold Sump	*124
TEH-222	Hot Sump	(B)103	TEH-228	Cold Sump	*125
TEH-225	Cold Sump Outlet	104	TEH-220	Hot Sump	(B)*126
TEH-230	Cold Tank Inlet	105	TEH-221	Hot Sump	(B)*127
TEH-201	Boost Sump Drain - Heater D	106 (Low)	TEH-211	Riser - Storage End - Heater H	128
TEH-202	Cold Pump Outlet - Heater C	107 (Low)	TEH-241	FCV-151, Heater H	(A)129
TEH-265	Cold Sump Outlet	108	TEH-212	Downcomer - Storage - Heater K	130
TEH-229	Cold Sump Inlet	109	TEH-240	FCV-161, Heaters A-Y, K	<u>131</u>
TEH-233	Cold Tank #1, CT-1 thru 7	*110	TEH-213	Hot Tank #1	*134
TEH-234	Cold Tank #2, CT--1 thru 7	*111	TEH-214	Hot Tank #2	*135
TEH-235	Cold Tank #3, CT-1 thru 7	*112	TEH-215	Hot Tank #3	*136
TEH-231	FCV-201	113	TEH-217	Cold/Hot Tank Bypass-Heater AA	(A,B)137
TEH-232	Cold Tank Outlet	114	TEH-223	Propane Heater	(A)138 <sup>472</sup>
TEH-205	Boost Sump - Heater W	115 (SKIP)	TEH-224	Propane Heater	(A)139 <sup>478.0</sup>
TEH-206	Boost Sump - Heater W	116	TEH-236	Cold/Hot Tank Bypass, Heater AA	(A,B)140 <sup>good</sup>
TEH-203	Boost Pump Bypass - Heater E	117	TEH-238	FCV-242	141 <sup>432</sup>
TEH-204	Boost Pump Outlet - Heater B	118 (Low)	TEH-239	Propane Heater Outlet	(A)142
TEH-209	Cold Tank Inlet - Heater F	(B)119	<p>* <u>Record for TSS Step 2, stored salt temp's</u>                      (A) Normally not operating during system operation                      (B) Not required for Propane Heater operation</p>		
TEH-210	Cold Tank Bypass - Heater G	120			
TEH-237	FCV-162, Heater F	(B)121			

Table B TSS Heat Trace Instrumentation

7-11

<u>T/C</u>	<u>DESCRIPTION</u>	<u>ACUREX CHANNEL</u>	
TEH-305, 306	Hot Salt Inlet Lines	200, 201	
TEH-307, 308	Salt Piping Between SH and EV	202, 203	
TEH-309 thru 311	Cold Salt Inlet Lines	204 thru 206	
TEH-312 thru 314	EV Salt Outlet	207 thru 209	
TEH-315 thru 317	Salt Drain Lines	<u>210 thru 212</u>	
TEH-318, 319	SH and EV Outlet Overpressure	**213, 214	
TEH-320, 321	Superheater	215, 216	
TEH-322, 323	Evaporator	<u>217, 218</u>	
6005 thru 6009	Misc. Salt Lines (info.)	230 thru 234	233 (Skip)
6011 thru 6016	Superheater (info.)	##236 thru 241	234 (O.R.)
----	FCV-351 Body, Bonnet	<u>242, /243</u>	
6020 thru 6025	Evaporator (info.)	##245 thru 250	
6026 thru 6029	Hot Salt Inlet (info.)	251 thru 254	
6030, 6031	FCV-341 Body, Bonnet	<u>255, /256</u>	
6032, 6033	FCV-301 Body, Bonnet	257, 258	
6034, 6035	FCV-321 Body, Bonnet	259, 260	
6036, 6037	FCV-381 Body, Bonnet	261, 262	
6038, 6039	FCV-382 Body, Bonnet	263, 264	
6040 thru 6042	Salt Drain Lines (info.)	##265 thru 267	
6043	SH Drain (info.)	<u>**268</u>	
6044 thru 6053	Misc. Lines (info.)	269 thru 278	275 (Skip) 277 (O.R.)

\*\*These will normally be below salt freezing temperature (no problem).

##These may be below 480°F - But they should be above 400°F prior to salt flow.

TABLE C SGS HEAT TRACE INSTRUMENTATION

# TABLE D GROUP ALARM LIST

## GAL GENERAL ALARMS

LT-201	TE-180	TE-383	TE-508	LS-541	LV-28
LT-221	TE-181	387	-509	PS-281	LV-481
LT-281	TE-184	388	-581	PS-485	LV-N91
LT-291	TE-211	TE-481		TS-501	N90-AL
LT-311	TE-231	484		TS-502	
LT-471	TE-281	486			
LT-511	TE-286				

## RAL REGENER OPERATIONAL ALARMS

FT-101	LT-151	TE-101	PT-181
	LT-161	TE-102	PT-182
		TE-161	
		RS TE'S	

## SAL STEAM GENERATOR OPERATIONAL ALARMS

TE-301	TE-384	PT-321	PT-431
TE-331	386	382	432
332	421	383	483
TE-382	483	384	
		386	

## PAL ELECT. POWER OPERATIONAL ALARMS

ET-581	TI-501	TE-505	TI-521	PT-501	PT-531
ST-581	TI-502	TE-506	TI-567	502	581
ZSH-AEP	TE-503	TI-507			583



TABLE E

MSEE REMOTE OPERATED VALVE ALIGNMENT

VALVE	FUNCTION	PRETEST			OPERATION		POST TEST
		BASIC FULL SYSTEM	MODIFICATION TO OPERATE 1. W/O RECVR 2. W/ OR W/O PROPANE HTR	MODIFICATION TO OPERATE 1. RECVR ONLY -OR- 2. PROPANE HTR ONLY	BASIC FULL SYSTEM	MODIFICATION TO OPERATE 1. W/O RECVR -AND- 2. W/PROPANE HTR	
FCV-101	RECVR FLOW CTRL	○ MAN			⊙ CASE SP,SALT SP 1000 °F	○ MAN	○ MAN
FCV-102	RECVR FLOW CTRL	○ MAN			⊙ CASE SP,SALT SP 1000 °F	○ MAN	○ MAN
FCV-151	CST LEVEL CTRL	● MAN	● L MAN	● L MAN (W/ HTR)	⊙ CASE LT-151 SP 87"	● L MAN	○ MAN
FCV-161	HST LEVEL CTRL	● <del>MAN</del>	● L MAN	● L MAN (W/ HTR)	⊙ AUTO SP 20"	● L MAN	○ MAN
FCV-162	HST LEVEL CTRL	● <del>MAN</del>	○ MAN	○ MAN (W/ HTR)	● AUTO SP 20"	○ MAN	○ MAN
FCV-180-189	RECVR DRAIN	○			●		●
FCV-190-198	RECVR PURGE	○			●		●
FCV-501	TURBINE STOP	●			○		●
FCV-511	HOTWELL OVERFLOW	●			⊙ EN,HLC ON	●	●
FCV-512	HOTWELL MAKE-UP	● ENR,LC OFF (LOCAL CNTRL)			⊙ (AUTO CNTRL)	● ENR,LC OFF (LOCAL CNTRL)	● (LOCAL CNTRL)
FCV-521	OIL COOLANT FLOW CTRL	● AUTO SP 120 °F			⊙ AUTO SP 120 °F	●	● MAN
FCV-541	CNST MAKE-UP	● LOCAL CNTRL			LOCAL CNTRL	●	● LOCAL CNTRL
FCV-551	CONDENSATE RECIRC	●			●	●	●
FCV-561	TURBINE TRIP	● ET OFF			● ET OFF	●	● ET OFF
TVM	TURBINE THROTTLE	●			⊙	●	●
		● L	○	⊙			
		↑ LOCKED	↑ OPEN	↑ CONTROLLING			
		↓ CLOSED					

7-12B

**COP #2 CONTROL ROOM POST-TEST CHECKLIST**

Test Date  
9/22/84

This Console operating procedure will be utilized to secure the process controls following all tests. This checklist shall be completed by the Control Room process console operator.

STEP                      DESCRIPTION                      VERIFICATION

**I. HELIOSTAT SUBSYSTEM**

1. Verify system returned to a safe condition; (Heliostats, salt, steam, water) \_\_\_\_\_

**II. RS RECEIVER SUBSYSTEM**

1. Verify the following valve alignment: \_\_\_\_\_

01	FCV-101	Man/Open		
	FCV-102	Man/Open		
	FCV-180 thru 189	Off/Closed	(ZSL's on)	08
	FCV-190 thru 198	Off/Closed	(ZSL's on)	09

- 02 2. Verify the receiver cavity door is fully closed (ZSLDR on). \_\_\_\_\_

3. Verify RS secured from technician - post test checklist completed (ROP #4). \_\_\_\_\_

**III. TSS THERMAL STORAGE SUBSYSTEM**

1. Verify the following valve alignment in MAN:

02	FCV-151 Open	04	FCV-211 Closed/Locked	
	FCV-161 Open	04	FCV-221 Closed	
	FCV-162 Open	04	FCV-231 Closed/Locked	
	FCV-199 Open	05	FCV-241 Closed	
04	FCV-201 Closed	05	FCV-242 Closed	
	CSP.EN Off, BP.EN Off, HSP.EN Off			

2. Record the following salt levels & temp's:

	LT-201 Cold sump	_____ in.	@ _____ °F	(Acurex Chan 124,125)
03	LT-281 Cold tank	_____ in.	@ _____ °F	(Acurex Chan 110-112)
	LT-221 Hot sump	_____ in.	@ _____ °F	(Acurex Chan 126,127)
	LT-291 Hot tank	_____ in.	@ _____ °F	(Acurex Chan 134-136)

3. Verify TSS secured from technician - post test checklist completed (TOP #4). \_\_\_\_\_

**COP #2 CONTROL ROOM POST-TEST CHECKLIST**

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
-------------	--------------------	---------------------

**IV. SGS STEAM GENERATION SUBSYSTEM**

1. Verify the following valve alignment:

—	*FCV-301	Closed	MAN.384 On	
	*FCV-321	Open	FCV.384 On (open)	
13	*FCV-331	10% Open	MAN.38182 On	
	*FCV-341	Closed	FCV.38182 Off (closed)	
—	*FCV-351	Closed		

\*Emcon commands - MAN signals on with SP in Auto to the positions noted.

2. Verify SGS secured from technician - post test checklist completed (SOP #4).

**V. HRFS HEAT REJECTION AND FEEDWATER SUBSYSTEM**

1. Verify the following device alignment:

—	EN.DTC451	--	Off	
	EN.DTC452	--	Off	
	GSTAT	--	Off	
—	FCV-431	Closed	Casc	
18	FCV-432	Open	Auto SP 233 or 240 psi	
	FCV-471	Closed	Auto SP 0%	
—	FY-472	Closed	Auto SP 0%	
	FCV-411	Closed	MAN.411 On/SP.411 Auto 0%	
	FCV-491	Closed	Auto Closed	
—	FCV-501	Closed	Off/ZSL-501 On	
19	Pump EN Signals		Off	
20				

2. Verify HRFS secured from technician - post test checklist completed (HOP #4).

**VI. EPGS ELECTRIC POWER GENERATION SUBSYSTEM**

21 1. Verify TCRMS is off.

2. If used, reset bkr control switch to green flag, remove the RGP Sync switch handle and return it to the MSEE key box. Set Run Volt and Speed controls down.

3. Verify EPGS secured from technician - post test checklist completed (POP #4).

**VII. MCS MASTER CONTROL SUBSYSTEM**

1. Disable general alarms by turning GAL off.

2. Safe the Emcon and Net. 90 control consoles to eliminate any inadvertant control inputs. (Lock-up)

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
1.	EMCON System Shutdown	
	a) Terminate MSSND execution	_____
	b) Execute "SHUT UP" command file	
	1) No device modifications	_____
	c) Spin down disk drives	_____
	d) Turn off power to equipment	_____
2.	Acurex System Shutdown	
	a) Terminate host operation via key switch control	_____
	b) Turn off power to equipment	_____
3.	Data System Shutdown	
	a) Terminate programs	_____
	b) Spin down disc drive	_____
	c) Turn off power to equipment	_____
4.	Net-90	

7.2 RECEIVER OPERATING PROCEDURES

Test Date  
6/7/84

ROP #1 RECEIVER PRETEST CHECKLIST

This Receiver operating procedure will be utilized to verify RS integrity prior to all tests that use the Receiver. This checklist shall be completed by the RS technician.

STEP	DESCRIPTION	VERIFICATION
1.	Turn on the Tower Air Compressor in continuous duty. Verify pneumatic air is available at 80 psig min. Note it may already be on for HRFS or Facility.	_____
2.	Verify air is being supplied to the Cold Surge Tank and backup air supply for the Drain/Purge Valves (separate manifolds) as follows: a. Open valves on supply bottles. b. Verify supply bottles at 300 psig minimum. c. Adjust HPCV-171 to read 200 psig on the Cold Surge Tank regulator. d. Adjust the backup air supply regulator to 65 psig	_____
3.	Verify the EPS and 2 each control panel power supplies are ON with each set to 24 volts.	_____
4.	Verify the receiver uninterruptible power supply (UPS) is ready and operational (battery gage greater than 90V).	_____
5.	Set up remote camera.	_____
6.	Verify/adjust the pneumatic activated valve air set on the Drain and Purge valves (FCV 180 - 198) to 30 psig outlet pressure (should be done with valves open).	_____

CAUTION

Verify valve temp's with control room prior to cycling.

7. Align/verify valve positions as specified - coordinate with EMCON operator; verify pneumatic pressure to the valves (FCVs)

FCV 101	Salt Flow Control	Open/N
FCV 102	Salt Flow Control	Open/N
FCV 180-189	Drain Valves	Open/N
FCV 190-198	Purge Valves	Open/N

8. Using a probe, verify the Hot Surge Tank Vent is free of frozen salt (not blocked). \_\_\_\_\_
9. Check Flux Gage Coolant Pump, and radiator for leaks. Verify level in radiator is within 2" of top. \_\_\_\_\_

ROP #1 RECEIVER PRETEST CHECKLIST

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
10.	Verify coolant flow through Flux Gages.( indication on flowmeter.)	_____
11.	Visually check the Receiver Cavity Door, Cavity Walls, and the door supports for evidence of scorching. Coordinate RS cavity door operation with Emcon operator.	_____
12.	Check for visual evidence of blown fuses, burned relays or burned electrical components in the power junction box and generally through out the receiver subsystem.	_____
13.	Inspect the salt system for evidence of leaks and insulation damage. This is a general inspection for any condition that appears abnormal. If a problem is detected (i.e. salt leak, etc.), a more thorough inspection will be required. <ul style="list-style-type: none"><li>o RS tower piping</li><li>o Surge Tanks (2 ea)</li><li>o Valves (21 ea)</li><li>o Receiver Assembly (Panel)</li></ul>	_____
14.	Advise the control room that the RS pre-test checklist has been completed.	_____

THE RECEIVER SUBSYSTEM IS READY FOR STARTUP

This Receiver operating procedure shall be performed by the Emcon operator. Periodically advise the RS technician of status.

STEP	DESCRIPTION	VERIFICATION
1.	Verify completion of the following checklists: o CS Pretest Activity (Heliostats to Line Bottom) o COP #1 Control Room Pretest Checklist ✓ o ROP #1 RS Pretest Checklist ✓ o TOP #1 TSS Pretest Checklist ✓	<hr/> <div style="text-align: right;">✓ ✓</div>
<u>WARNING</u>		
Only operating personnel are allowed in the salt storage and receiver areas while system is operating. Access is to be controlled by the test conductor. Protective clothing must be worn by personnel working in these areas during operation. All other personnel are to keep clear of these areas.		
2.	Advise the Heliostat operator to Bring the Heliostat Field up to Far Standby.	<hr/> <div style="text-align: right;">✓ ✓</div>
02	3. Open the Receiver Cavity Door (DR.OPN). Verify visually and by micro indications (ZSHDR on).	<hr/> <div style="text-align: right;">✓</div>
26	4. Reset EPS Racks 1 and 3 (turn EPS1.RST and EPS3.RST on then off). Verify Emcon SCRAM disable signal is On.	<hr/> <div style="text-align: right;">✓</div>
5.	Advise the Heliostat operator to Direct Warmup A Heliostat Group at the receiver. (Use CRTF's OP-78-03 for specific steps.)	<hr/>

NOTE

Graphic 990 Receiver panel temperatures (TE-131 thru TE-148) must be greater than 450°F prior to opening FCV 151 (step 19) during manual startup or starting RS.Fill automatic sequence (step 11) during automatic startup.

CAUTION

o Receiver maximum temperature: 1050°F

If any receiver temperatures remain below 450°F, heliostats may need to be added to increase the temperature of that portion of the panel. Conversely, if any temperatures start approaching 1000°F, heliostats will have to be removed to limit the flux to that portion of the panel.

**ROP #2 RECEIVER STARTUP**

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
	6. Advise the salt storage tech. to unlock FCV-211.	✓
04	7. When unlocked, <sup>check</sup> open FCV 211, verify micros. (If Cold Sump level LT-201 is equal to or greater then 50 inches, this step should be delayed until just prior to starting the CSP to avoid leakage and possible sump overflow.)	✓
	8. Enable cold sump level control and fill sump as follows to prime CSP for starting and provide an adequate salt reservoir for fill operations:	
	a. Activate FCV-201 with a SP of 48"	
04	b. Verify sump level is 50" min. (60" max.)	✓
	c. Reset FCV-201 SP to 45"	
	9. Reverify salt path temperatures are acceptable:	
06	• Receiver Panel           TE-131 thru 148	
10	• Receiver Pass Outlet   TE-101 thru 120	
07	• Receiver Header        TE-182 thru 198	
	• Acurex RS               (COP #1 Table A)	
	• Acurex TSS             (COP #1 Table B)	✓
	<u>NOTE</u>	
12	The auto fill sequence starts here. Start-up can be accomplished using the auto start sequence (RS.FILL On) or manually from the Emcon console.	
GR 992	For auto fill verify RS.MAN OFF	MAN <u>AUTO</u> 1.24.10
	10. Activate the FCV 161 Hot Surge Tank Level Control with a set point of 75 inches.	
	11. Activate the FCV 162 Hot Surge Tank Level Control with a set point of 56 inches. In manual fill RS.MAN must be enabled to permit a SP change different than 20".	

NOTE

RS.MAN is available to override FCV-161/162's transfer control.



**ROP #2 RECEIVER STARTUP**

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
12.	Start the Cold Salt Pump (CSP).	_____
13.	Start the Boost Pump (BP).	_____
14.	Enable pump pressure alarm PT180.	_____
15.	When the PT-180 Pump Outlet pressure is greater than 310 psi, incrementally open FCV 151 to 50% in 10% steps.	_____

NOTE

Monitor the Receiver sequential fill.  
 Pipes fill (TE-161), CST level rises (LT-151),  
 Flow starts (FT-101), HST level rises (LT-161).

16.	Close FCV-199 (FCV-199 on) when HST level LT-161 reaches 10" (after 50" CST level). Verify micro ZSL199 on.	_____									
17.	When the LT-161 Hot Surge Tank level approaches 55 inches, Verify FCV-162 is in auto and maintaining 56 inches.	_____									
18.	Close drain valves FCV-180 thru 189 (off). Verify closure.	_____									
19.	Sequentially close the following Purge Valves at 10 sec. intervals (off) to establish serpentine flow. Verify closure.	_____									
	<table style="width: 100%; border: none;"> <tr> <td style="width: 33%;">FCV-190</td> <td style="width: 33%;">FCV-193</td> <td style="width: 33%;">FCV-196</td> </tr> <tr> <td>FCV-191</td> <td>FCV-194</td> <td>FCV-197</td> </tr> <tr> <td>FCV-192</td> <td>FCV-195</td> <td>FCV-198</td> </tr> </table>	FCV-190	FCV-193	FCV-196	FCV-191	FCV-194	FCV-197	FCV-192	FCV-195	FCV-198	_____
FCV-190	FCV-193	FCV-196									
FCV-191	FCV-194	FCV-197									
FCV-192	FCV-195	FCV-198									
20.	Reset the FCV-162 Hot Surge Tank Level set point to 20".	_____									
21.	Reset the FCV-201 Cold Sump Level set point to 23".	_____									
22.	Establish Receiver manual salt flow control:	_____									
	<ul style="list-style-type: none"> <li>a. Take RCA off scan.</li> <li>b. Activate FCV-101/102 CASC control (from FD-101)</li> <li>c. Verify FD-101 is in auto and adjust SP to 30 Klb/hr. Verify flow below 35Klb/hr. (level &amp; flow)</li> </ul>	_____									
23.	Activate the FCV 151 casc. Cold Surge Tank Level Control, then update auto. LT 151 level control with a set point of 87 inches.	_____									

*Handwritten notes:*  
 Done  
 8/1/80  
 9:44

ROP #2 RECEIVER STARTUP

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
24.	Activate the Receiver Temperature Control by putting RCA on scan. (Temperature set point SP.SALT will automatically come up at 750°F. This will maintain a low salt flow rate through the receiver with only the warm-up Heliostats on target. FD-101 is automatically controlled from RCA.)	_____
25.	Enable Receiver operational alarms by turning RAL on.	_____
26.	Verify/Turn off RS.FILL if it was used. (Turns itself off when auto fill is complete).	_____

THIS IS THE END OF THE AUTOMATIC SEQUENCE. THE R.S. IS NOW OPERATIONAL (WARM STANDBY) AWAITING START OF SOLAR CHARGING ACTIVITY.

NOTE

Receiver minimum flow rate is auto limited to 30 klb/hr.

- 01
- 02
27. To maintain the Warm Standby condition (cold flow) for an extended period of time:
- a. Deactivate the Receiver Control Algorithm by taking RCA off scan.
  - b. Reset the FD-101 Salt Flow Control set point to 30 klb/hr or to desired flow rate.
  - c. Remove the warmup heliostats from the receiver.
  - d. Close the receiver cavity door and verify.

Extended Warm Stdbby

28. Prepare for solar charging by verifying:
- a. Receiver cavity door is open.
  - b. Warm-up Heliostats are on Receiver.
  - c. RCA Receiver temperature control algorithm is activated - scan on.
  - d. SP.SALT setpoint is initially set to 750°F.
29. Conduct solar charging by advising the Heliostat operator to direct incremental Heliostat groups onto the Receiver per operating condition requirements. (Eighth of the field increments are standard). Adjust/Step-up SP.SALT accordingly (1050°F max.) and be alert for cloud and process transients.

Solar Charging

ROP #2 RECEIVER STARTUP

---

STEP      DESCRIPTION      VERIFICATION

30. When individual heat trace thermocouple temperatures exceed 750°F, verify the following Acurex channels indicate CLSD (circuit automatically turned off):

<u>Channel</u>	<u>Area</u>
*063	Upper and Lower Headers
*064	Secondary Headers
065	Header East End
066	Receiver outlet
069	Hot Surge Tank
451	Downcomer and Hot Tank inlet

\*The switch on the Module Control Room local control panel must be in REMOTE to allow Acurex automatic control to turn these off.

---

THE RS IS NOW ON LINE IN SOLAR CHARGING CONFIGURATION.

NOTE

During RS Solar operations, intermittantly monitor these parameters:

- Solar Insolation      - (CF) Control Room Weather Monitor Panel  
above 600 W/M<sup>2</sup>      - (TSS) Emcon 'SUN'
- Cavity Door Temperatures      - Acurex channels 45,46, & 47

This Receiver operating procedure shall be performed by the Emcon operator. Periodically advise the RS and TSS technicians of status.

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
-------------	--------------------	---------------------

- |          |  |       |
|----------|--|-------|
|          | 1. Defocus the heliostats.   | _____ |
| 01       | 2. Verify/Adjust SP.SALT to 750°F, FCV-201 SP to 23".  | _____ |
| 02       | 3. When FT-101 drops to less than 30 Klb/hr, close the receiver cavity door and verify micros.   | _____ |
| 01<br>02 | 4. Deactivate the Receiver Control Algorithm (by taking RCA off scan) and set the FD-101 set point to 60 Klb/hr. Wait 3 minutes minimum and continue when TE-161 is less than 700°F. Verify FCV-162 is open and maintaining level in HST.                                      | _____ |
| 02       | 5. Deactivate FCV-161 control and close.   | _____ |
|          | 6. Check Acurex Ch 000-018, if below 480°F advise RS technician to turn heat trace to local 'ON' until acceptable. When individual heat trace thermocouple temperatures drop below 700°F, verify the following Acurex channels indicate OPEN (circuit automatically turns on): |       |

- \*063 Upper and Lower Headers
- \*064 Secondary Headers
- 065 Header East End
- 066 Receiver Outlet
- 069 Hot Surge Tank Inlet

\*The switch on the Module Control Room local control panel must be in REMOTE to allow Acurex automatic control to turn these on.

THE RS IS NOW IN WARM STANDBY. SALT FLOW MAY BE VARIED TO PROVIDE DESIRED TEMPERATURE/FLOW THROUGH THE RECEIVER.

NOTE

12  
GR 992

The RS.DRAIN Auto Drain Sequence starts here. Shutdown can be accomplished using the Auto sequence or manually from the EMCON console. Note Auto seq. steps are not performed in the exact order that follows.

MAN AUTO

- |    |   |       |
|----|---|-------|
| 01 | 7. Set FD-101 setpoint to 30 Klb/hr. Wait for flowmeter FT-101 to stabilize at 30 Klb/hr + 3 Klb/hr, then cont. | _____ |
|----|---|-------|

ROP #3 RECEIVER SHUTDOWN

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
8.	Open the following purge and drain valves (on). Verify open micros ZSH 180 thru 198 on.  FCV-180-189      FCV-194 FCV-190            FCV-195 FCV-191            FCV-196 FCV-192            FCV-197 FCV-193            FCV-198	<hr/> <hr/> <hr/> <hr/> <hr/>
9.	Disable RAL by turning it off.	<hr/> <hr/>
10.	Deactivate FCV-101 & 102 auto control. Close FCV-101 & 102. Verify closed micros. Wait 30 seconds before continuing. (Note Auto sequence leaves these in Auto).	<hr/> <hr/>
11.	Change LT-151 set point to zero. Verify FCV-151 closed.	<hr/> <hr/>
12.	Deactivate FCV-151 auto control.	<hr/> <hr/>
13.	Verify FCV-162 closed (in Auto). <u>The RS is now bottled up and stagnant.</u>	<hr/> <hr/>

CAUTION

The next three steps initiate salt drain back to the Cold Salt Tank and must be accomplished following the sequence described. An early response could cause an overflow of the hot surge tank. A late response could cause damage to the receiver piping.

WARNING

Only operating personnel are allowed in the salt storage and receiver areas while system is draining. Access is to be controlled by the test conductor. All other personnel are to keep clear of these areas.

14.	To drain HST and downcomer, Deactivate FCV-162 auto control, ramp open FCV-162 to 100% in 20% increments 5 seconds apart, verify open micro, continue when LT-161 reaches 0" or stops decreasing.	<hr/> <hr/>
15.	Open FCV-199 to drain CST and riser, observe LT-151 at 15 inches, then wait 5 seconds.	<hr/> <hr/>
16.	Open FCV-101 & 102 5% to drain Receiver residual salt, Record time. (Ref. step 24).	<hr/> <hr/> <hr/>

TIME

ROP #3 RECEIVER SHUTDOWN

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
-------------	--------------------	---------------------

17. Deleted.

NOTE

If SGS is operating (ZSH.HSP ON), go to Step 24.

18. Disable PT-180 pump pressure alarm.

19. Turn off boost pump.

20. Turn off cold salt pump.

21. Change FCV-201 set point to zero, wait 15 seconds.

22. Put FCV-201 into manual.

23. Close FCV-211 and manually lock it closed.

24. Open FCV-101 & 102 100%, approximately 2 minutes after completing Step 16.

TIME

25. Verify/Turn off RS.DRAIN. (Turns itself off when Auto Drain is complete)

THIS IS THE END OF THE AUTOMATIC DRAIN SEQUENCE.  
THE RS IS AWAITING RESIDUAL SALT DRAINBACK.

02 26. If the SGS is not in operation, 15 minutes after completing Step 24, open:

FCV-151  
FCV-161 (only if hot tank has salt level)

01 27. If the SGS is not in operation, 20 minutes after completing Step 24, close the following valves:

FCV-180-189	FCV-194
FCV-190	FCV-195
FCV-191	FCV-196
FCV-192	FCV-197
FCV-193	FCV-198

28. Advise RS tech to turn trace heat back to remote, if turned on locally in step 6.

29. Advise the RS and TSS technicians to complete their post test checklists (ROP #4 & TOP #4). if no further RS or TSS operation planned.

THE RS IS NOW SHUTDOWN AND DRAINED.

ROP #4 RECEIVER POST TEST CHECKLIST

Test Date  
6/7/84

This Receiver operating procedure will be utilized to verify RS integrity following all tests that use the Receiver. This checklist shall be completed by the RS technician.

STEP	DESCRIPTION	VERIFICATION								
1.	Inspect the salt system for evidence of leaks and insulation damage. This is a general inspection for any condition that appears abnormal. If a problem is detected (i.e. salt leak, etc.), a more thorough inspection will be required.									
	<ul style="list-style-type: none"> <li>o RS tower piping</li> <li>o Surge Tanks (2 ea)</li> <li>o Valves (21 ea)</li> </ul>									
2.	Verify the following valve alignment. Coordinate with Emcon operator.									
	<table border="0"> <tr> <td>FCV-101</td> <td>OPEN</td> </tr> <tr> <td>FCV-102</td> <td>OPEN</td> </tr> <tr> <td>FCV-180 thru 189</td> <td>CLOSED</td> </tr> <tr> <td>FCV-190 thru 198</td> <td>CLOSED</td> </tr> </table>	FCV-101	OPEN	FCV-102	OPEN	FCV-180 thru 189	CLOSED	FCV-190 thru 198	CLOSED	
FCV-101	OPEN									
FCV-102	OPEN									
FCV-180 thru 189	CLOSED									
FCV-190 thru 198	CLOSED									
3.	Open the Receiver Cavity Door and inspect Receiver Assembly for evidence of leaks (white on black surface) and general condition. Close the door when the inspection is complete. Coordinate with Control Room.									
4.	Secure remote camera.									
5.	Close the Cold Surge Tank and Receiver pneumatic backup supply bottles handvalves. Record values, CST = _____ p/Air = _____.									
6.	Turn off the Tower Air Compressor only after obtaining clearance from Control Room. (It may still be in use for HRFS or Facility).									
7.	Note any items or abnormalities encountered during test activities.									
8.	Advise the control room that RS post-test checklist has been completed and the RS is secure.									

## 7.3 THERMAL STORAGE OPERATING PROCEDURES

Test Date

## TOP #1 TSS PRETEST CHECKLIST

6/20/84

This Thermal Storage operating procedure will be utilized to verify TSS integrity prior to all tests that use Molten Salt. It shall be performed by the TSS tech.

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
1.	Inspect the salt system for evidence of leaks and insulation damage. This is a general inspection for any condition that appears abnormal. If a problem is detected, a more thorough inspection will be required. <ul style="list-style-type: none"> <li>o TSS salt piping</li> <li>o Hot, Cold, and Booster Pumps and Sumps</li> <li>o Vents</li> <li>o Valves</li> </ul>	_____
2.	Check for visual evidence of blown fuses, burned relays or burned electrical components in the power junction boxes and generally throughout the TSS.	_____
3.	Verify that the EPS Power Supply (lower part of rack) is set to 24 VDC and is ON.	_____
4.	Start/verify the air compressors are ON with a 80 psig supply pressure. Drain water from old compress tank.	_____
5.	Inspect the fan and louvers in the pump house for proper operation. Verify that the fan thermostat is set to 70°F.	_____
6.	Open the hand valve HV-284 at the old air compressor	_____
7.	Verify coolant flow through the HSP and BP bearings (piping will be cold with indication on the flow meter).	_____
8.	Verify the HSP, CSP and BP circuit breakers are off and the shafts of all three pumps are free. (Bump BP to verify freedom with C.B. On in local).	_____
9.	Turn on the HSP, CSP and BP circuit breakers and place the controls for the pumps in Auto. and verify air flow through the Cold Salt Pump bearings.	_____
10.	Using a probe, verify the C.S., C.T., H.S., H.T., and Booster Pump Sump vents are free of frozen salt. During routine operation, only intermittent verification is required. Particularly verify prior to restart after a shutdown or if pluggage is suspected from high salt levels (CS 60", HS 45").	_____



TOP #1 TSS PRETEST CHECKLIST

---

STEP      DESCRIPTION      VERIFICATION

11. Turn ON the TSS/SGS backup pneumatic air supply as follows:

- a) Verify supply bottles are at 300 psig minimum
- b) Open the valves on the supply bottles and main isolation valve
- c) Adjust the regulator to 50 psig

12. Check coolant pumps and radiators for leaks and proper operation. Verify that HV-290, 291, 292, and 293 are open. At the beginning of each month, check the level in the radiators and fill if necessary.

13. Align/verify the valve positions listed below. Coordinate with Emcon operator.

<u>Valve</u>	<u>Description</u>	<u>Position</u>	<u>Air Press.</u>
FCV-151	Cold Surge Level	Closed/N	
FCV-161	Hot Tank Inlet	Closed/N	
FCV-162	Cold Tank Inlet	Closed/N	
FCV-199	Bypass	Open/N	30 psi
FCV-201	Cold Sump Level	Closed/N	
FCV-211	Cold Sump Isolation	Closed/Locked	40 psi
FCV-221	Hot Sump Level	Closed/N	
FCV-231	Hot Sump Isolation	Closed/Locked	40 psi
FCV-241	Propane Heater Flow	Closed/Locked	
FCV-242	Propane Heater Isolation	Closed/Locked	30 psi
FCV-301	Bypass Salt Flow Control	Closed/N	
FCV-341	Cold Salt Isolation	Closed/N	
FCV-351	Hot Salt Isolation	Closed/N	

14. For operation with Propane Heater instead of Receiver, OR for SGS alone, Modify the valve alignment of step 13 as follows:

FCV-151	Locked
FCV-161	Locked
FCV-162	Open/N
FCV-242	Neutral

15. For operation without SGS, Modify the valve alignment of step 13 as follows:

FCV-301	Locked
FCV-341	Locked

TOP #1 TSS PRETEST CHECKLIST

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
16.	Align/Verify the hand valve positions listed below: HV-280 HS/CS Tie Closed HV-281 HT/CT Tie Closed	_____
17.	Determine if the OLIN Salt Test Loop is to be used. If it is, align these HV's accordingly (with SGS only): HV-282 Salt Inlet Open HV-283 Salt Outlet Open	_____
18.	Set up the Eppley sun meter insolation instrument. It is located on a post south of the TSS. (Emcon 'SUN'). a) Rotate platform of tracker (by hand) to acquire sun. Fine adjust using azimuth and elev. screw adjust. (Sun dot should be in center of target on rear of instr.) b) Open door of timer box located on post. Rotate timer (turn on) to appropriate run time. (Adjust to approx. one half hour past shut-down). Close timer door c) Verify operation. Listen for tracker motor running. Recheck sun target on Eppley, readjust using thumb screws. Tighten lock screws.	_____
19.	Advise the Control Room that the TSS Pretest checklist has been completed.	_____

NOTE

Complete the SGS pretest checklist (SOP #1) and/or  
Local Propane Heater startup (TOP #2A) as required.

9/28  
Test Date  
8/02/84

TOP #2 PROPANE HEATER PROCESS START-UP

The Propane Heater is used to charge hot salt when weather conditions do not allow adequate solar charging or when the Receiver or Collector subsystems are not on line.

This Thermal Storage operating procedure shall be performed by the Emcon operator. Periodically advise the TSS technician of status.

Turn on propane inlet and outlet lines trace heater circuits (TEH 223, TEH 224, and TEH 239 for temperature readings) a minimum of 10 hours prior to intended usage of the Propane Heater.

ch 138, 139, 142

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
1.	Verify completion of the following checklists: <ul style="list-style-type: none"><li>◦ COP #1 Control Room pretest checklist ✓</li><li>◦ TOP #1 TSS pretest checklist</li></ul>	✓
2.	Instruct/Confirm TOP #2A Local Propane Heater Start-up.	✓
3.	Record the time upon notification from the TSS technician that the Propane Heater is on Main Flame with 700°F stack outlet temperature. (Ref. steps 10 and 12).	12:03 TIME
05 4.	Verify Cold Tank level LT-281 is greater than 30 inches. If the SGS is operating (on-line) continue at step 11.	
5.	Verify Cold Sump Level LT-201 is less than 60 inches.	
6.	Place FCV-211 in neutral and fully open; verify micros.	✓
7.	Verify/increase the Cold Sump Level to 50 inches.	
8.	Activate the FCV-201 Cold Sump Level Control with a set point of 23 inches.	
9.	Verify LT-201 alarm is activated.	✓
04 10.	14 minutes after MAIN FLAME (step 3) start Cold Pump.	✓✓
11.	Verify Cold Pump outlet pressure PT-180 increases to greater than 170 psi.	✓

NOTE

The Hot Tank must be precharged to 750°F prior to introduction of any high temp. salt. During precharge, leave FCV-221/231 open until the Hot Sump level increases (40" max.), then quickly close FCV-221/231.

TOP #2 PROPANE HEATER PROCESS START-UP

---

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
05 12.	Initiate salt flow through the Propane Heater 15 minutes after completing step 3; Unlock and open FCV-241 to to 50% open.	<hr/>
13.	Open FCV-242. Record Time.	<hr/> 12:55 Time
	<p style="text-align: center;"><u>NOTE</u></p> <p>It will take approximately 10 minutes for the salt to flow through the Propane Heater. Monitor Acurex channel 142 and LT-291 for verifying flow through the heater.</p>	
14.	Advise the TSS technician to turn off the trace heater L6-1 and inlet to Hot Tank if TEH-239 salt temperature will be exceeding 750°F. Verify. <span style="margin-left: 20px;">on 142</span>	<hr/>
15.	Adjust the Propane Heater for a 1050°F (or desired temperature) salt outlet temperature by accomplishing the following after salt flow into hot tank verified (LT-291 10 minutes later):	
	a. Advise the TSS technician to set the Burner Temperature control to 1100-1200°F stack temperature.	<hr/>
	b. Use TEH-239 (Acurex channel 142) as the actual salt salt outlet temperature indication (1040°F max.). Actual temperature approximately 50°F higher than channel 142 read-out at high (1000 °F) temperatures; approximately 20°F higher at low (700°F) temperatures.	<hr/>
	c. Adjust FCV 241 to TBD% (approximately 40 to 55% for 750-900 F salt and 35-40% for 900-1050 salt). If 1050 salt is desired place stack tempature at 1250 and start with FCV 241 at 50% and adjust accordingly.	<hr/>
	d. Monitor Acurex channels 134/136 as hot tank salt temperature and EMCON TE-291.	

THE PROPANE HEATER IS NOW ON-LINE AND CHARGING SALT

This Thermal Storage operating procedure will be utilized to locally operate the Propane Heater in conjunction with Emcon (Propane Heater) process operation. This procedure shall be performed by the TSS technician.

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
1.	Place switch on local console to off position and temperature control to 200°F.	_____
2.	Check level of the Propane Tank and verify sufficient propane for present test - 15% or 900 gallons minimum.	_____
3.	Check/ignite pilot lights of propane evaporators:	
	A. If vaporizers are not lit, then remove small square cover on south side. Turn knob to pilot.	_____
	B. Open center cover (west side) to get to pilot. Pilot is located between metal cylinders at the bottom.	_____
	C. While holding knob on south side in full C.C.W. position, light pilot.	_____
	D. Hold in this position for 30 to 60 seconds, then turn to on position. Replace covers slowly or flame may go out.	_____
4.	Open all three evaporator outlet hand valves (top east side of evaporators) fully. Pressure gauge at Heater inlet should read 55 to 60 psi.	_____
5.	Check pressure gauge bottom north side of heater. The reading should be about 8 oz.	_____
6.	Place Burner switch on local console to preheat.	_____
7.	Turn on power switch - red power and timer light should come on.	_____
8.	Timer light will remain on for about 2 min. as system is purged prior to introduction of pilot flame gas. Timer light will then go off and about 20 sec. later both timer and pilot light will come on to ignite the pilot flame. If IR scanner does not detect a pilot flame within 6 sec., the start sequence will be stopped and the timer will reset and start over. When the pilot flame is achieved, the PILOT LIGHT will come on.	_____

## TOP #2A LOCAL PROPANE HEATER START-UP

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
	<p style="text-align: center;"><u>WARNING</u></p> <p style="text-align: center;">If pilot flame does not light after two tries, close valve on vaporizer and troubleshoot system.</p>	
9.	After pilot is lit for about 1 minute, switch to main flame, set temperature control to 250°F and allow to soak for three minutes minimum.	_____
10.	Slowly advance temperature control to 700°F - do this slowly to avoid screeching of heater. Main flame light should stay lit.	_____
11.	Notify Control Room that the Propane Heater is on Main Flame with a 700°F stack outlet temperature (awaiting 15 min. heat soak prior to process operation).	_____

## TROUBLE SHOOTING GUIDE

Signs of trouble are:

1. Low or very high reading at pressure gauge.
2. Stack temperature varies or stays low.
3. Unit will not start, no pilot.

All the above can be caused by the vaporizers not being lit. Any vaporizer that is out can cause these troubles.

If the heater is running and frost can be noted on the fuel lines, DO NOT TURN HEATER OFF. Relight the vaporizer(s) that are out and continue to run at reduced temperature until the frost is gone.

If you cannot get the vaporizer to light, turn off the hand valve and let the heater run until frost has left the lines. Heater will run on one vaporizer at reduced output. Try to get at least one lit to help remove the liquid propane from the lines.

If the heater will not light, check to see if the ignition wire on bottom of the heater is on the plug.

This Thermal Storage operating procedure shall be completed by the Emcon operator. Periodically advise the TSS technician of status.

STEP      DESCRIPTION      VERIFICATION

NOTE

When shutting down the Propane Heater in conjunction with the SGS (both in operation), perform SOP #5 - not this procedure.

- |    |  |                        |
|----|--|------------------------|
| 05 | 1. Advise the TSS technician to adjust the burner temperature Control to 600°F stack temperature when the Hot Tank level LT-291 is within 12 inches of the desired level (or within 7 inches of desired level in the Cold Tank). | ✓<br>_____             |
|    | 2. Open FCV-241 to 60%.  | ✓<br>_____             |
|    | 3. When 2 inches from desired level, or when channel 142 reads 800°F, deactivate FCV-201 Cold Sump Level Control.  | ✓<br>_____             |
|    | 4. Close FCV-201 and FCV-211 (manually lock closed).   | ✓<br>_____             |
| 04 | 5. Turn off the Cold Pump when it cavitates. (PT-180 drops below 165 psig, LT-201 approx. 11.5"). Record Time. (Ref. steps 7 and 8).   | 13:45<br>TIME<br>_____ |
| 05 | 6. Open FCV-241 to 100% open.  | _____<br>_____         |
| 02 | 7. Wait 2 minutes to allow salt drainage, then unlock and open FCV-151 and FCV 161.  | ✓<br>_____             |

NOTE

LT-201 will increase to approximately 58 inches during propane heater draining.

- |     |  |       |
|-----|--|-------|
| 8.  | Advise the TSS technician to shutdown the Propane Heater 30 minutes after Cold Pump shutoff (step 5) with TOP #3A. | _____ |
| 05  | 9. Close FCV-241, FCV-242.   | _____ |
| 10. | Advise the TSS technician of the following days operating requirements for heat trace actuation.                   | _____ |
| 11. | Verify Propane Heater shutdown from TSS technician.  | _____ |
| 12. | Advise the TSS tech to complete TOP #4 as required.  | _____ |

This Thermal Storage operating procedure will be utilized to locally shut down the Propane Heater after Emcon (Propane Heater) process operation. This procedure shall be performed by the TSS technician.

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
1.	Turn stack temperature control to 600°F when directed to do so by Emcon operator.	_____
2.	After cold salt pump has been turned off, allow a minimum of 30 minutes to drain.	_____
<u>NOTE</u>		
If shutdown includes SGS, the Cold Pump may be restarted to deplete the cold sump. Allow full 30 minutes drain time.		
3.	Turn main flame/preheat switch to preheat.	_____
4.	Turn temperature to 200°F.	_____
5.	Turn power off.	_____
6.	Close the 3 evaporator outlet hand valves to avoid the collection of liquid propane in the line.	_____
7.	Adjust the Propane Heater heat tracing as follows:	
	a. For Propane Heater use the following day, Turn on the Propane Heater outlet line LG-1 and Hot Tank inlet heat trace.	_____
	b. If Propane Heater is not to be used the following day, turn off the Propane Heater inlet line heat trace (TEH-223, 224).	_____
8.	Advise the Control Room that the Propane Heater is shutdown.	_____



This Thermal Storage Operating procedure will be utilized to verify TSS integrity following all tests that use the TSS. This checklist shall be completed by the TSS technician.

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
1.	Complete the SGS post test checklist SOP #4 (first) if no further SGS operation planned.	_____
2.	Inspect the salt system for evidence of leaks and insulation damage. This is a general inspection for any condition that appears abnormal. If a problem is detected, a more thorough inspection will be required. Particularly inspect: <ul style="list-style-type: none"> <li>◦ TSS salt piping</li> <li>◦ Hot, Cold, and Booster Pumps and Sumps</li> <li>◦ Vents</li> <li>◦ Valves</li> </ul>	_____
3.	Check for visible evidence of blown fuses, burned relays, or burned electrical components in the power junction boxes and generally throughout the TSS.	_____
4.	Close and Lock these valves, Verify. FCV-211 Close/Lock FCV-231 Close/Lock	_____
5.	If the Olin test loop was used, close HV-282 and HV-283.	_____
6.	Turn off the CSP, BP, and HSP local starter circuit breakers.	_____
7.	Turn off the CSP bearing cooling air HV-284.	_____
8.	Secure the TSS/SGS back-up pneumatic air by closing the supply bottles HV's.	_____
9.	Leave both Air Compressors On.	_____
10.	Leave TSS coolant pump and radiator On.	_____
11.	Advise the Control Room that the TSS post test checklist is complete and the TSS is secure.	_____

A. HOT TANK TO COLD TANK

I. Gravity Transfer (700 F maximum)

1. Verify completion of the following checklists.  
Particularly verify TSS heat trace temp's and valve align.

- ° COP #1 Control Room pretest checklist
- ° TOP #1 TSS pretest checklist

2. Verify FCV-211 and 231 manually closed and locked.

3. Open HV-281.

4. Open FCV-201 and 221.

(Salt flow rate starts to lessen when LT-291 passes 50".  
Gravity transfer can take the Hot Tank down to approx. 30".)

II. C.S. Pumped Transfer to C.T.

1. Verify RS heat trace temps are OK ( COP #1 Table A ).

2. Start off with Gravity Transfer to ensure proper flow

3. Close FCV-101/102. (For safety - not really required)

4. Open FCV-162 and FCV-199 (verify micro's).

5. Unlock and place FCV 211-in neutral.

6. Ensure LT-201 is greater than 50" (Open/close FCV-211).

7. Start the CSP and BP verify PT-180 increases to over 300 psi.

8. Close FCV-201.

9. Open FCV-211.

10. Incrementally open FCV-151 to approximately 40%.

NOTE

Maintain Cold Sump level at 25" by varying FCV-151 setting.  
(Setting will need to decrease as LT-291 decreases.)

III. Shutdown

11. When reaching desired LT-291 level, perform the next steps expeditiously:

- a. Close FCV-151
- b. Turn off the CSP and BP
- c. Close FCV-221 and FCV-201
- d. Close FCV-211 (and manually lock it).
- e. Close HV-281.

12. After 2 minutes, Open FCV-151, 101, 102, (and FCV-161 if elbow is above 480°F) to drain back residual salt.

13. After 5 minutes, close FCV-151, 161, and 162.

B. HOT SUMP TO COLD TANKI. C.S. Pumped Transfer to C.T.

1. Valve Configuration per COP #1 Part VI TSS. \_\_\_\_\_
2. Verify transfer line and HV-280 are greater than 450°F by local T/C check. \_\_\_\_\_
3. Close FCV 101/102 (for safety not really required.) \_\_\_\_\_
4. Verify FCV-221 and 231 manual closed and lock FCV-231. \_\_\_\_\_
5. Open FCV-162 and FCV-199 (verify micros). \_\_\_\_\_
6. Place FCV-201 in Automatic Control with a set point of 50 inches. \_\_\_\_\_
7. Unlock and place FCV-211 in neutral. \_\_\_\_\_
8. Open FCV-211. \_\_\_\_\_
9. Ensure LT-201 is approximately 50 inches and change FCV-201 set point to 25 inches. \_\_\_\_\_
10. Start the CSP and BP and verify PT-180 increases to over 300 psi. \_\_\_\_\_
11. In 10% increments open FCV-151 to approximately 40%. \_\_\_\_\_

## NOTE

Circulation of salt must stabilize at a sump level (LT-201) of approximately 25 inches. Monitor LT-151 and LT-161 levels.

II. H.S. Pumped Transfer to C.S.

12. Open HV-280. \_\_\_\_\_
13. Turn on Hot Salt Pump. \_\_\_\_\_

III. Shutdown

14. When reaching desired LT-221 level:
  - a) Turn off Hot Salt Pump
  - b) Close HV-280\_\_\_\_\_
15. When LT-201 stabilizes at approximately 25 inches:
  - a) Close FCV-151
  - b) Turn off BP and CSP
  - c) Close FCV-211 (and manually lock it)
  - d) Deactivate and manually close FCV-201\_\_\_\_\_
16. After 2 min., open FCV-151, 101, 102 (and FCV-161 if elbow is above 480°F) to drain back residual salt. \_\_\_\_\_
17. After 5 min., close FCV-151, 161 and 162. \_\_\_\_\_

7.4 STEAM GENERATOR OPERATING PROCEDURES

Test Date  
6/25/84

SOP #1 SGS PRETEST CHECKLIST

This Steam Generation operating procedure will be utilized to verify SGS integrity prior to all tests that use the SGS. This checklist shall be completed by the SGS technician. This checklist presumes SGS is in Diurnal Shutdown.

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>																		
1.	Verify completion of TOP #1 TSS pretest checklist.	_____																		
2.	Inspect the salt system for evidence of leaks or damage. This is a general inspection for any condition that appears abnormal. If a problem is detected, a more thorough inspection will be required. <ul style="list-style-type: none"> <li>◦ All SGS salt piping</li> <li>◦ Valves</li> <li>◦ Superheater and Evaporator</li> </ul>	_____																		
3.	Inspect the water/steam system similarly: <table style="margin-left: 20px; border: none;"> <tr> <td>◦ SGS piping</td> <td>◦ Superheater</td> </tr> <tr> <td>◦ Valves, traps</td> <td>◦ Evaporator</td> </tr> <tr> <td>◦ BWCP</td> <td>◦ Steam Drum</td> </tr> <tr> <td>◦ Flange Connestions</td> <td>◦ Attemperator</td> </tr> <tr> <td>◦ Drain Plugs</td> <td>◦ Drain and Blowdown Tank</td> </tr> </table>	◦ SGS piping	◦ Superheater	◦ Valves, traps	◦ Evaporator	◦ BWCP	◦ Steam Drum	◦ Flange Connestions	◦ Attemperator	◦ Drain Plugs	◦ Drain and Blowdown Tank	_____								
◦ SGS piping	◦ Superheater																			
◦ Valves, traps	◦ Evaporator																			
◦ BWCP	◦ Steam Drum																			
◦ Flange Connestions	◦ Attemperator																			
◦ Drain Plugs	◦ Drain and Blowdown Tank																			
4.	Check for visual evidence of blown fuses, burned relays or burned electrical components in the power junction box and generally throughout the SGS.	_____																		
5.	Intermittantly verify these amperages with a clamp-on Ammeter. Caution - 480V. <table style="margin-left: 20px; border: none;"> <tr> <td>A. Circ. Heater</td> <td>EH-1</td> <td>28A</td> </tr> <tr> <td></td> <td>EH-2</td> <td>28A</td> </tr> <tr> <td></td> <td>EH-3</td> <td>16A</td> </tr> <tr> <td></td> <td>EH-4</td> <td>16A</td> </tr> <tr> <td></td> <td>EH-5</td> <td>16A</td> </tr> <tr> <td>B. BWCP</td> <td>Each Phase</td> <td>7.8A</td> </tr> </table>	A. Circ. Heater	EH-1	28A		EH-2	28A		EH-3	16A		EH-4	16A		EH-5	16A	B. BWCP	Each Phase	7.8A	_____
A. Circ. Heater	EH-1	28A																		
	EH-2	28A																		
	EH-3	16A																		
	EH-4	16A																		
	EH-5	16A																		
B. BWCP	Each Phase	7.8A																		
6.	If freezing ambient temperatures have been experienced, Verify operability - Unthaw the following: <ul style="list-style-type: none"> <li>A. Instrument Transmitters - particularly LT-311 - open xmtr piping drain valves for 10-15 sec. intervals - work with system temp. increases.</li> <li>B. Steam Traps - T-481/HV-491 and T-482/HV-487 - open 1/4 turn and listen for flow. Externally heat as necessary. Open fully after 10 minutes.</li> </ul>	_____																		

SOP #1 SGS PRETEST CHECKLIST

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
7.	SGS water chemistry sampling -	
	A. Obtain a drum water sample by opening HV-386, flushing the sample station lines for 10 minutes, then filling a one liter sample bottle.	_____
	B. Analyze and Evaluate the sample per HOP #6.	_____
	C. Conduct a Millipore filter sampling and analysis for suspended iron. Results of this must be added to the HOP #6 dissolved iron determination for comparison to the 500 ppb limit.	_____
	D. Close HV-386 upon completion of sampling and Open the vent HV-384 located adjacent to HV-386 to drain the sample line, particularly to protect against freezing. Close the vent HV-384 after totally draining the line.	_____

8. SGS Phosphate injection -

- A. As determined by water chemistry sampling of step 7, phosphates can be added to the SGS with the chemical feed station on the SGS skid (HV-387/388). Injection should be started as early as possible.
- B. The phosphate injection mixture consists of 175 grams of granular Trisodium Phosphate and 50 grams of powdery Disodium Phosphate mixed with 2 and 1/2 gallons of demineralized water

9. Align/Verify the valve positions listed below. Coordinate with Emcon operator.

<u>Valve</u>	<u>Description</u>	<u>Position</u>
FCV-321	Main Salt Flow	Open
FCV-331	Steam Attemperator	10% Open
FCV-381	Evap. Salt Drain	Open
FCV-382	Superhtr. Salt Drain	Open
FCV-383	Circ. Htr. Bypass	Closed
FCV-384	Circ. Htr. Supply	Open
FCV-491	Steam Delivery	Closed

SOP #1 SGS PRETEST CHECKLIST

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
-------------	--------------------	---------------------

10. Align/Verify the following valve positions.

<u>Valve</u>	<u>Description</u>	<u>Position</u>
HV-370	Bridge Feedwater Drain	Closed
HV-371	Circ. Heater Drain	Closed
HV-372	BWCP Volute Drain	Closed
HV-373	BWCP Bearing Cavity	Closed
HV-375	SGS Air Supply	Open
HV-381	Drain	Closed
HV-382	Blowdown Control	Closed
HV-383	Blowdown Isolation	Closed
HV-384	Pump Isolation	Open/Locked
HV-385	Steam Drum Vent	Closed
HV-386	Sample Line Isolation	Closed
HV-387	Chemical Feed Metering	As needed
HV-388	Chemical Feed Isol.	As needed
HV-389	Chemical Feed Drain	Closed
HV-390	Drum N <sub>2</sub> Inlet	Closed
HV-481	Steam Delivery Isol.	Closed
HV-485	Steam Delivery Drain	Closed
HV-486	Steam Delivery Drain	Closed
HV-487	Trap Isolation	Open
HV-488	Feedwater Supply Isol.	Closed
HV-491	Steam Trap Isol.	Open

11. After HRFS start-up, coordinate with the Control Room to replenish SGS water. Particularly operate HV-370 and HV-488 as needed. Leave HV-370 closed and HV-488 Open.

12. Advise the Control Room operator that the SGS pretest checklist has been completed.

NOTE

After operation is established and consent obtained from the Control Room, Blowdown the steam drum to reduce high Iron and TDS concentrations found by the water chemistry analysis. The blowdown period using HV-382 and HV-383 shall be as follows:

<u>Iron (ppm)</u>	<u>TDS (ppm)</u>	<u>Blowdown Time</u>
200	50	0 Minute
200 to 300	50 to 100	1 Minute
300 to 500	100	2 Minute

Blowdown will only help remove dissolved solids Periodically drain certain dead legs in the SGS using HV-371 and HV-372 to remove suspended solids.

This Steam Generation Operating Procedure shall be performed by the Emcon operator. Periodically advise the SGS technician of status. This procedure assumes SGS is in Diurnal Shutdown.

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
-------------	--------------------	---------------------

A. DIURNAL SHUTDOWN TO WARM STANDBY MODE

1. Verify completion of the following checklists:

- o COP #1 Control Room pretest checklist
- o TOP #1 TSS pretest checklist
- o SOP #1 SGS pretest checklist
- o HOP #1 HRFS pretest checklist and local startup
- o HOP #2 HRFS startup

CAUTION

If freezing temperatures have been experienced, be aware of possible bad SGS instrument readings.

- |    |    |  |       |
|----|----|--|-------|
| 18 | 2. | Verify D/D temp TE-451 (DTC PV) is above 250°F, then position FCV-431 to Manual Open to start steam pipe heat-up with D/D steam.                                 | _____ |
| 02 | 3. | If R.S. is not operational, check Acurex channels 121, 129, and 131 are above 480°F and reverify FCV-151 and 161 are closed and locked, FCV-162 is open.         | _____ |
| 16 | 4. | Place/verify MAN.EHAC and EHAC are ON. This places the Circulation Heater in Automatic Pressure Control. Also, verify MAN.ESH-1 thru MAN.ESH-5 are off.          | _____ |
| 13 | 5. | Verify that SP.DL is set at 0.0" , that MAN.411 is off, FCV-411 is in cascade at Net 90, and that drum level is being maintained at 0.0 inches + or - .5 inches. | _____ |
|    | 6. | Place/verify SDC and MAN.SDC are both OFF.<br>(These may have to be on to override Hi steam drum levels)   | _____ |
|    | 7. | Place/verify FCV-321, and 331 are in cascade, at the N90 console Groups H & F, (COT/C). (Ready for N90 control after EMCON deact)                                | _____ |
|    | 8. | Verify the following set points:   |       |
| 13 |    | SP.EST 850°F Evaporator Salt Temperature (FCV-301)   |       |
|    |    | SP.SP 1100 psi Steam Delivery Pressure (FCV-321)   |       |
|    |    | SP.ST 950°F Steam Delivery Temperature (FCV-331)   | _____ |

SOP #2 SGS START-UP (EMCON)

STEP	DESCRIPTION	VERIFICATION
18 9.	Verify D/D Feedwater Temperature at TE451 is above 250°F. Change DTC-451 and DTC-452 set points to 300°F.	_____
10.	Note the Steam Drum Temperature at TE-383. The temperature must be above 500°F to initiate salt flow. If the temperature is below 500°F, wait for circulation heaters to increase the temperature above 500°F prior to proceeding.	_____
11.	Verify cold sump temp. Accurex channel 124 and 125 are within 100°F of TE-383 to prevent shocking the superheater. If difference is over 100°F, continue to heat SGS to within 100°F with circulation heaters.	_____
12.	Reverify salt path temperatures are acceptable Ref. COP #1 Table B & C.	_____
13.	Reset FCV-201 SP to 45" and stabilize.	_____
14.	Advise the SGS technician to open HV-481 (ahead of FCV-491) and Verify HV-488 is Open.	_____
15.	Have field technician unlock FCV-211.	_____
16.	Activate FCV-431 casc. control via PT-431 SP 1080 psi.	_____
17.	Activate FCV-491 automatic control with SP 1000 psi.	_____
18.	Monitor PT-321 and reduce set point of FCV-491 as required to maintain a constant level during auto SGS.CF sequence.	_____
19.	During auto SGS.CF sequence when LT-311 reaches 6" turn on MAN.SDC and SDC.	_____
20.	Close salt drain valves after verifying Acurex channel 265 is above 480°F by turning FCV-38182 and MAN.38182 off. Verify closure.	
	<u>NOTE</u>	
	The SGS cold flow auto sequence starts here. Monitor 'Control Room' Notes during auto sequence and perform as required.	
21.	Activate SGS.CF 'ON' to start auto sequence.	_____
GR 994 22.	Activate the FCV-201 level control with a set point of 50 inches. Open FCV-211. When level reaches 50 inches, change the setpoint to 23 inches.	_____
23.	Start the cold pump; PT-180 greater than 150 PSI before continuing.	_____
24.	Activate the following alarms:	
	LT-311      PT-180      TE-301      TE-384 PT-383      TE-383	



SOP #2 SGS START-UP (EMCON)

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
-------------	--------------------	---------------------

25. Set SP.341 to 100% to fully open FCV-341 and verify the position. This fills the SGS with cold salt in approx. 12 minutes.

NOTE (CONTROL ROOM)

TIME  
(REF STEP 25)

1. Monitor LT-201 to maintain sump level above 17 inches Do not cavitate pumps.
2. If salt temps are low (550°F) turn on Net 90 heater 1 to protect against freezing. Heater 1 will turn off upon FCV-383/384 switchover.

NOTE (CONTROL ROOM)

After opening FCV-341 monitor the SGS temperatures on Acurex and EMCON as listed below to verify that salt is flowing thru the SGS. Each Acurex chanel or EMCON Thermocouple read the same as the Cold Salt Temperature in the order listed:

204	°F
255	-----
270	TE-382
254	°F
TE382 (EMCON)	-----
216	COLD SALT TEMP
215	(ACUREX CH 124/125)
241	
203	
TE301 (EMCON)	
250	
TE384 (EMCON)	
208	

If these channels do not appear to be consistent with the Cold Salt Temperature, a blockage may exist. If so, OPEN FCV-301 fully to improve flow temporarily then CLOSE FCV-301 and monitor FT-321 to determine if the blockage has cleared.

NOTE (CONTROL ROOM)

When auto ramp is complete and LT-311 is below 7" turn off MAN.SDC and SDC.

26. Once superheater is filled with salt, TE-301 should read cold salt temp (approx. 5 minutes after step 24). Open FCV-301 with SP.301 to 100% and verify position.

27. When FT-321 flow is greater than 10 Klb/hr., set SP.301 to 0% and turn MAN.301 OFF. Verify that FCV-301 closes.

NOTE

The SGS.CF cold flow auto sequence stops here. The next few steps will be performed manually.

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
28.	Place FCV-301 in Cascade at the Network 90 to control Evaporator salt temperature at SP.EST.	_____
	<u>NOTE</u> Reactivate FCV-301 at Net 90 after any trip. SGS IS NOW IN WARM STANDBY AWAITING INTRODUCTION OF HOT SALT	
<b>B. <u>WARM STANDBY TO THE ON-LINE CONDITION</u></b>		
	1. Verify FCV-221 is closed.	_____
	2. Verify the Hot Sump level (LT-221) is less than 48 inches.	_____
13	3. Set MAN.331 to OFF to activate the FCV-331 Steam Delivery Temperature Control at SP.ST. Verify that FCV-331 closes and is in Casc. at Net. 90.	_____
	4. Verify/place FCV-231 in neutral.	_____
	<u>NOTE</u> The SGS.ON auto ramp sequence starts here.	
	5. Activate SGS.ON 'ON' to start auto ramp sequence.	_____
	6. Set MAN.383 to ON and FCV-383 ON (Open) and verify Micro.	_____
	7. Set MAN.384 to ON and FCV.384 to OFF (Closed) and verify micro; verify that all circulation heater circuits are off.	_____
	8. Verify the CSP is operating and FCV-341 is open 100%	_____
	9. Activate the FCV-221 Hot Sump Level Control with a set point of 40 inches.	_____
	10. Open FCV-231 by turning OPN.231 on, then off. Verify open micro.	_____
	11. When Hot Sump level reaches 40 inches, reset FCV-221 set point to 20 inches.	_____
	12. Close FCV-231 (CLS.231 ON, then off).	_____
	<u>NOTE (CONTROL ROOM)</u> When LT-221 reaches 30" open FCV-231 to allow hot salt to enter the hot sump. Operate as required to maintain level.	
	13. Turn on the Hot Salt Pump.	_____

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
-------------	--------------------	---------------------

NOTE

During the following activity of increasing salt temperature, verify the operation of FCV-432 so that deaerator pressure is held constant at 233 psi and all excess energy is being rejected by the cooling water circuit.

CAUTION

Monitor PT-382. If PT-382 pressure goes above 85 psig, close FCV-351.

14. Open FCV-351 then close FCV-341 in series using the following incremental steps to increase superheater inlet temperature (TE-382). The Operator shall monitor TE-382 to assure that TE-382 does not increase more than 100°F in any 6-minute period.

FCV-351 to 2% for 2 minutes		°F
" to 3% " " "		-----
" to 4% " " "		TE-382 TEMP
" to 5% " " "		-----
" to 6% " " "		°F
" to 7% " " "		-----
" to 8% " " "		Hot Salt Temp
" to 9% " " "		(Acurex Ch 126/127)
" to 10% " " "		-----
		; maintains 10% position

FCV-341 to 80% for 1 minute	
" to 60% " " "	
" to 40% " " "	
" to 20% " " "	
" to 10% " " "	
" to 05% " " "	
" to 2.5% " " "	
" to 1.0% " " "	
" to 0% " " "	; maintain closed

15. Close FCV-321 to 50% by setting SP.321, wait 5 sec. then set SP.321 to 10%. Wait 5 sec., then set SP.351 to 50%. Wait 5 sec., then set SP.351 to 100%.

16. Set the TSS, SGS, and HRFS operational alarms and wait 30 seconds.

PT-431	LT-221
PT-432	LT-281
	LT-291
TE-483	LT-471

SOP #2 SGS START-UP (EMCON)

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
17.	Set SP.321 to 20%, wait 20 seconds.	_____
18.	Set SP.321 to 30%, wait 20 seconds.	_____
19.	Set SP.321 to 40%, wait 20 seconds.	_____

NOTE

The SGS.ON auto ramp sequence stops here

20.	Verify/Turn off SGS.ON if it was used.	_____
-----	--	-------

THE SGS IS NOW ON-LINE IN SALT FLOW CONTROL  
(FCV-321 manually controlling SGS salt flow  
and FCV-431 auto controlling HRFS steam pressure  
via PT-431 SP normally 1080 psi.)

21.	Advise the SGS technician that drum blowdown may now be performed if required. (As determined by his SGS pretest checklist water chemistry analysis.)	_____
-----	---	-------

NOTE

The Turbine/Generator will be brought on line at this point in later testing(POP#2). To simulate the Turbine loading, complete the transfer from HRFS pressure control to SGS pressure control (steps 22 & 23) and manually position FCV-431 to change the steam dump to the deaerator.

22.	Set MAN.321 to OFF to activate SGS Steam Press. control. (FCV-321 auto controlling steam pressure at SP.SP 1100 psi.)	_____
-----	---	-------

23.	Deactivate the FCV-431 HRFS Steam Pressure Control and manually position valve to establish minimum steam flow (approx. 3 K1b/Hr.) and simulate steam loading.	_____
-----	--	-------

THE SGS IS NOW ON LINE IN AUTOMATIC BOILER FOLLOWING MODE.

REFERENCE INFORMATION

<u>Steam Load</u>	<u>FCV-431-% Open</u>	<u>FCV-321-%</u>
30% 3.45K1b/Hr	55%	
60% 7 K1b/Hr	74%	
FW Temp 400°F 100% 9.8K1b/Hr	85%	102%

This Steam Generation operating procedure shall be performed by the Emcon operator. Periodically advise the SGS technician of status.

STEP      DESCRIPTION      VERIFICATION

1. When steam demand has dropped to less than 3500 lbs/hr, switchover from SGS pressure control to flow control:
  - a) Set SP.321 value to the same value as shown on ZT321, or 50%.
  - b) Activate the FCV-431 HRFS Steam Pressure Control (using PT-431) with a set point of 1080 psig. Turn off GSTAT, Reset FCV-432 SP to 233 psi.
  - c. Deactivate the SGS Steam Pressure Control by turning MAN.321 ON.
  
2. Close FCV-351 to 10% and open FCV-321 to 100% in the following steps. Set SP.351 to 50% wait 5 seconds, then set SP.351 to 10%. After 5 seconds, set SP.321 to 50%, wait 5 seconds then set SP.321 to 100%.

NOTE

The SGS.OFF auto ramp may be used to complete step 3.

3. Open FCV-341 then close FCV-351 in series using the following incremental steps to decrease superheater inlet temperature (TE-382). The operator shall monitor TE-382 to assure that it does not decrease more than 100F° in any six minute period. Record start time.

MAN      AUTO

Time

SP.341	to	10%	for	1	minute	
"	"	to	20%	"	"	"
"	"	to	30%	"	"	"
"	"	to	40%	"	"	"
"	"	to	50%	"	"	"
"	"	to	60%	"	"	"
"	"	to	70%	"	"	"
"	"	to	80%	"	"	"
"	"	to	90%	"	"	"
"	"	to	100%	"	"	" ; maintain open

TE-382 °F

SOP #3 SGS SHUTDOWN (EMCON)

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
3.	Hot salt ramp down (cont'd).  SP.351 to 6% for 1 minute " " to 4% " 3 " " " to 2% " " " " " to 1.5% " " " " " to 1% " " " " " to 0.5% " " " " " to 0% " " "; maintain closed	
	Verify/Turn off SGS.OFF if it was used. (USED--NOT USED)	_____
04 4.	Turn off the Hot Salt Pump. N90 will hold FCV-351 closed if the Hot Salt Pump is not running.	_____
5.	Deactivate automatic control and close FCV-221. Verify closed.	_____
6.	Close FCV-231. If sump level (LT-221) shows indication of leakage (slow rise), manually lock FCV-231 closed.	_____
13 7.	Deactivate the FCV-331 Steam Delivery Temperature Control by setting SP.331 to 10% and turning MAN.331 to ON.	_____
8.	Set FCV-384 to ON (Open) and verify the position on the micros.	_____
9.	Set FCV-383 to OFF (Close) and verify the position on the micros.	_____
10.	Verify MAN.EHAC ON, EHAC OFF and then back ON (pulse signal). TE-383 must be below 500°F.	_____

THE SGS IS NOW IN WARM STANDBY

NOTE

To maintain the Warm Standby condition accomplish the following:

- a) Verify salt system temperatures (COP #1 Tables A & B) are 480°F minimum.
- b) To maintain water/steam pressure at 1100 psig, reduce salt flow thru FCV-341 to lowest compatible with stable flow (still maintaining PT-383 at 1100 psig).

Extended Warm Stdby

SOP #3 SGS SHUTDOWN (EMCON)

---

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>															
13	11. Deactivate the FCV-301 Evaporator Salt Inlet Temperature Control by setting SP.301 at 0% and turning MAN.301 ON.	_____															
15 18	12. Deactivate the following Alarms:  <table style="margin-left: 40px;"> <tr> <td>TE-301</td> <td>LT-221</td> <td>PT-383</td> </tr> <tr> <td>TE-383</td> <td>LT-281</td> <td>PT-432</td> </tr> <tr> <td>TE-384</td> <td>LT-291</td> <td>PT-483</td> </tr> <tr> <td>TE-483</td> <td>LT-311</td> <td></td> </tr> <tr> <td></td> <td>LT-471</td> <td></td> </tr> </table>	TE-301	LT-221	PT-383	TE-383	LT-281	PT-432	TE-384	LT-291	PT-483	TE-483	LT-311			LT-471		_____
TE-301	LT-221	PT-383															
TE-383	LT-281	PT-432															
TE-384	LT-291	PT-483															
TE-483	LT-311																
	LT-471																
04	13. Turn off the boost pump and cold salt pump. Verify FCV-341 closed. N-90 will hold FCV-341 and FCV-301 closed if the Cold Salt Pump is not running.	_____															
13	14. Place/verify the following setpoints: <table style="margin-left: 40px;"> <tr> <td>SP.301</td> <td>0%</td> </tr> <tr> <td>SP.341</td> <td>0%</td> </tr> <tr> <td>SP.351</td> <td>0%</td> </tr> </table>	SP.301	0%	SP.341	0%	SP.351	0%	_____									
SP.301	0%																
SP.341	0%																
SP.351	0%																
04	15. Deactivate automatic control and close FCV-201.	_____															
	16. Close FCV-211. If sump level shows indication of leakage (slow rise), manually lock FCV-211 closed.	_____															
	17. Turn MAN.SDC and SDC ON. This <u>MUST</u> be accomplished to allow opening of the Salt Valves for drainage.	_____															
	18. Record sump levels and time prior to SGS drainback.  LT-201 Cold sump _____, LT-221 Hot sump _____	_____															
13	19. Open the Cold Salt and Salt Drain Valves by setting the following controls and verify correct valve position.  <table style="margin-left: 40px;"> <tr> <td>SP.301</td> <td>100%</td> </tr> <tr> <td>SP.341</td> <td>100%</td> </tr> <tr> <td>MAN.38182</td> <td>On</td> </tr> <tr> <td>FCV-38182</td> <td>On</td> </tr> </table>	SP.301	100%	SP.341	100%	MAN.38182	On	FCV-38182	On	Time _____							
SP.301	100%																
SP.341	100%																
MAN.38182	On																
FCV-38182	On																
	20. Wait 5 minutes from step 18 to allow drainage of salt to the Cold Sump prior to proceeding to step 21. Cold sump level should increase 6 to 10" during drainback.	_____															

SOP #3 SGS SHUTDOWN (EMCON)

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
21.	Open the Hot Salt Valve by setting SP.351 to 100%. Verify the valve position and expect a hot sump level change of approximately 16 inches.	_____
22.	Verify FCV-491 is closed in auto with a SP of 980 psi.	_____
23.	Fill the drum with Feedwater to a level of +15 inches by setting SP.411 to 20% and turning Man.411 ON. When the level has reached +15 inches, set SP.411 to 0%.	_____

NOTE

HRFS is no longer needed to support SGS and may be shutdown now if not separately required.

13	24.	20 minutes after step 18, set the controls in the following positions and verify the correct valve position:		
		SP.341	0%	
		SP.301	0%	
		SP.351	0%	
		FCV-38182	OFF	_____
	25.	Turn SDC and MAN.SDC OFF.		_____

NOTE

If ambient temperature conditions either are or expected to be less than 32°F, assure that water side freeze protection circuits are operational and that no water/steam transmitter signals (particularly LT-311) are frozen prior to leaving the system unattended. If there is any indication that LT-311 may not provide a valid signal during unattended diurnal shutdown, due to freezing or any other reason, the circulation heater should be de-energized.

02	26.	If FCV-151, FCV-161, and FCV-162 have not been manually locked closed during the SGS salt flow activity, an accumulation of salt will leak by and stagnate. Open FCV-151, FCV-161, and FCV-162 and allow the salt to drain.		_____
	27.	Advise the SGS technician to complete the SGS posttest checklist (SOP #4) if no further SGS operation is planned, and the TSS posttest checklist (TOP #4) if no further TSS operation is on-going or planned.		_____

SGS IS NOW IN DIURNAL SHUTDOWN WITH THE SALT SYSTEM DRAINED.

NOTE

This procedure will not detail the steps to take the SGS from Diurnal Shutdown to the Empty Condition because it is not a planned part of the SGS testing. Refer to the SGS Manual Section 3.10 (Operating Procedures) for these detailed steps.



This Steam Generation operating procedure will be utilized to verify SGS integrity following all tests that use the SGS. It shall be performed by the SGS technician.

STEP      DESCRIPTION      VERIFICATION

CAUTION

Salt and water/steam temperatures will normally be maintained above 500°F. If repairs are required, a shut down to the Empty condition may be required.

1. Close the following isolation valves:
 

HV-481 St. Deliv.	HV-488 Feedwater
HV-487 T-482	HV-491 T-481
  
2. Inspect the salt system for evidence of leaks and insulation damage. This is a general inspection for any condition that appears abnormal. If a problem is detected, a more thorough inspection will be required.
  - o All SGS salt piping
  - o Valves
  - o Superheater and Evaporator
  
3. Inspect the water/steam system for evidence of leaks and insulation damage. This is a general inspection for any condition that appears abnormal. If a problem is detected, a more thorough inspection will be required.
 

o SGS piping	o Superheater
o Valves, traps	o Evaporator
o BWCP	o Steam Drum
o Flange connections	o Attemperator
o Drain Plugs	o Drain & Blowdown Tank
  
4. Check for visual evidence of blown fuses, burned relays or burned electrical components in the power junction box and generally throughout the SGS/TSS.
  
5. Verify operation of the SGS skid coolant pump and radiator.
  
6. Secure the boiler water sample station (HV-386).
  
7. Turn off/verify the chemical feed pump and close HV-387.
  
8. Note any abnormalities encountered during test activities.
  
9. Advise the Control Room that the SGS post test has been completed and the SGS is secure.
  
10. Complete the TSS post test checklist (TOP #4) if no further TSS operation is planned.

This procedure will only be used for shutdown when the SGS and Propane Heater are in simultaneous operation. Due to the volume of salt that must be drained into the Cold Sump from the Propane Heater, salt will be bottled up in the SGS for approximately 20 minutes prior to drain. Perform steps 16 through 27 expeditiously.

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
	1. Advise the TSS technician to adjust the Propane Heater stack temperature control to 600°F. Propane Heater salt outlet temperature (Acurex channel 142) will decrease over a period of time.	_____
13	2. When steam demand has dropped to less than 3500 lbs/hr, switchover from SGS pressure control to flow control.  a) Set SP.321 value to the same value as shown on ZT321.  b) Activate the FCV 431 HRFS Steam Pressure Control (using PT-431) with a set point of 1100 psig.  c) Deactivate the Steam Pressure Control by turning MAN.321 on.	_____
	3. Close FCV 351 to 10% and open FCV 321 to 100% in the following steps: Set SP.351 to 50%, wait 5 seconds; then set SP.351 to 10%; after 5 seconds, set SP.321 to 50%; wait 5 seconds, then set SP.321 to 100%.	_____
	4. Open FCV 341; then close FCV 351 in series using the following incremental steps to decrease superheater inlet temperature (TE382). The operator will monitor TE382 to assure that TE382 does not decrease more than 100°F in any 6-minute period. Record start time.	_____
		Time
	SP.341 to 10% for 1 minute	
	" " to 20% for " "	
	" " to 30% for " "	
	" " to 40% for " "	
	" " to 50% for " "	
	" " to 60% for 1 minute	
	" " to 70% for " "	
	" " to 80% for " "	
	" " to 90% for " "	
	" " to 100% for " " ; maintain full open	

SOP #5 SGS AND PROPANE HEATER SHUTDOWN

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
	SP.351 to 6% for 1 minute	
	" " to 4% for 3 minutes	
	" " to 2% for 3 minutes	
	" " to 1.5% for 3 minutes	
	" " to 1% for 3 minutes	
	" " to 0.5% for 3 minutes	
	" " to 0% for 3 minutes; maintain closed	_____
04	5. Turn off the Hot Salt Pump. N90 will hold FCV351 closed if the Hot Salt Pump is not running.	_____
	6. Deactivate hot sump level control and close FCV 221. Verify closed.	_____
	7. Close FCV231. If sump level (LT-221) shows indication of leakage (slow rise), manually lock FCV231 closed.	_____
13	8. Deactivate the FCV331 Steam Delivery Temperature Control by setting SP.331 to 10% and turning MAN.331 On.	_____
14	9. Set FCV384 to ON (open) and verify the position on the micros.	_____
13	10. Set FCV383 to OFF (closed) and verify the position on the micros.	_____
	11. Verify MAN.EHAC ON. Turn EHAC off and then back on (pulse signal)	_____

SGS IS NOW IN WARM STANDBY

NOTE

To maintain the Warm Standby condition accomplish the following:

- a) Verify salt system temperatures (COP #1 Table A & B) are 480 F minimum,
- b) To maintain water/steam pressure at 1100 psig, reduce salt flow thru FCV341 to lowest compatible with stable flow (still maintaining PT-383 at 1100 psig).

Extended Warm Stdby

SOP #5 SGS AND PROPANE HEATER SHUTDOWN

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
13	12. Deactivate the FCV-301 Evaporator Salt inlet temperature control by setting SP.301 at 0% and turning MAN.301 on.	_____
04	13. Deactivate cold sump level control and close FCV 201.	_____
	14. Close FCV 211 and manually lock it closed.	_____

CAUTION

The salt in the SGS will be bottled up until the cold salt valves are opened in Step 26. Do not delay in performing the following steps:

	15. Turn off the Cold Salt Pump and Boost Pump when the PT-180 pump outlet pressure drops below 150 psig (LT-201 approx. 11.5 in.) N90 interlock will close FCV 301 and FCV 341 - verify.	_____
05	16. Start Propane Heater drain by Opening FCV 241 to 100% open. Verify position.	_____

NOTE

There are two ways to deplete cold sump level after propane heater has been drained back to the cold sump. The best way is thru FCV-151, FCV-199, FCV-162 and back to the cold tank. The alternate way is to go thru SGS. Some of the following steps will have two parts; one for depleting the cold sump via FCV-151, or one for depleting cold sump via SGS.

	17. Place the FCV-151 handwheel in neutral. (This step isn't necessary if SGS will be used for depleting cold sump)	_____
	18. Continue to monitor LT-201. When it stabilizes at 55", close FCV 241 and manually lock it closed.	_____
04	19. Start the Cold Salt Pump and Boost Pump and verify PT-180 increases to greater than 170 psig.	_____
	20. Incrementally open FCV 151 to 40%.	_____

SOP #5 SGS AND PROPANE HEATER SHUTDOWN

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
13	21. If SGS is used to deplete cold sump, Open FCV-301 and FCV-341.	_____
04	22. Turn off the Cold Salt Pump and Boost Pump when LT-201 reaches approx. 25".	_____
02	23. Close FCV 151, if used.	_____
	24. Turn MAN.SDC and SDC ON. This <u>MUST BE</u> accomplished to allow opening of the Salt Valves for drainage.	_____
13	25. Open the Salt and Salt Drain Valves by setting the following controls. Verify correct valve position.	
	MAN.301 On/SP.301 100%      MAN.38182 On	
	MAN.341 On/SP.341 100%      FCV.38182 On	_____

NOTE

Monitor LT201 Cold Sump level during salt drainage. The level should increase by approx 6 inches.

- 26. Open the Hot Salt Valve by setting SP.351 to 100%. Verify the valve position and expect a hot sump level change of approximately 16 inches. Do not exceed 40" on LT-221. \_\_\_\_\_
- 27. Verify FCV491 is closed in auto with a SP of 1050 psi. \_\_\_\_\_
- 28. Fill the drum with Feedwater to a level of +15 inches, set SP.411 to 20% and turning MAN.411 ON. When the level has reached +15 inches, set SP.411 to 0%. \_\_\_\_\_

NOTE

HRFS is no longer needed to support SGS and may be shutdown now if not seperately required.

SOP #5 SGS AND PROPANE HEATER SHUTDOWN

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
	29. Advise the TSS technician to complete TOP #3A Local Propane Heater Shutdown.	_____
13 02 05	30. Close the following valves as follows:  SP.341    0%       FCV 151    Closed SP.301    0%       FCV 162    Closed SP.351    0%       FCV 241    Closed FCV.38182 OFF      FCV 242    Closed	_____
	31. Lock the following valves closed:  FCV 301 FCV 341 FCV 241 FCV 242	_____
	32. Turn SDC and MAN.SDC OFF.	_____
<u>NOTE</u>		
If ambient temperature conditions either are or are expected to be less than 32 F, assure that water side freeze protection circuits are operational and that no water/steam transmitter signals (particularly LT-311) are frozen prior to leaving the system unattended. If there is any indication that LT-311 may not provide a valid signal during unattended diurnal shutdown, due to freezing or any other reason, the circ. heater should be deenergized.		
02	33. If FCV-151, FCV-161, & FCV-162 have not been manually locked closed during the SGS salt flow activity, an accumulation of salt will leak by and stagnate. Open FCV-151, 161, & 162 to allow the salt to drain.	_____
	34. Advise the TSS/SGS technicians to complete the SGS and TSS posttest checklists (SOP #4 & TOP #4) if no further TSS/SGS operation planned.	_____

SGS IS NOW IN DIURNAL SHUTDOWN WITH THE SALT SYSTEM DRAINED

NOTE

This procedure will not detail the steps to take the SGS from Diurnal Shutdown to the Empty Condition because it is not a planned part of the SGS testing. Refer to the SGS Manual Section 3.10 (Operating Procedures) for these detailed steps.

7.5 ELECTRIC POWER GENERATION OPERATING PROCEDURES

Test Date  
6/19/84

POP #1 EPGS PRETEST CHECKLIST

This electric Power generation operating procedure will be utilized to verify EPGS integrity prior to all tests that use the EPGS. This checklist shall be completed by the EPGS technician.

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
-------------	--------------------	---------------------

NOTE 1. Be advised that these valve positions are verified correct in HRFS check-lists:

HV-501	Main Steam Isolation	(Open)
HV-577A & B	FWP Cooling Water	(As Req'd)
FCV-471	Condensate Return	(Closed from EMCON)

NOTE 2. Inspect for evidence of water and oil leaks or other abnormalities as you complete this checklist. (Verify none found in Setp 34).

A. Condenser Platform - 60' Level

1. These valves remain closed. \_\_\_\_\_  
Check only if you suspect they have been opened.
  - a. HV-593 Condenser inlet waterbox vent
  - b. HV-594 Condenser inlet waterbox drain
  - c. HV-597 Condenser blind waterbox drain
  - d. HV-598 Condenser blind waterbox vent
2. Verify these valves are open: \_\_\_\_\_
  - a. HV-584 Hotwell outlet/CNP suction
  - b. HV-581 CNP discharge
  - c. HV-582 CNP discharge orifice recirculation
  - d. HV-583 Condenser vacuum exhaust isolation
  - e. HV-586 Turbine steam seal exhaust isolation
3. Record hotwell level from sight glass LI-581, leave isolation HV-595 & 596 open. Lvl. \_\_\_\_\_"

B. 60' Level

4. Verify these valves are open: \_\_\_\_\_
  - a. HV-578 AEP seperator tank make-up
  - b. HV-588A AEP cooler cooling water supply
  - c. HV-588B AEP cooler cooling water return
5. Verify AEP separator tank level is between 4 & 6" at sight glass LI-583 (auto LV-581 M-U) \_\_\_\_\_
6. Verify CNP and AEP local disconnect switches are closed. \_\_\_\_\_

POP #1 EPGS PRETEST CHECKLIST

STEP	DESCRIPTION	VERIFICATION
C. <u>Control Area - 80' Level</u>		
7.	Verify EPGS UPS has 2 Green lights on.	_____
8.	Turn on exciter cabinets vent fans with switch on side of VRP. Verify vent fan operation at VRP, rectifier cabinet, resistor cabinet, and at isolation transformer enclosure (L4 Bkr. 12).	_____
9.	Verify generator breaker is racked in, charged, and open.	_____
10.	Verify electrical power is (always) on:	_____
	<ul style="list-style-type: none"> <li>a. TCP - Timer display on (L4 bkr 9)</li> <li>b. GCP - Generator Breaker green light on (L4 bkr 15)</li> <li>c. Generator heater - Local starter on/TCP sw in Auto</li> <li>d. Oil heater - Local starter on/TCP sw in Auto</li> </ul>	
11.	Close TCP sw.'s for FCV-501, 511, 512, 541, & 551	_____
12.	Determine where the EPGS will be operated from - 'local' at T-G or 'remote' at Emcon Console. Reposition mode select switch, if required, in the next step.	Local    Remote
13.	Determine if CTP is operating for HRFS/FWP (TCP red light)	
	a. CTP off - Position TCP mode select switch in the control mode determined in Step 12.	_____ CTP off
	b. CTP on - Verify TCP mode select sitch is positioned in agreement with Step 12. Correct switch position, if necessary, only with Emcon operator permission (to avoid FWP trip).	_____ CTP on
14.	Turn on all local starters except Exciter disc., 8 total, and verify 5 TCP indicating lights on.	_____
15.	Verify compressed air is available and controls functional by stroking FCV-521 from oper. mode cont'l location. Verify local air venting or valve motion and Emcon ZT-521 operation. Close FCV-521 and confirm after function check.	_____
16.	Assure turbine oil temperature is above 60°F. Conduct POP #1A Part A - Turbine oil temp. ck., if necessary, to determine oil temperature and/or warm oil.	_____



POP #1 EPGs PRETEST CHECKLIST

STEP	DESCRIPTION	VERIFICATION
D. <u>T-G Platform - 80' Level</u>		
17.	Verify HV-592 steam line drain valve is closed.	_____
18.	Verify these valves are open:	_____
	<ul style="list-style-type: none"> <li>a. HV-575 Steam line trap</li> <li>b. HV-576 Steam seal (1/4 turn open)</li> <li>c. HV-587 Generator cooling water supply</li> <li>d. HV-521 Lube oil cooler oil diverting (open to cool.)</li> <li>e. HV-574 Throttle Valve trap</li> </ul>	
19.	Verify OST mechanism is reset.	_____
20.	Verify Throttle Valve is reset closed by inspection - no un-threaded rod showing on cylinder screw.	_____
21.	Verify FCV-501 is closed by inspection.	_____
22.	Verify EOP local disconnect switch is closed.	_____
23.	Verify turbine oil reservoir level is 2 1/2", + 1/2", above normal operating level mark at dipstick LI-582; or if EOP is on for oil heating, verify dipstick LI-582 normal operating level is maintained.	_____
24.	Verify excitor bearing oil reservoir is full by removing wing-nut reservoir plug & inspecting.	_____
25.	Verify duplex oil strainers are operational. Alternate strainer selection weekly.	_____
E. <u>Tank Area - 80' Level</u>		
26.	Verify CTP local disconnect switch is closed.	_____
27.	These valves remain closed. Check only if you suspect they have been opened.	_____
	<ul style="list-style-type: none"> <li>a. HV-580 CNST drain</li> <li>b. HV-590 CTDI make-up</li> <li>c. HV-591 CTDI drain</li> <li>d. HV-599 CNST make-up isolation</li> </ul>	
28.	Open these valves:	_____
	<ul style="list-style-type: none"> <li>a. HV-579 Hotwell make-up</li> <li>b. HV-585 Hotwell dump</li> <li>c. HV-589 CTP suction</li> </ul>	_____

POP #1 EPGs PRETEST CHECKLIST

STEP	DESCRIPTION	VERIFICATION
29.	Verify CTDt is full by overflow when M-U water is added thru HV-590; or if CTP is on for HRFS/FWP, verify CTDt maintains normal operating level of 18" between 16 and 20" at sight glass LI-585.	_____
30.	Assure hotwell water quality is acceptable. Conduct (HRFS) water chemistry analysis as necessary to insure iron is less than 500 ppb. Record, if measured. Drain and refill hotwell if required to correct, Ref. POP #1A Parts B & C.	ppb. Iron _____
31.	Verify hotwell and CNST levels are correct. Conduct POP #1A Parts B & C, Hotwell and CNST level adjustment, if necessary, to correct.	_____
	a. Hotwell level 12" (betw. 9 & 14") at condenser sight glass LI-581, initially recorded in Step 3.	_____
	b. CNST level between 12 & 30" at tank sight glass LI-584.	_____
	c. Verify agreement between TCP meter LT-511 and LI-581 sight glass hotwell level.	_____
F.	<u>CMUP Room - 80' Level</u>	_____
32.	Verify FCV-471 is closed by inspection.	_____
33.	Open HV-406 condensate return to HRFS.	_____
34.	Verify no water or oil leaks or other abnormalities found.	_____
35.	Advise control room that EPGs Pre-test checklist has been completed. (Turbine oil temperature & hotwell are okay).	_____

"EPGS PRE-TEST CHECKLIST COMPLETE"

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
A.	Turbine Oil Temperature Check, as Required. Reference EPGs Pretest Checklist Step 16.	
1.	Complete pretest checklist (Steps 10,14)	_____
2.	Verify Turbine oil reservoir level is 2 1/2" + 1/2" above normal operating level mark at dipstick LI-582	_____
3.	Verify EOP local disconnect switch is on.	_____
4.	Conduct the following operations from the control location selected at the TCP mode select switch (TCPMS).	Local Remote
5.	Start EOP.	_____
6.	Verify PT-501 oil pressure increases above 6 psi.	_____
7.	Wait 1 minute, then check TT-521 oil temperature. If desired, confirm locally at TI-586.	_____
8.	Check is complete if TT-521 oil temperature is above 70°F. Turn off EOP.	_____
9.	If TT-521 oil temperature is below 70°F, leave on EOP and oil heater until temperature increases above 70°F, then turn off EOP.	_____
<u>NOTE</u>		
Pre-test checks may be continued during oil heating.		
10.	Note in remote Emcon control, the oil heater auto control may be overridden and the heater forced on, if desired, by enabling 'OH.ON'.	Enable OH.ON
11.	Disable OH.ON and return heater control to auto after oil is warm.	Disable OH.ON

POP #1A EPGs FLUID ADJUSTMENT

---

STEP	DESCRIPTION	VERIFICATION
B.	<u>Hotwell Level Adjust, as Required</u>	
1.	Complete pretest checklist (Steps 1 - 30)	_____
2.	Transfer record of hotwell level here from POP #1 EPGs Pretest checklist Step 3.	Lvl. _____"
3.	Verify remote Emcon EN.HLC auto hotwell level control is off.	_____
4.	Make up Hotwell if less than 9"	_____
	a. Attempt to determine cause of level loss (leaky pipes, improperly opened valves, shutdown). Correct as required.	
	b. From TCP control location selected, open make-up FCV-512.	
	c. Fill till hotwell level sight glass LI-581 is 12".	
	d. If CNST did not have enough water to complete fill, close FCV-512, conduct CNST make-up (POP #1A Part C), then resume fill.	
	e. Close FCV-512.	
5.	Dump Hotwell if above 14".	_____
	a. Attempt to determine cause of level increase (improperly opened valves). Correct as required.	
	b. Start CNP.	
	c. Open FCV-511.	
	d. Dump till hotwell level sight glass LT-581 is 12"	
	e. Close FCV-511.	
	f. Stop CNP.	
6.	Alternate dump if above 14" or to correct water quality (wastes condensate). Open CNP inlet strainer S-581 HV till LI-581 is 12", or if draining, Zero".	_____
7.	Verify agreement between LT-511 TCP meter and LI-581 sight glass hotwell level. Record level as left.	Lvl. _____"

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
C.	<u>CNST Level Adjustment, as Required</u>	
	1. Verify CNST level is between 12 and 30" at sight glass LI-584.	_____
	2. Dump if above 30" by draining through HV-580 into floor drain. The preferred dump is into the hotwell (POP #1A Part B, Step 4), but it is assumed here that the hotwell level is already properly adjusted.	_____
	3. Fill if lower than 12".	_____

NOTE

This fill procedure will deplete the CMUP stand pipe. If CMUP is operating, do not allow this to happen by reducing the stand pipe air overpressure, either by relief valve manual blow-off or regulator adjustment.

- a. Verify HRFS/Cycle Fill Pump is on.
- b. Open CNST M-U FCV-541 with TCP switch.
- c. Open M-U HV-599.
- d. When filled, close HV-599 and FCV-541.
- e. Readjust CMUP stand pipe level.

NOTE

Hydrazine can be added to the CNST as determined from a Water Quality Analysis by filling a beaker at the HRFS Hydrazine Feed Tank drain and pouring it into the CNST LS-541 flange opening.

STEP DESCRIPTION

VERIFICATION

*This is all local  
from 7-65 thru  
to 7-72*

A. EPGS PUMP S/U

1. Verify:
  - Synch sw. handle has been procured as required.
  - POP #1 EPGS Pretest Checklist is complete.
  - EPGS control is in local (Do not disrupt CNP oper.). \_\_\_\_\_
2. Start CTP, if not already on. Verify on. \_\_\_\_\_
3. Start CTF if ambient temp. is above freezing. Verify. \_\_\_\_\_
4. Confirm LT-511 hotwell level is 12" (or between 9 & 14"). \_\_\_\_\_
5. Open FCV-551 for CNP recirculation. \_\_\_\_\_
6. Start CNP. Verify on, LT-511 hotwell level will drop 1". Note EPS will lock this out upon prior SGS BCP shutdown. Advise the Emcon operator to reset EPS 3 and 2 to clear. \_\_\_\_\_
7. Start AEP. Verify on, PT-502 condenser pressure should decrease to less than 15" Hg. \_\_\_\_\_
8. Confirm oil cooling FCV-521 closed (Emcon ZT-521). \_\_\_\_\_
9. Place EOP select. sw. in auto. Start EOP. Verify on. PT-501 oil bearing pressure should increase above 8 psi. \_\_\_\_\_
10. Wait 1 minute, then verify TT-521 oil temperature is above 60°F. \_\_\_\_\_
11. Reset Emerg. trip ETR (FCV-561) and verify PT-531 Hydraulic oil pressure is above 50 psig. \_\_\_\_\_

'EPGS PUMPS ON'

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
<b>B. T-G SET-UP</b>		
1.	Verify from Emcon operator that condenser cooling water temp. TE-486 is below 100°F.	_____
2.	Verify <u>SGS</u> steam production from Emcon operator.	_____
	a. PT-431 Steam pressure above 1000 psi	_____
	b. TE-483 Steam temperature above 600°F and rising	_____
3.	Verify from Emcon operator that SGS is in manual salt flow control (5 klb/hr min. steam flow) and FCV-431 is controlling steam pressure.	_____
4.	Advise the Emcon operator to transfer primary D/D level control from CMUP to CNP by activating FCV-471 with a SP of 15" and resetting the SP of FY-472 to 14".	_____
5.	<del>Close</del> <sup>Close</sup> CNP recirc. FCV-551.	_____
6.	Verify <u>EPGS</u> turbine start-up readiness	_____
	a. (sight windows) FI-501 & 502 brg. oil flow	_____
	b. TT-521 oil temperature above 60°F	_____
	c. PT-501 brg. oil press above 8 psig	_____
	d. PT-502 condenser vacuum below 15" Hg.	_____
	e. LT-511 hotwell level at 12" (betw 9 & 14")	_____
	f. PT-531 hydraulic oil press above 50 psig	_____
7.	Drain steam pipe condensate by opening HV-592A & B until dry steam emerges. Reclose. Open Traps.	_____
8.	Verify TT-583 turb. steam temp. is above 550°F.	_____
9.	Open FCV-501 to allow steam up to throttle valve.	_____
10.	Verify PT-581 turb. steam press. increases above 850 PSI.	_____
11.	Record time of day and wait 2 min. to warm pipe before starting turbine.	_____
12.	Establish LT-511 12" hotwell lvl. control betw. 9 & 14"	_____
	1. Continuously monitor LT-511 hotwell lvl.	_____
	2. Dump if LT-511 above 14" by opening FCV-511 until level drops to 12".	_____
	3. Make-up if LT-511 below 9" by opening FCV-512 until level rises to 11".	_____
		<u>(Continuous)</u>
13.	Establish FCV-521 120°F cool. oil temp. cont'l.	_____
	1. Continuously monitor TT-521 oil temp.	_____
	2. Adjust FCV-521 position to maintain TT-521 oil temp. at 120°F (betw. 110-130°)	_____
		<u>(Continuous)</u>

**POP #2A LOCAL EPGs START UP**

**STEP      DESCRIPTION**

**VERIFICATION**

**WARNING**

Clear non-involved personnel  
away from the T-G for safety.

**CAUTION**

Trip Turbine if operation abnormal with ET - Emerg. Trip

**NOTES**

1. Maintain coordination between T-G and Steam operations.
2. Verify proper turbine operation as follows:
  - a. Field monitor
    1. Turbine rolling
    2. No abnormal rubbing or noise (rod ck)
    3. No unusually excessive vibration (5 G Trip)
    4. FI-501 & 502 bearing oil flowing (sight windows)
  - b. Instruments
    1. ST-582 generator speed below 1250 rpm
    2. AZT-581 turbine vibration not abnormal (Emcon VIB.OVR override available)
    3. TT-501, 502, 507 (also TE-503, 505, 506 at Emcon). Bearing oil temp.'s equalize within 20° of each other, within 50° of TT-521, and betw. 60 - 170°F limits.
    4. PT-502 cond'r vacuum below 15" Hg.
    5. PT-582 steam seal press. above      PSI.
    6. TT-583 steam temperature above 700°F
    7. PT-581 steam pressure above 850 PSI
  - c. Controls
    1. LT-511 hotwell level between 9 & 14"
    2. TT-521 cooling oil temp. between 60 & 130°F.
    3. EOP controlling hydraulic oil press. at 120 psi.  
(On at 10 pressures, Off when shaft pump operating).
3. Verify ET/OST Turbine trips as follows:
  - a. PT-531 hydraulic oil press drops to '0' PSI
  - b. ST-582 generator speed decreasing
  - c. Turbine physically slowing down
  - d. FCV-501 closed (ZSL-501 on)
4. Conduct the following 3 test trips to verify their functional operation & preheat the Turbine.



<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
<u>C. T-G START-UP</u>		
1.	Start the 1 <sup>st</sup> Turbine roll to half speed, after 2 minute pipe warming, by opening throttle valve to 25% with motor. Continue opening throttle valve manually until roll starts, then close slightly to roll-out very slowly and smoothly. Progressively and very slowly increase speed to 600 RPM. Verify proper Turbine operation (Note 2).	<hr/>
2.	Conduct test trip 1 - Lo speed MOST (Man. Overspeed Trip): a. Hit OST trip button on turbine b. Verify turbine tripped (Note 3) c. Reset OST mechanism d. Reset throttle valve closed TVM.CLS, ZT-581 0% open e. Reset EPS2.RST f. Verify trip reset by PT-531 hydraulic oil pressure above 50 psi	<hr/>
3.	Restart Turbine a 2 <sup>nd</sup> time to half speed, if trip functioned properly and before turbine stops, by reopening FCV-501 and throttle valve until generator again slowly reaches 600 RPM. Reverify proper Turbine operation (Note 2).	<hr/>
4.	Conduct test trip 2 - Lo speed ET (Emerg. Trip): a. Actuate ET Emerg. Trip b. Verify Turbine tripped (Note 3) c. Reset ETR FCV-561 (ET off) d. Reset throttle valve closed TVM.CLS, ZT-581 0% open e. Reset EPS2.RST e. Verify trip reset by PT-531 hydraulic oil pressure above 50 psi	<hr/>
5.	Restart Turbine a 3 <sup>rd</sup> time to full speed, if trip functioned properly and before turbine stops, by reopening FCV-501 and throttle valve until generator slowly reaches 1200 RPM. Locally guarantee ST-582 gen. speed does not exceed 1200 rpm and that govern. control holds it at 1200 rpm. Reverify proper turb. operation (Note 2). Do not prolong full speed operation unless TT-521 above 100°F	<hr/>
6.	Conduct test trip 3 - Full speed trip. On alternate day start-ups, repeat either the MOST, the ET, or the EPS T-G trip (Control Room PB).	<hr/>
7.	Restart Turbine a 4 <sup>th</sup> time to full speed by reopening FCV-501 and throttle valve 100%. Locally guarantee ST-582 gen. speed holds at 1200 rpm.	MOST ET PB <hr/>

STEP DESCRIPTION

VERIFICATION

8. Reverify proper turbine operation (Note 2).  
Continue manually controlling LT-511 and FCV-521.  
Confirm CTF is on and EOP is off.
- 

CAUTION

Do not continue full speed oper. unless TT-521  
oil temperature quickly increases above 110°F  
(within 5 minutes)

9. Locally turn on Exciter Disc. Sw. to start  
Generator voltage build-up.
- 

10. Verify generator no-load operation:

- a. 460V at GCP meter or Emcon ET-581
  - b. 'O'A at GCP meter or Emcon IT-581
  - c. Generator air temperature below 120°F  
(Emcon TE-508)
  - d. Emcon gen. stator temp.'s equalize within  
5°F below 180°F. (Emcon TT-510 thru 515)
- 

CAUTION

Synchronize the generator ASAP after achieving  
turbine full speed and generator voltage to  
minimize high turbine exhaust temperatures.  
TI-581 or TE-581 should be kept below 150°F.

NOTE

During the turbine heat soak, SGS salt flow  
can be reduced to the minimum required to  
maintain 1100 psi steam (controlled by HRFS  
FCV-431) to conserve hot salt.

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>		
D.	<u>GENERATOR SYNCHRONIZING / LOCAL OR EMCON</u>			
1.	Verify that T-G operation is established and then continue to complete this synch. procedure ASAP. A control transfer from local to Emcon may be done at this point.	<table border="0"> <tr> <td style="text-align: center;">Local</td> <td style="text-align: center;">Emcon</td> </tr> </table>	Local	Emcon
Local	Emcon			
<u>NOTE</u>				
Synchronizing control location coincides with turbine control location (i.e., Local - GCP or Remote - RGP) as determined by TCPMS.				
2.	Advise the steam operator to prepare for Gen. Sync. by increasing SGS salt flow to 10 kibs/hr, (FCV-321 in flow control), and insuring that HRFS FCV-431 is in steam press. control. Verify that he has done so before proceeding.	_____		
3.	Verify gen. speed above 1150 rpm and adjust to rated speed of 1200 rpm and freq. of 60 HZ with the governor control sw.	_____		
4.	Adjust the generator sync voltage using the voltage control switch until the running volts equals incoming volts at approximately 120 v. + 2 V.	_____		
5.	Install the sync sw handle and place the sync sw in the ON position. Verify sync LT's and synchroscope operation.	_____		
6.	Adjust the generator speed with the governor control switch until the pointer on the synchroscope slowly rotates in a clockwise (fast) direct.	_____		
<u>CAUTION</u>				
The generator must be in sync prior to closing the generator circuit breaker.				
7.	When the pointer is just before 12 o'clock with the sync lights out, close the generator circuit breaker.	_____		
8.	Verify the generator C/B closes by red light on.	_____		
9.	Partially load the generator to about 25 KW by raising the turb. gov. setting with the governor control switch.	_____		
10.	Adjust the power factor between 1 and .8 lag with the voltage control switch ( 5 - 10 KVARS at VT-581).	_____		
11.	Turn off the sync switch, record time and heat soak the Turbine for 15 minutes at this load. A control transfer from local to Emcon may be done at this point.	Time		
12.	Start conducting T-G hourly checks.	_____		

CAUTION

On-line generator breaker trips automatically initiate a turbine trip by FCV-501 closure.





TEST DATE

POP #2A EPGs HOURLY OPERATING CHECK-LIST

UPDATED 6/20/84

Verify all Parameters 1/2 Hourly or Hourly as shown.  
 Record Values for Parameters indicated 'R'.  
 Primarily Monitor Gauge Values,  
 Compare & Confirm TCP & Emcon values

AREA	PARAMETER	LOCAL	TCP/EMC	EMCON	VALUE	V	TIME					
							1 1/2 HR	2 1/2 HR	3 1 HR	4 1 HR	5 1 HR	6 1 HR
<u>COND'R</u>	COND'R VAC.	PI-584	PT-502		< 15" Hg	R						
	COND'R (STEAM) TEMP.	TI-581				R						
	HOTWELL (CONDENSATE) TEMP.	TI-582			100-150°F	R						
	HOTWELL LVL.	LI-581	LT-511		9-14"							
	COND'R IN GLYCOL C.W.	TI-584 TI-583 PI-586			< 120°F < 120°F 16 PSI	R R R						
<u>60' LVL</u>	AEP SEP. TK LVL.	LI-583			4-6"							
	AEP C.W. TEMP	TI-590			< 120°F	R						
	CNP SUCT. DISCH.	PI-585		PT-583		R R						
<u>TANKS</u>	CNST LVL.	LI-584			12-30"							
	CTDT LVL	LI-585			16-20"							
	CTP SUCT. DISCH.	PI-588 PI-587			1" Hg. Vac. 30-35 PSI	R R						
	C.W.			TE-582		R						

AREA	PARAMETER	LOCAL	TCP/EMC	EMCON	VALUE	V	1	2	3	4	5	6	
TURB	OIL LVL.	DIPSTICK LI-582			OPER. LVL MARK								
	OIL FLOW	FI-501			FLOW								
		FI-502			FLOW								
	OIL BRG. PRESS	PI-581	PT-501		>6 PSI								
		HYD.	PI-582	PT-531		>50 PSI							
	BRG OIL TEMP.			TI-501		110-170°F	R						
				TI-502		110-170°F	R						
					TE-503	110-170°F	R						
					TE-505	110-170°F	R						
					TE-506	110-170°F	R						
					TI-507	110-170°F	R						
	COOLER OIL TEMP.	TI-586	TI-521		80-130°F	R							
	COOLER C.W. TEMP	IN	TI-588			<120°F	R						
		OUT	TI-587			<120°F	R						
MAIN ST.			PT-581		850 PSI	R							
			TI-583		750°F	R							
ST. SEAL		PI-583				R							
			PT-582			R							
GEN	AIR TEMP	TI-580		TE-508	<100°F <40°C	R							
	C.W. TEMP	TI-589			<120°F	R							
	STATOR TEMP					<260°F	R						
						<260°F	R						
						<260°F	R						
						<260°F	R						
						<260°F	R						
GEN ELECT.	WATTS		JT-581	<750 KW	R								
★	VARS		VT-581	<100 KVAR									
	VOLT		ET-581	460V									
	CURRENT		IT-581	<1200 A									
	POWER FACTOR		PFT-581	1 To .8 Lag									
	FREQ.		ST-581	60 HZ									

★ INSTR.'s LISTED ARE AT GCP/EMC.

STEP      DESCRIPTION

VERIFICATION

A. LOCAL START-UP COORDINATION

Complete these items at the request of the local EPGS operator.

1. Momentarily enable EPS3.RST and EPS2.RST if required. \_\_\_\_\_
2. Verify Condenser C.W. temperature TE-486 is below 100°F. \_\_\_\_\_
3. Transfer primary D/D level control from CMUP to CNP by activating FCV-471 with a SP of 15" and resetting the SP of FY-472 to 14". \_\_\_\_\_
4. Verify PT-431 above 1000 psi and TE-483 above 600°F. \_\_\_\_\_
5. Place/confirm SGS in manual salt flow control (5 klb/hr min. steam flow) with FCV-431 activated and MAN.321 on. \_\_\_\_\_

B. EPGS CONTROL TRANSFER CHECKLIST

Complete this checklist before transferring EPGS control from Local to Emcon (TCPMS 'OFF' to 'ON') after T-G operation is locally established (POP #2A). PCK may be used to auto align these, turning itself off when complete.

1. Turn on FCV-501. \_\_\_\_\_
2. Enable the auto. hotwell level control EN.HLC. \_\_\_\_\_
3. Verify that lube oil cooling FCV-521 is in auto S.P. 120°F. \_\_\_\_\_
4. Turn on the following enable and control signals:

(19)	(20)	(21)
CTP	CTF	CNP
CTP.EN	CTF.EN	CNP.EN
		AEP
		AEP.EN
		EOP
		EOP.EN

5. Enable EPGS operational alarms PAL. \_\_\_\_\_

NOTE

Control transfer may be completed before or after synchronizing. Follow POP #2A guidelines to synchronizing.

6. Coordinate transfer with EPGS technician, accomplished by him switching TCP key switch from local to remote. \_\_\_\_\_

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
<b>C. <u>STEAM CONTROL TRANSFER</u></b>		
1.	Transfer SGS steam control from manual salt flow to boiler following mode.	
	a. Assure steam flow FT-311 is 5 klb/hr or more with FCV-321 in manual (SGS in manual flow control, FCV-431 is controlling steam line pressure).	_____
	b. Load turbine generator to 50-100 KW, 10-20 KVARs.	_____
	c. Verify FCV-321 is cascaded at Net 90 in preparation for it to assume control.	_____
	d. Turn off MAN.321. This puts FCV-321 in auto, controlling steam pressure at 1100 psi. (SGS in boiler following mode). Note FCV-431 is also in auto SP 1080 psi at this time.	_____
	e. Once FCV-321 has stabilized, (ZT-321 doesn't fluctuate too much), immediately continue on. (Otherwise deactivate FCV-431 & manually control.)	_____
2.	Prepare for Gen. Loading by completing the following to actuate GSTAT (Gen. status). GSTAT is only used when the T-G is on-line. Its function is to shift FCV-431 casc. control from steam line pressure PT-431 to D/D press. PT-432. D/D overpress. is limited by FCV-432.	
	a. Verify PT-432 is in auto SP 225 psi. When PT-432 goes above 225 psi, turn on GSTAT.	_____
	b. Continue to monitor FCV-321, FCV-431, FCV-432 to ensure GSTAT is functioning properly.	_____

**D. GENERATOR LOADING**

CAUTION

Coord. gen. load changes with the steam system and do not increase gen load faster than 75 kw/min. SGS load following cannot exceed a steam flow ramp rate of 10%/min.

1. Determine & adjust generator load to required load conditions using the gov. and volt. control switches.

CAUTION

Do not exceed rated load conditions of 750 KW at 0.8 P.F. lag (between 0.8 & 1.0 lag)

2. Monitor the attached list of T-G operating parameters. Verify the local T-G hourly checklist is being completed.

'ELECTRIC POWER PRODUCTION'



POP #2 EPGS OPERATION

---

Monitor these parameters intermittantly during T-G operation from Emcon:

<u>GROUP</u>	<u>PARAMETER</u>	<u>DESCRIPTION</u>	<u>VALUE</u>	<u>PARTICULARLY</u>
23	JT-581 VT-581	KW generation KVAR generation	0 - 750 KW 10 - 20 KVAR	Watch for creep Adjust with load
22	TT-501 TT-502 TE-503 TE-505 TE-506 TT-507	Brg. oil temps	110 - 160 °F	Establish stability
23	TT-510 TT-511 TT-512 TT-513 TT-514 TT-515	Gen. stator temps	150 - 200 °F	Establish stability
22	PT-581 TT-583	Steam pressure Steam temp.	above 750 psi above 750 °F	Trip parameter Trip parameter
call-up	TT-509	Gen. air temp	below 110 °F	Trip parameter
22	PT-502	Condenser vacuum	below 15 "Hg.	Affects KW generation
22 21	LT-511 FCV-521	Hotwell level Oil temp. control	9 - 14 " 120 °F	Controls check Controls check
call-up	TE-581	Turb. exh. temp	130 -150 °F	Minimize overtemp.

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
A.	<u>T-G Manual Emerg. trip</u>	
	<u>NOTE</u>	
	Initiate emerg shutdown only if necessary, but do not hesitate if emerg. conditions exist. Advise all operators of actions ASAP. If possible, try to reduce generator load before trip with governor control switch.	
1.	Open generator breaker with breaker CS or Actuate ET or Actuate EPS T-G trip button from control room. (Operate all 3 for safety)	<u>C.S. ET. EPSTGT</u>

CAUTION

Stay clear of T-G/generator breaker for safety. Expect HRFS & SGS safety relief valves to open. SGS salt flow will stop and HRFS will attempt to desuperheat steam.

2.	Verify trip; turbine speed decreasing, gen. breaker open.	_____
3.	When safe and orderly, proceed with manual shutdown Step 6.	_____
B.	<u>T-G Normal Shutdown</u>	
1.	Establish communications with Emcon operator to coordinate generator load shedding with steam reduction operations.	_____
2.	Reduce generator load by lowering governor control switch and voltage control switch. Do not reduce load faster than 75 kw/min. (Do not exceed an SGS steam flow reduction rate of 10%/min.)	_____

NOTE

Opening the gen. bkr CS automatically initiates a turb. trip by FCV-501 closure.

3.	Shutdown the T-G by opening the generator breaker with the breaker control switch as generator load is reduced to zero with the governor control switch.	_____
4.	Verify generator breaker open by green light on.	_____



This electric Power generation operating procedure will be utilized to verify EPGS integrity following all tests that use the EPGS. This checklist shall be completed by the EPGS technician.

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
1.	If used, remove the GCP synchronizing switch handle and return it to the MSEE key box.	_____
2.	Turn off local starters. Do <u>not</u> turn off CTP if being used for HRFS/FWP.	_____
	a. CTF	
	b. CTP	
	c. AEP	
	d. EOP	
	e. CNP	
	f. Exciter Disconnect	
	g. Throttle Valve Disconnect	
3.	Verify oil heater and generator heater local starters are on, TCP switches are in auto, and Emcon 'OH.ON' is off.	_____
4.	Turn off Exciter cabinet vent fans.	_____
5.	Verify EPGS UPS has 2 green lights on.	_____
6.	Record, then Reset any trip functions.	_____
7.	Verify throttle valve is reset closed by inspection. No unthreaded rod showing on cylinder screw.	_____
8.	Verify FCV-501 is closed by inspection.	_____
9.	Close these valves:	_____
	a. HV-579 Hotwell make-up Tanks at 80' Level	
	b. HV-585 Hotwell dump Tank at 80' Level	
	c. HV-406 Condensate to HRFS CMUP room at 80'	
10.	Drain hotwell through CNP S-581 HV if extended shutdown planned (longer than 1 week).	_____
11.	Verify no evidence of leaks or other abnormalities found.	_____
12.	Notify control room that the EPGS post-test has been completed.	_____

'EPGS SECURED'



Section 8  
EMCON Graphics and Groups

This section contains reproductions of the EMCON graphic displays and the pre-defined groups in the 22 line format. This material is arranged as follows:

Graphic Displays

<u>Graphic Number</u>	<u>Graphic Name</u>	<u>Page</u>
990	Receiver Panel Warm-up Temperatures	8-2
991	MSEE Overall	8-3
992	Receiver Subsystem	8-4
993	Thermal Storage Subsystem	8-5
994	Steam Generator Subsystem	8-6
995	Heat Rejection and Feedwater Subsystem	8-7
996	Electric Power Generation Subsystem	8-8

Pre-defined Groups

<u>Group Number</u>	<u>Group Name</u>	<u>Page</u>
01	RS controls with drain and purge valves	8-9
02	RS and TSS controls	8-10
03	RS and TSS instrumentation	8-11
04	TSS pump house	8-12
05	TSS storage tanks for propane heater operations	8-13
06	RS back tube temp	8-14
07	RS header temp	8-15
08	RS drain micros	8-16
09	RS purge micros	8-17
10	RS pass temp	8-18
11	Critical instrument readings	8-19
12	RS fill and drain sequence	8-20
13	SGS operation	8-21
14	SGS operations	8-22
15	SGS instrumentation	8-23
16	SGS heater control	8-24
17	SGS valve micros	8-25
18	HRFS controls	8-26
19	HRFS pump controls	8-27
20	HRFS cooling fan controls	8-28
21	Turbine operations	8-29
22	Turbine operations	8-30
23	Generator operations	8-31
26	EPS trips	8-32
27	EPS trips	8-33

# RECEIVER PANEL

MAX T: 848.F    MIN T: 486.F

EAST

WEST

TE136	TE135	TE134	TE133	TE132	TE131
850.F	696.F	675.F	559.F	566.F	498.F

TE142	TE141	TE140	TE139	TE138	TE137
837.F	792.F	528.F	644.F	688.F	641.F

TE148	TE147	TE146	TE145	TE144	TE143
600.F	819.F	613.F	649.F	730.F	487.F

09:36:03 30-JUL-84

DSP990

RECEIVER

FCV190 THRU 198

SP. SALT  
1030.F

CAVITY  
DOOR:  
OPEN

TE101  
643.F

CLOSED

LT161  
20.4IN

TE102 1030.F

LT151  
77.7IN

FCV101  
64.9PCT

HOT SURGE TANK

FCV180 THRU 189

PT182  
120.PSI

COLD  
SURGE  
TANK

CLOSED

PT181  
44.PSI

FT101  
59.4KLB  
FD101  
60.2KLB

TE161  
1020.F

FCV102  
64.9PCT

TE291  
948.F

TE281  
639.F

FCV199  
CLOSED

FCV161  
41.3PCT


FCV162  
.0PCT

FCV151  
100.0PCT


LT291  
95.0IN

LT281  
51.0IN

BP  
ON



HOT TANK




COLD TANK

FCV201  
96.4PCT

LT201  
21.8IN

CSP  
ON




COLD SUMP

PT180  
297.PSI

14:49:33 1-AUG-84  
DSP992




# THERMAL STORAGE



8-5

# STEAM GENERATOR




9-8

10:17:53 27-JUL-84  
DSP994

# HEAT REJECTION

TRIP - PCM3




8-7

09:25:51 27-JUL-84  
DSP995

# POWER GENERATION

# OPERATING STATUS



8-6

10:20:27 27-JUL-84 DSP996

ID	FCV	UNIT	RCVR	SALT	FLOW	CONTROL	H	100.0	L	0	PCM	
01	FCV101	.1PCT	XXX	RCVR	SALT	FLOW	CONTROL	H	100.0	L	.0	PCM 1
02	FCV102	.0KLB	XXX	RCVR	SALT	FLOW		H	100.0	L	20.0	PCM 1
03	FT101	.0KLB	XXX	RCVR	SALT	FLOW		H	100.0	L	.0	PCM 1
04	FD101	.0KLB	XXX	FLOW	DEMAND			H	100.0	L	.0	PCM 1
05	RCA	.0KLB	OFF	RCVR	CONTROL	ALGORM		H	100.0	L	.0	PCM 1
06	SP.SALT	750.F	XXX	RCVR	SALT	TEMP	SETPT	H	1060.	L	700.	PCM 1
07	PT180	0.PSI	XXX	RCVR	BOOST	PUMP	DSCHGE	H	400.	L	275.	PCM 3
08	PT181	0.PSI	XXX	RCVR	INLET	PRESS		H	125.	L	10.	PCM 1
09	TE101	632.F	XXX	RCVR	INLET	HEADER		H	650.	L	500.	PCM 1
10	TE102	531.F	XXX	RCVR	OUTLET	HEADER		H	1060.	L	500.	PCM 1
11	FCV180T89	0.OFF		RCVR	DRAIN	VALVES						PCM 1
12	FCV190	0.OFF		PURGE	VALVE	PANELS	01.02					PCM 1
13	FCV191	0.OFF		PURGE	VALVE	PANELS	03.04					PCM 1
14	FCV192	0.OFF		PURGE	VALVE	PANELS	05.06					PCM 1
15	FCV193	0.OFF		PURGE	VALVE	PANELS	07.08					PCM 1
16	FCV194	0.OFF		PURGE	VALVE	PANELS	09.10					PCM 1
17	FCV195	0.OFF		PURGE	VALVE	PANELS	11.12					PCM 1
18	FCV196	0.OFF		PURGE	VALVE	PANELS	13.14					PCM 1
19	FCV197	0.OFF		PURGE	VALVE	PANELS	15.16					PCM 1
20	FCV198	0.OFF		PURGE	VALVE	PANELS	17.18					PCM 1
21	LT151	.0IN	XXX	RCVR	COLD	SURGE	TANK	H	90.0	L	10.0	PCM 1
22	LT161	1.0IN	XXX	RCVR	HOT	SURGE	TANK	H	70.0	L	15.0	PCM 3

8-8

COPY

GROUP 01  
27-JUL-84 15:41:54

01	FCV101	98.4PCT	XXX	RCVR	SALT	FLOW	CONTRL	H	100.0	L	.0	PCM	1
02	FCV102	98.6PCT	XXX	RCVR	SALT	FLOW	CONTRL	H	100.0	L	.0	PCM	1
04	FCV151	.1PCT	XXX	RCVR	COLD	SURGE	TANK	H	100.0	L	.0	PCM	1
05	FCV161	1.4IN	XXX	RCVR	DWNCMR	HOT	TANK	H	70.0	L	15.0	PCM	3
06	FCV162	1.4IN	XXX	RCVR	DWNCMR	COLD	TANK	H	70.0	L	15.0	PCM	3
07	FCV201	26.4IN	XXX	TSS	COLD	SUMP	LEVEL	H	60.0	L	15.0	PCM	3
08	FCV199	0.OFF		RCVR	DRAIN	FILL	ISOLAT					PCM	3
09	FCV171	0.OFF		RCVR	CTANK	AIR	SUPPLY					PCM	1
10	ZSH199	1.ON	XXX	RCVR	DRAIN	FILL	ISOLAT					PCM	3
11	ZSL199	0.OFF	XXX	RCVR	DRAIN	FILL	ISOLAT					PCM	3
12	OPN.211	0.OFF		TSS	COLD	SUMP	ISOLAT					PCM	3
13	CLS.211	0.OFF		TSS	COLD	SUMP	ISOLAT					PCM	3
14	ZSH211	0.OFF	XXX	TSS	COLD	SUMP	ISOLAT					PCM	3
15	ZSL211	1.ON	XXX	TSS	COLD	SUMP	ISOLAT					PCM	3
16	DR.OPN	0.OFF		RCVR	CAVITY	DOOR	OPEN					PCM	1
17	DR.CLS	0.OFF		RCVR	CAVITY	DOOR	CLOSE					PCM	1
18	ZSHDR	0.OFF	XXX	RCVR	CAVITY	DOOR	OPEN					PCM	1
19	ZSLDR	1.ON	XXX	RCVR	CAVITY	DOOR	CLOSED					PCM	1
20	LT281	124.9IN		TSS	COLD	TANK	LEVEL	H	134.0	L	15.0	PCM	3
21	LT291	.9IN	LOA	TSS	HOT	TANK	LEVEL	H	190.0	L	10.0	PCM	3
22	PS281	1.ON		TSS	SGS	AIR	SUPPLY					PCM	3

8-10

COPY

GROUP 02

01	LT161	0.7IN	XXX	RCVR	HOT	SURGE	TANK	H	70.0	L	15.0	PCM	3
02	LT201	29.8IN	XXX	TSS	COLD	SUMP	LEVEL	H	60.0	L	15.0	PCM	3
04	LT221	39.8IN	XXX	TSS	HOT	SUMP	LEVEL	H	41.0	L	15.0	PCM	3
05	LT281	50.2IN	XXX	TSS	COLD	TANK	LEVEL	H	134.0	L	15.0	PCM	3
06	LT291	108.2IN	XXX	TSS	HOT	TANK	LEVEL	H	190.0	L	10.0	PCM	3
07	PT180	0.PSI	XXX	RCVR	BOOST	PUMP	DSCHGE	H	400.	L	275.	PCM	3
08	PT181	0.PSI	XXX	RCVR	INLET	PRESS		H	125.	L	10.	PCM	1
09	PT182	0.PSI	XXX	RCVR	COLD	SURGE	TANK	H	180.	L	10.	PCM	1
10	FT101	0KLB	XXX	RCVR	SALT	FLOW		H	100.0	L	20.0	PCM	1
11	TE101	598.F	XXX	RCVR	INLET	HEADER		H	650.	L	500.	PCM	1
12	TE102	526.F	XXX	RCVR	OUTLET	HEADER		H	1060.	L	500.	PCM	1
13	TE180	94.F	XXX	BOOST	PUMP	BEARNG	TEMP	H	190.	L	-99.	PCM	3
14	TE181	178.F	XXX	BOOST	PUMP	SUMP	VENT	H	350.	L	-99.	PCM	3
15	TE182	563.F	XXX	RCVR	COLD	SURGE	TANK	H	750.	L	500.	PCM	1
16	TE183	488.F	XXX	RCVR	HOT	SURGE	TANK	H	1070.	L	500.	PCM	1
17	TE184	274.F	XXX	RCVR	HOT	SURGE	VENT	H	400.	L	-99.	PCM	1
18	TE211	175.F	XXX	TSS	COLD	SUMP	VENT	H	400.	L	-99.	PCM	3
19	TE231	96.F	XXX	TSS	HOT	SUMP	VENT	H	400.	L	-99.	PCM	3
20	TE281	584.F	XXX	TSS	CTANK	RAKE	LOWER	H	750.	L	500.	PCM	3
21	TE283	568.F	XXX	TSS	CTANK	RAKE	UPPER	H	750.	L	500.	PCM	3

8-11

COPY

GROUP 03  
27-JUL-84 15:47:45

01	OPN.211	0. OFF	XXX	TSS	COLD	SUMP	ISOLAT						PCM	3
02	CLS.211	0. OFF		TSS	COLD	SUMP	ISOLAT						PCM	3
03	ZSH211	0. OFF	XXX	TSS	COLD	SUMP	ISOLAT						PCM	3
04	ZSL211	1. ON	XXX	TSS	COLD	SUMP	ISOLAT						PCM	3
05	FCV221	39.9 IN	XXX	TSS	HOT	SUMP	LEVEL	H	100.0	L	.0		PCM	3
06	OPN.231	0. OFF		TSS	HOT	SUMP	ISOLAT						PCM	3
07	CLS.231	0. OFF		TSS	HOT	SUMP	ISOLAT						PCM	3
08	ZSH231	0. OFF	XXX	TSS	HOT	SUMP	ISOLAT						PCM	3
09	ZSL231	1. ON	XXX	TSS	HOT	SUMP	ISOLAT						PCM	3
10	PT180	0. PSI	XXX	RCVR	BOOST	PUMP	DSCHGE	H	400.	L	275.		PCM	3
11	CSP	0. OFF		TSS	COLD	SALT	PUMP						PCM	3
12	CSP.EN	0. OFF		TSS	CSP	ENABLE							PCM	3
13	BP	0. OFF		RCVR	BOOST	PUMP							PCM	3
14	BP.EN	0. OFF		RCVR	BP	ENABLE							PCM	3
15	ZSHCSP	0. OFF	XXX	TSS	COLD	SALT	PUMP						PCM	3
16	ZSHBP	0. OFF	XXX	RCVR	SALT	BOOST	PUMP						PCM	3
17	HSP	0. OFF		TSS	HOT	SALT	PUMP						PCM	3
18	HSP.EN	0. OFF		TSS	HSP	ENABLE							PCM	3
19	ZSHHSP	0. OFF	XXX	TSS	HOT	SALT	PUMP						PCM	3
20	TE180	94. F	XXX	BOOST	PUMP	BEARNG	TEMP	H	190.	L	-99.		PCM	3
21	TE286	156. F	XXX	TSS	COLD	PUMP	BEARNG	H	190.	L	-99.		PCM	3

8-12

COPY

GROUP 04  
27-JUL-84 15:50:03



01	FCV242	0. OFF	XXX	TSS	PRPANE	HEATER	ISOLAT	H	100.0	L	0	0	FCM	3
02	FCV201	29.9IN	XXX	TSS	COLD	SUMP	LEVEL	H	60.0	L	15.0	0	PCM	3
03	FCV221	39.8IN	XXX	TSS	HOT	SUMP	LEVEL	H	100.0	L	0	0	PCM	3
04	PT180	0. PSI	XXX	RCVR	BOOST	PUMP	DSCHGE	H	400.	L	275.	0	PCM	3
05	OPN.211	0. OFF		TSS	COLD	SUMP	ISOLAT						PCM	3
06	CLS.211	0. OFF		TSS	COLD	SUMP	ISOLAT						PCM	3
07	LT201	29.9IN		TSS	COLD	SUMP	LEVEL	H	60.0	L	15.0	0	PCM	3
08	LT221	39.9IN	XXX	TSS	HOT	SUMP	LEVEL	H	41.0	L	15.0	0	PCM	3
09	LT281	50.2IN	XXX	TSS	COLD	TANK	LEVEL	H	134.0	L	15.0	0	PCM	3
10	TE281	585.F	XXX	TSS	CTANK	RAKE	LOWER	H	750.	L	500.	0	PCM	3
11	TE282	570.F	XXX	TSS	CTANK	RAKE	MIDDLE	H	750.	L	500.	0	PCM	3
12	TE283	568.F	XXX	TSS	CTANK	RAKE	UPPER	H	750.	L	500.	0	PCM	3
13	LT291	108.0IN	XXX	TSS	HOT	TANK	LEVEL	H	190.0	L	10.0	0	PCM	3
14	TE291	722.F	XXX	TSS	HTANK	RAKE	LOWER	H	1070.	L	500.	0	PCM	3
15	TE292	702.F	XXX	TSS	HTANK	RAKE	MIDDLE	H	1070.	L	500.	0	PCM	3
16	TE293	698.F	XXX	TSS	HTANK	RAKE	UPPER	H	1070.	L	500.	0	PCM	3
17	ZT241	94.2PCT	XXX	TSS	PRPANE	HEATER	FLOW	H	100.0	L	0	0	PCM	3
18	ZSH242	0. OFF	XXX	TSS	PRPANE	HEATER	ISOLAT						PCM	3
19	ZSL242	1. ON	XXX	TSS	PRPANE	HEATER	ISOLAT						PCM	3
20	ZSH211	0. OFF	XXX	TSS	COLD	SUMP	ISOLAT						PCM	3
21	ZSL211	1. ON	XXX	TSS	COLD	SUMP	ISOLAT						PCM	3

8-13

COPY

01	TE131	214.F	XXX	RCVR	PANEL	BACK	UPPER	H	645.	L	500.	PCM	1
02	TE132	98.F	XXX	RCVR	PANEL	BACK	UPPER	H	745.	L	500.	PCM	1
03	TE133	105.F	XXX	RCVR	PANEL	BACK	UPPER	H	815.	L	500.	PCM	1
04	TE134	92.F	XXX	RCVR	PANEL	BACK	UPPER	H	915.	L	500.	PCM	1
05	TE135	135.F	XXX	RCVR	PANEL	BACK	UPPER	H	980.	L	500.	PCM	1
06	TE136	228.F	XXX	RCVR	PANEL	BACK	UPPER	H	1045.	L	500.	PCM	1
07	TE137	100.F	XXX	RCVR	PANEL	BACK	MIDDLE	H	680.	L	500.	PCM	1
08	TE138	133.F	XXX	RCVR	PANEL	BACK	MIDDLE	H	735.	L	500.	PCM	1
09	TE139	94.F	XXX	RCVR	PANEL	BACK	MIDDLE	H	825.	L	500.	PCM	1
10	TE140	91.F	XXX	RCVR	PANEL	BACK	MIDDLE	H	905.	L	500.	PCM	1
11	TE141	128.F	XXX	RCVR	PANEL	BACK	MIDDLE	H	990.	L	500.	PCM	1
12	TE142	153.F	XXX	RCVR	PANEL	BACK	MIDDLE	H	1045.	L	500.	PCM	1
13	TE143	161.F	XXX	RCVR	PANEL	BACK	LOWER	H	660.	L	500.	PCM	1
14	TE144	158.F	XXX	RCVR	PANEL	BACK	LOWER	H	725.	L	500.	PCM	1
15	TE145	176.F	XXX	RCVR	PANEL	BACK	LOWER	H	830.	L	500.	PCM	1
16	TE146	110.F	XXX	RCVR	PANEL	BACK	LOWER	H	895.	L	500.	PCM	1
17	TE147	133.F	XXX	RCVR	PANEL	BACK	LOWER	H	985.	L	500.	PCM	1
18	TE148	269.F	XXX	RCVR	PANEL	BACK	LOWER	H	1035.	L	500.	PCM	1
19	RMAXT	270.F	XXX	RCVR	PANEL	MAX	TEMP	H	1080.	L	500.	PCM	1
20	RMINT	92.F	XXX	RCVR	PANEL	MIN	TEMP	H	1080.	L	500.	PCM	1

8-14

COPY

GROUP 06  
27-JUL-84 15:59:07

01	TE182	566.F	XXX	RCVR	HOT	SURGE	TANK	H	1070.	L	500.	PCM	1
02	TE183	473.F	XXX	RCVR	PASS02	OUTLET	TEMP	H	665.	L	500.	PCM	1
03	TE185	311.F	XXX	RCVR	PASS03	OUTLET	TEMP	H	690.	L	500.	PCM	1
04	TE186	598.F	XXX	RCVR	PASS04	OUTLET	TEMP	H	720.	L	500.	PCM	1
05	TE187	237.F	XXX	RCVR	PASS05	OUTLET	TEMP	H	750.	L	500.	PCM	1
06	TE188	177.F	XXX	RCVR	PASS06	OUTLET	TEMP	H	780.	L	500.	PCM	1
07	TE189	406.F	XXX	RCVR	PASS07	OUTLET	TEMP	H	810.	L	500.	PCM	1
08	TE190	642.F	XXX	RCVR	PASS08	OUTLET	TEMP	H	835.	L	500.	PCM	1
09	TE191	337.F	XXX	RCVR	PASS09	OUTLET	TEMP	H	865.	L	500.	PCM	1
10	TE192	615.F	XXX	RCVR	PASS12	OUTLET	TEMP	H	950.	L	500.	PCM	1
11	TE193	361.F	XXX	RCVR	PASS13	OUTLET	TEMP	H	975.	L	500.	PCM	1
12	TE194	672.F	XXX	RCVR	PASS14	OUTLET	TEMP	H	990.	L	500.	PCM	1
13	TE195	443.F	XXX	RCVR	PASS15	OUTLET	TEMP	H	1010.	L	500.	PCM	1
14	TE196	655.F	XXX	RCVR	PASS16	OUTLET	TEMP	H	1030.	L	500.	PCM	1
15	TE197	343.F	XXX	RCVR	PASS17	OUTLET	TEMP	H	1050.	L	500.	PCM	1
16	TE198	566.F	XXX	RCVR									

8-15

COPY

GROUP 07  
27-JUL-84 16:00:34

01	ZSH180	0. OFF	XXX	RCVR	DRAIN	NO. 1	OPEN	PCM	1
02	ZSH181	0. OFF	XXX	RCVR	DRAIN	NO. 2	OPEN	PCM	1
03	ZSH182	0. OFF	XXX	RCVR	DRAIN	NO. 3	OPEN	PCM	1
04	ZSH183	0. OFF	XXX	RCVR	DRAIN	NO. 4	OPEN	PCM	1
05	ZSH184	0. OFF	XXX	RCVR	DRAIN	NO. 5	OPEN	PCM	1
06	ZSH185	0. OFF	XXX	RCVR	DRAIN	NO. 6	OPEN	PCM	1
07	ZSH186	0. OFF	XXX	RCVR	DRAIN	NO. 7	OPEN	PCM	1
08	ZSH187	0. OFF	XXX	RCVR	DRAIN	NO. 8	OPEN	PCM	1
09	ZSH188	0. OFF	XXX	RCVR	DRAIN	NO. 9	OPEN	PCM	1
10	ZSH189	0. OFF	XXX	RCVR	DRAIN	NO. 10	OPEN	PCM	1
11	ZSL180	1. ON	XXX	RCVR	DRAIN	NO. 1	CLOSED	PCM	1
12	ZSL181	1. ON	XXX	RCVR	DRAIN	NO. 2	CLOSED	PCM	1
13	ZSL182	1. ON	XXX	RCVR	DRAIN	NO. 3	CLOSED	PCM	1
14	ZSL183	1. ON	XXX	RCVR	DRAIN	NO. 4	CLOSED	PCM	1
15	ZSL184	1. ON	XXX	RCVR	DRAIN	NO. 5	CLOSED	PCM	1
16	ZSL185	1. ON	XXX	RCVR	DRAIN	NO. 6	CLOSED	PCM	1
17	ZSL186	1. ON	XXX	RCVR	DRAIN	NO. 7	CLOSED	PCM	1
18	ZSL187	1. ON	XXX	RCVR	DRAIN	NO. 8	CLOSED	PCM	1
19	ZSL188	1. ON	XXX	RCVR	DRAIN	NO. 9	CLOSED	PCM	1
20	ZSL189	1. ON	XXX	RCVR	DRAIN	NO. 10	CLOSED	PCM	1

01	ZSH190	0.OFF	XXX	RCVR	PURGE	NO.1	OPEN	PCM	1
02	ZSH191	0.OFF	XXX	RCVR	PURGE	NO.2	OPEN	PCM	1
03	ZSH192	0.OFF	XXX	RCVR	PURGE	NO.3	OPEN	PCM	1
04	ZSH193	0.OFF	XXX	RCVR	PURGE	NO.4	OPEN	PCM	1
05	ZSH194	0.OFF	XXX	RCVR	PURGE	NO.5	OPEN	PCM	1
06	ZSH195	0.OFF	XXX	RCVR	PURGE	NO.6	OPEN	PCM	1
07	ZSH196	0.OFF	XXX	RCVR	PURGE	NO.7	OPEN	PCM	1
08	ZSH197	0.OFF	XXX	RCVR	PURGE	NO.8	OPEN	PCM	1
09	ZSH198	0.OFF	XXX	RCVR	PURGE	NO.9	OPEN	PCM	1
10	ZSL190	1.ON	XXX	RCVR	PURGE	NO.1	CLOSED	PCM	1
11	ZSL191	1.ON	XXX	RCVR	PURGE	NO.2	CLOSED	PCM	1
12	ZSL192	1.ON	XXX	RCVR	PURGE	NO.3	CLOSED	PCM	1
13	ZSL193	1.ON	XXX	RCVR	PURGE	NO.4	CLOSED	PCM	1
14	ZSL194	1.ON	XXX	RCVR	PURGE	NO.5	CLOSED	PCM	1
15	ZSL195	1.ON	XXX	RCVR	PURGE	NO.6	CLOSED	PCM	1
16	ZSL196	1.ON	XXX	RCVR	PURGE	NO.7	CLOSED	PCM	1
17	ZSL197	1.ON	XXX	RCVR	PURGE	NO.8	CLOSED	PCM	1
18	ZSL198	1.ON	XXX	RCVR	PURGE	NO.9	CLOSED	PCM	1

8-17

COPY

GROUP 09

01	TE101	522.F	XXX	RCVR	INLET	HEADER	H	650.	L	500.	PCM	1	
02	TE103	214.F	XXX	RCVR	PASS01	OUTLET	TEMP	H	640.	L	500.	PCM	1
03	TE104	203.F	XXX	RCVR	PASS02	OUTLET	TEMP	H	665.	L	500.	PCM	1
04	TE105	208.F	XXX	RCVR	PASS03	OUTLET	TEMP	H	690.	L	500.	PCM	1
05	TE106	228.F	XXX	RCVR	PASS04	OUTLET	TEMP	H	720.	L	500.	PCM	1
06	TE107	235.F	XXX	RCVR	PASS05	OUTLET	TEMP	H	750.	L	500.	PCM	1
07	TE108	255.F	XXX	RCVR	PASS06	OUTLET	TEMP	H	780.	L	500.	PCM	1
08	TE109	233.F	XXX	RCVR	PASS07	OUTLET	TEMP	H	810.	L	500.	PCM	1
09	TE110	176.F	XXX	RCVR	PASS08	OUTLET	TEMP	H	835.	L	500.	PCM	1
10	TE111	231.F	XXX	RCVR	PASS09	OUTLET	TEMP	H	865.	L	500.	PCM	1
11	TE112	204.F	XXX	RCVR	PASS10	OUTLET	TEMP	H	890.	L	500.	PCM	1
12	TE113	251.F	XXX	RCVR	PASS11	OUTLET	TEMP	H	920.	L	500.	PCM	1
13	TE114	188.F	XXX	RCVR	PASS12	OUTLET	TEMP	H	950.	L	500.	PCM	1
14	TE115	246.F	XXX	RCVR	PASS13	OUTLET	TEMP	H	975.	L	500.	PCM	1
15	TE116	200.F	XXX	RCVR	PASS14	OUTLET	TEMP	H	990.	L	500.	PCM	1
16	TE117	191.F	XXX	RCVR	PASS15	OUTLET	TEMP	H	1010.	L	500.	PCM	1
17	TE118	261.F	XXX	RCVR	PASS16	OUTLET	TEMP	H	1030.	L	500.	PCM	1
18	TE119	282.F	XXX	RCVR	PASS17	OUTLET	TEMP	H	1050.	L	500.	PCM	1
19	TE120	242.F	XXX	RCVR	PASS18	OUTLET	TEMP	H	1070.	L	500.	PCM	1
20	TE102	515.F	XXX	RCVR	OUTLET	HEADER		H	1060.	L	500.	PCM	1

8-18

COPY

GROUP 10  
27-JUL-84 16:04:52

01	TE180	0. PSI	XXX	RCVR	BOOST	PUMP	TEMP	H	400.	L	500.	PUMP	3
02	PS281	1. ON		TSS	SGS	AIR	SUPPLY					PCM	3
03	ZSHDR	0. OFF	XXX	RCVR	CAVITY	DOOR	OPEN					PCM	1
04	ZSLDR	1. ON	XXX	RCVR	CAVITY	DOOR	CLOSED					PCM	1
05	TE286	158. F	XXX	TSS	COLD	PUMP	BEARNG	H	190.	L	-99.	PCM	3
06	TE180	95. F	XXX	BOOST	PUMP	BEARNG	TEMP	H	190.	L	-99.	PCM	3
07	TE101	517. F	XXX	RCVR	INLET	HEADER		H	650.	L	500.	PCM	1
08	TE102	513. F	XXX	RCVR	OUTLET	HEADER		H	1060.	L	500.	PCM	1
09	RMAXT	249. F	XXX	RCVR	PANEL	MAX	TEMP	H	1080.	L	500.	PCM	1
10	RMINT	89. F	XXX	RCVR	PANEL	MIN	TEMP	H	1080.	L	500.	PCM	1
11	TE140	90. F	XXX	RCVR	PANEL	BACK	MIDDLE	H	905.	L	500.	PCM	1
12	PT181	0. PSI	XXX	RCVR	INLET	PRESS		H	125.	L	10.	PCM	1
13	TE211	205. F	XXX	TSS	COLD	SUMP	VENT	H	400.	L	-99.	PCM	3
14	TE181	147. F	XXX	BOOST	PUMP	SUMP	VENT	H	350.	L	-99.	PCM	3
15	TE184	263. F	XXX	RCVR	HOT	SURGE	VENT	H	400.	L	-99.	PCM	1
16	ZSHBP	0. OFF	XXX	RCVR	SALT	BOOST	PUMP					PCM	3
17	ZSHCSP	0. OFF	XXX	TSS	COLD	SALT	PUMP					PCM	3
18	ZSHCLP	0. OFF	XXX	TSS	COOLNT	PUMP						PCM	3
19	LV181	1. ON	XXX	24VDC	CONTRL	POWER	SUPPLY					PCM	1
20	LV281	1. ON	XXX	24VDC	CONTRL	POWER	SUPPLY					PCM	3
21	FT101	.0KLB	XXX	RCVR	SALT	FLOW		H	100.0	L	20.0	PCM	1
22	TE161	417. F	XXX	TSS	DMNCMR	OUTLET	TEMP	H	1070.	L	500.	PCM	3

8-19

COPY

GROUP 11  
27-JUL-84 16:07:36

01	FCV160	.0 IN	XXX	RCVR	COLD	SURGE	LEVEL	H	60.0 L	15.0	PCM	3
02	ZSHCSP	0. OFF	XXX	TSS	COLD	SALT	PUMP				PCM	3
03	ZSHBP	0. OFF	XXX	RCVR	SALT	BOOST	PUMP				PCM	3
04	PT180	0. PSI	XXX	RCVR	BOOST	PUMP	DSCHGE	H	400. L	275.	PCM	3
05	FCV151	.0 PCT	XXX	RCVR	COLD	SURGE	TANK	H	100.0 L	.0	PCM	1
06	FCV162	.0 IN	XXX	RCVR	DWNCMR	COLD	TANK	H	70.0 L	15.0	PCM	3
07	FCV161	.0 IN	XXX	RCVR	DWNCMR	HOT	TANK	H	70.0 L	15.0	PCM	3
08	FCV199	0. OFF		RCVR	DRAIN	FILL	ISOLAT				PCM	3
09	DRCLSD	1. ON	XXX	RS	DRAIN	VALVES	CLOSED				PCM	1
10	PUCLSD	1. ON	XXX	RS	PURGE	VALVES	CLOSED				PCM	1
11	PT182	0. PSI	XXX	RCVR	COLD	SURGE	TANK	H	180. L	10.	PCM	1
12	LT151	.0 IN	XXX	RCVR	COLD	SURGE	TANK	H	90.0 L	10.0	PCM	1
13	PT181	0. PSI	XXX	RCVR	INLET	PRESS		H	125. L	10.	PCM	1
14	FT101	.0 KLB	XXX	RCVR	SALT	FLOW		H	100.0 L	20.0	PCM	1
15	FCV171	0. OFF		RCVR	CTANK	AIR	SUPPLY				PCM	1
16	RS.DRAIN	0. OFF	XXX	RCVR	DRAIN						PCM	3
17	RS.FILL	0. OFF	XXX	RCVR	FILL						PCM	3
18	RS.MAN	0. OFF	XXX	RCVR	UNDER	MANUAL	CONTRL				PCM	3
19	SP.SALT	750. F	XXX	RCVR	SALT	TEMP	SETPT	H	1060. L	700.	PCM	1

*when this is on, the two valves FCV161 & FCV162 are not temperature controlled*

8-20

COPY

GROUP 12  
27-JUL-84 16:09:01



01	SP	550	EVAP	SAL	TEMP	SETPT	H	550	L	550	PCN	3	
02	SP.DL	.0IN	XXX	SGS	DRUM	LEVEL	SETPT	H	4.0	L	-4.0	PCN	3
03	SP.SP	1100.PSI	XXX	SGS	STEAM	PRESS	SETPT	H	1130.	L	1070.	PCN	3
04	SP.ST	950.F	XXX	SGS	STEAM	TEMP	SETPT	H	980.	L	920.	PCN	3
05	MAN.301	0.OFF		REQUEST	MANUAL	CONTRL	FCV301					PCN	3
06	SP.301	.0PCT	XXX	SGS	FCV301	MANUAL	SETPT	H	100.0	L	.0	PCN	3
07	MAN.321	0.OFF		REQUEST	MANUAL	CONTRL	FCV321					PCN	3
08	SP.321	99.7PCT	XXX	SGS	FCV321	MANUAL	SETPT	H	100.0	L	.0	PCN	3
09	MAN.331	0.OFF		REQUEST	MANUAL	CONTRL	FCV331					PCN	3
10	SP.331	9.9PCT	XXX	SGS	FCV331	MANUAL	SETPT	H	100.0	L	.0	PCN	3
11	MAN.341	0.OFF		REQUEST	MANUAL	CONTRL	FCV341					PCN	3
12	SP.341	.0PCT	XXX	SGS	FCV341	MANUAL	SETPT	H	100.0	L	.0	PCN	3
13	MAN.351	0.OFF		REQUEST	MANUAL	CONTRL	FCV351					PCN	3
14	SP.351	.0PCT	XXX	SGS	FCV351	MANUAL	SETPT	H	100.0	L	.0	PCN	3
15	MAN.411	0.OFF		REQUEST	MANUAL	CONTRL	FCV411					PCN	3
16	SP.411	.0PCT	XXX	SGS	FCV411	MANUAL	SETPT	H	100.0	L	.0	PCN	3
17	MAN.38182	0.OFF		SGS	EVAP	SUPHTR	DRAIN					PCN	3
18	FCV38182	0.OFF		SGS	EVAP	SUPHTR	DRAIN					PCN	3
19	MAN.383	0.OFF		SGS	ELECT	HEATER	BYPASS					PCN	3
20	FCV383	0.OFF		SGS	ELECT	HEATER	BYPASS					PCN	3
21	MAN.384	0.OFF		SGS	ELECT	HEATER	STRUP					PCN	3
22	FCV384	0.OFF		SGS	ELECT	HEATER	STRUP					PCN	3

8-21

COPY

GROUP 13  
27-JUL-84 16:10:25

01	UNIT	UNIT	UNIT	UNIT	UNIT	UNIT	UNIT	UNIT	UNIT	UNIT	UNIT	
02	TE483	105.F	XXX	HRFS	HIGH	PRESS	STEAM	H	990.	L	850.	PCM
03	PT383	62.PSI	XXX	SGS	STEAM	DRUM	PRESS	H	1250.	L	950.	PCM
04	FT411	.00KLB	XXX	HRFS	FEED	WATER	FLOW	H	16.00	L	.00	PCM
05	FT311	.01KLB	XXX	SGS	MAIN	STEAM	FLOW	H	12.60	L	3.20	PCM
06	FT381	0.LB	XXX	SGS	ATTEMP	STEAM	FLOW	H	2500.	L	0.	PCM
07	TE332	102.F	XXX	SGS	TURBIN	THROTL	TEMP	H	990.	L	910.	PCM
08	TE331	302.F	XXX	SGS	SPRHTR	STEAM	OUTLET	H	1200.	L	910.	PCM
09	PT321	63.PSI	XXX	SGS	STEAM	DLIVRY	PRESS	H	1150.	L	950.	PCM
10	PT386	0.PSI	XXX	SGS	FEED	WATER	PRESS	H	1500.	L	0.	PCM
11	TE386	97.F	XXX	HRS	FEED	WATER	TEMP	H	575.	L	500.	PCM
12	TE388	304.F	XXX	SGS	EVAPTR	WATER	TEMP	H	1100.	L	500.	PCM
13	ZT411	.0PCT	XXX	HRS	FCV411	VALVE	POS	H	100.0	L	0.	PCM
14	ZT331	.0PCT	XXX	SGS	FCV331	VALVE	POS	H	100.0	L	0.	PCM
15	ZSH384	1.ON	XXX	SGS	ELECT	HEATER	STRUP					PCM
16	ZSL384	0.OFF	XXX	SGS	ELECT	HEATER	STRUP					PCM
17	FCV401	18.PSI	XXX	HRFS	FDWATR	PUMP	PRESS	H	1500.	L	0.	PCM
18	FCV421	140.F	XXX	HRFS	FDWATR	TEMP	CONTRL	H	2500.	L	-99.	PCM
19	FCV431	.0PCT	XXX	HRFS	STEAM	CONTRL		H	100.0	L	0.	PCM
20	FCV432	1.PSI	XXX	DEATOR	OPRTNG	PRESS	CONTRL	H	400.	L	0.	PCM
21	FCV491	63.PSI	XXX	SGS	STEAM	DLIVRY	PRESS	H	1150.	L	950.	PCM
22	LT471	14.7IN	XXX	HRFS	DEATOR	LEVEL	CONTRL	H	30.0	L	10.0	PCM

8-22

COPY

GROUP 14  
27-JUL-84 16:11:54

ID	UNIT	UNIT	UNIT	UNIT	UNIT	UNIT	UNIT	UNIT	UNIT	UNIT	UNIT	UNIT	
01	TE382	457.F	XXX	SGS	SPRHTR	SALT	INLET	H	1070.	L	500.	PCM	3
02	TE301	521.F	XXX	SGS	EVAPTR	SALT	INLET	H	880.	L	500.	PCM	3
03	TE384	511.F	XXX	SGS	EVAPTR	SALT	OUTLET	H	640.	L	500.	PCM	3
04	PT384	3.PSI	XXX	SGS	EVAPTR	SALT	OUTLET	H	200.	L	0.	PCM	3
05	FT382	3.13KLB	XXX	SGS	COLD	BYPASS	FLOW	H	16.00	L	.00	PCM	3
06	FT321	4.5KLB	XXX	SGS	TOTAL	SALT	FLOW	H	100.0	L	.0	PCM	3
07	ZT301	62.6PCT	XXX	SGS	FCV301	VALVE	POS	H	100.0	L	.0	PCM	3
08	ZT321	100.0PCT	XXX	SGS	FCV321	VALVE	POS	H	100.0	L	.0	PCM	3
09	ZT341	.0PCT	XXX	SGS	FCV341	VALVE	POS	H	100.0	L	.0	PCM	3
10	ZT351	.0PCT	XXX	SGS	FCV351	VALVE	POS	H	100.0	L	.0	PCM	3
11	FCV221	39.9IN	XXX	TSS	HOT	SUMP	LEVEL	H	100.0	L	.0	PCM	3
12	FCV201	29.9IN	XXX	TSS	COLD	SUMP	LEVEL	H	60.0	L	15.0	PCM	3
13	PT180	0.PSI	XXX	RCVR	BOOST	PUMP	DSCHGE	H	400.	L	275.	PCM	3
14	LT281	49.9IN	XXX	TSS	COLD	TANK	LEVEL	H	134.0	L	15.0	PCM	3
15	LT291	108.5IN	XXX	TSS	HOT	TANK	LEVEL	H	190.0	L	10.0	PCM	3
16	PT383	58.PSI	XXX	SGS	STEAM	DRUM	PRESS	H	1250.	L	950.	PCM	3
17	FT311	.01KLB	XXX	SGS	MAIN	STEAM	FLOW	H	12.60	L	3.20	PCM	3
18	FT411	.00KLB	XXX	HRFS	FEED	WATER	FLOW	H	16.00	L	.00	PCM	3
19	LT311	-14.2IN	XXX	SGS	STEAM	DRUM	WATER	H	4.0	L	-4.0	PCM	3
20	TE387	103.F	XXX	HOT	SALT	PUMP	BEARNG	H	190.	L	-99.	PCM	3
21	TE286	154.F	XXX	TSS	COLD	PUMP	BEARNG	H	190.	L	-99.	PCM	3

8-23

COPY

GROUP 15  
27-JUL-84 16:13:13

01	ESH1	0. OFF	SGS	ELECT	HEATER NO. 1	PCM
02	ESH2	0. OFF	SGS	ELECT	HEATER NO. 2	PCM
03	ESH3	0. OFF	SGS	ELECT	HEATER NO. 3	PCM
04	ESH4	0. OFF	SGS	ELECT	HEATER NO. 4	PCM
05	ESH5	0. OFF	SGS	ELECT	HEATER NO. 5	PCM
06	MAN. ESH1	0. OFF	SGS	ELECT	HEATER NO. 1	PCM
07	MAN. ESH2	0. OFF	SGS	ELECT	HEATER NO. 2	PCM
08	MAN. ESH3	0. OFF	SGS	ELECT	HEATER NO. 3	PCM
09	MAN. ESH4	0. OFF	SGS	ELECT	HEATER NO. 4	PCM
10	MAN. ESH5	0. OFF	SGS	ELECT	HEATER NO. 5	PCM
11	EH1.ON	0. OFF	XXX	SGS	HEATER NO. 1	PCM
12	EH2.ON	0. OFF	XXX	SGS	HEATER NO. 2	PCM
13	EH3.ON	0. OFF	XXX	SGS	HEATER NO. 3	PCM
14	EH4.ON	0. OFF	XXX	SGS	HEATER NO. 4	PCM
15	EH5.ON	0. OFF	XXX	SGS	HEATER NO. 5	PCM
16	MAN. BWCP	0. OFF	SGS	WATER	CIRC PUMP	PCM
17	BWCP	0. OFF	SGS	WATER	CIRC PUMP	PCM
18	ZSHBCP	1. ON	XXX	BOILER	CIRC PUMP	PCM
19	MAN. 383	0. OFF	SGS	ELECT	HEATER BYPASS	PCM
20	MAN. 384	0. OFF	SGS	ELECT	HEATER STRTUP	PCM
21	FCV383	0. OFF	SGS	ELECT	HEATER BYPASS	PCM
22	FCV384	0. OFF	SGS	ELECT	HEATER STRTUP	PCM

Manwals must be turned on first

- manual control for electric startup heater

High & Low Micro, tells which heaters are on or off

COPY

01	ZSL381	0. OFF	XXX	SGS	EVAP	DRAIN												
02	ZSL381	0. OFF	XXX	SGS	EVAP	DRAIN												
03	ZSH382	1. ON	XXX	SGS	SUPER	HEATER	DRAIN											
04	ZSL382	0. OFF	XXX	SGS	SUPER	HEATER	DRAIN											
05	ZSH383	0. OFF	XXX	SGS	ELECT	HEATER	BYPASS											
06	ZSL383	1. ON	XXX	SGS	ELECT	HEATER	BYPASS											
07	ZSH384	1. ON	XXX	SGS	ELECT	HEATER	STRUP											
08	ZSL384	0. OFF	XXX	SGS	ELECT	HEATER	STRUP											
09	ZSL491	1. ON	XXX	HRFS	STEAM	SHUT	OFF											
10	ZT301	62.7PCT	XXX	SGS	FCV301	VALVE	POS	H	100.0	L								
11	ZT321	100.0PCT	XXX	SGS	FCV321	VALVE	POS	H	100.0	L								
12	ZT341	.0PCT	XXX	SGS	FCV341	VALVE	POS	H	100.0	L								
13	ZT351	.0PCT	XXX	SGS	FCV351	VALVE	POS	H	100.0	L								

8-25

COPY

GROUP 17  
27-JUL-84 16:16:12

01	PT472	14.6IN	XXX	HRFS	MAKEUP	PUMP	SHUT	H	30.0	L	10.0	PCM	2
02	DTC451	198.F	XXX	HRFS	DEATOR	HEATER	CONTRL	H	750.	L	-300.	PCM	2
03	DTC452	198.F	XXX	HRFS	DEATOR	HEATER	CONTRL	H	750.	L	-300.	PCM	2
04	FCV401	18.PSI	XXX	HRFS	FDWATR	PUMP	PRESS	H	1500.	L	0.	PCM	2
05	TE421	140.F	XXX	HRFS	FDWATR	TEMP	CONTRL	H	600.	L	400.	PCM	2
06	FCV421	140.F	XXX	HRFS	DEATOR	TEMP	CONTRL	H	2500.	L	-30.	PCM	2
07	PT431	8.PSI	XXX	HRFS	HIGH	PRESS	STEAM	H	1200.	L	900.	PCM	2
08	FCV431	0.PCT	XXX	HRFS	STEAM	CONTRL		H	100.0	L	0.	PCM	2
09	FCV432	1.PSI	XXX	DEATOR	OPRTNG	PRESS	CONTRL	H	400.	L	0.	PCM	2
10	FCV483	0.OFF		HRFS	DEATOR	VENT	NO.1					PCM	2
11	FCV484	0.OFF		HRFS	DEATOR	VENT	NO.2					PCM	2
12	PT401	18.PSI	XXX	HRFS	FDWATR	PUMP	PRESS	H	1400.	L	900.	PCM	2
13	PT432	1.PSI	XXX	HRFS	DEATOR	PRESS	CONTRL	H	250.	L	200.	PCM	2
14	PT482	4.PSI	XXX	HRFS	SPRAY	WATER	PRESS	H	300.	L	200.	PCM	2
15	PT483	0.PSI	XXX	HRFS	FDWATR	PRESS		H	1230.	L	1180.	PCM	2
16	PT481	16.PSI	XXX	HRFS	FDWATR	PUMP	SUPPLY	H	400.	L	170.	PCM	2
17	TE481	197.F	XXX	HRFS	DEATOR	STEAM	TEMP	H	400.	L	300.	PCM	2
18	TE483	105.F	XXX	HRFS	HIGH	PRESS	STEAM	H	990.	L	850.	PCM	2
19	TE482	196.F	XXX	HRFS	SPRAY	WATER	TEMP	H	445.	L	-300.	PCM	2
20	FT482	1.KLB	XXX	HRFS	SPRAY	WATER	FLOW	H	160.	L	0.	PCM	2
21	FT481	0.KLB	XXX	HRFS	FEED	SPRAY	WATER	H	160.	L	0.	PCM	2
22	FCV471	14.6IN	XXX	HRFS	DEATOR	LEVEL	CONTRL	H	30.0	L	10.0	PCM	2

PNPV

GROUP 18

07-11-2014 15:18:45







NO	NAME	UNIT	STATUS	DESCR	UNIT	DESCR	UNIT	DESCR	UNIT	DESCR	UNIT	DESCR
01												
02	FCV471	11.9IN	XXX	HRFS	DEATOR	LEVEL	CONTRL	H	30.0	L	10.0	PCM
03	FCV521	77.F	XXX	EPGS	OIL	COOLER	TEMP	H	500.	L	0.	PCM
04	OH.ON	0.OFF		EPGS	OIL	HEATER						PCM
05	EOP	1.ON		EPGS	ELECT	OIL	PUMP					PCM
06	EOP.EN	1.ON		EPGS	EOP	ENABLE						PCM
07	ZSHEOP	0.OFF	XXX	EPGS	ELECT	OIL	PUMP					PCM
08	PT501	0.PSI	XXX	EPGS	OIL	SUPPLY	PRESS	H	40.	L	10.	PCM
09	PT531	0.PSI	XXX	EPGS	HYDRO	OIL	PRESS	H	100.	L	55.	PCM
10	TT521	77.F	XXX	EPGS	OIL	COOLER	TEMP	H	140.	L	100.	PCM
11	TE582	75.F	XXX	EPGS	COOLNG	TOWER	DSCHGE	H	100.	L	40.	PCM
12	AEP	1.ON		EPGS	AIR	XHAUST	PUMP					PCM
13	AEP.EN	1.ON		EPGS	AEP	ENABLE						PCM
14	ZSHAEP	0.OFF	XXX	EPGS	AIR	XHAUST	PUMP					PCM
15	PT502	23.9IN	XXX	EPGS	COND	PRESS		H	15.0	L	0.	PCM
16	CNP	1.ON		EPGS	COND	PUMP						PCM
17	CNP.EN	1.ON		EPGS	CNP	ENABLE						PCM
18	ZSHCNP	0.OFF	XXX	EPGS	COND	PUMP	ON					PCM
19	PT583	0.PSI	XXX	HRFS	COND	PUMP	OUTPUT	H	300.	L	240.	PCM
20	FCV551	0.OFF		EPGS	COND	RECIRC						PCM
21	LT511	18.4IN	XXX	EPGS	HOT	WELL	LEVEL	H	16.0	L	8.0	PCM
22	EPS2.RST	0.OFF		EPS	RESET	FROM	PCM2					PCM

8-29

COPY

01	UNIT	UNIT	UNIT	UNIT	UNIT	UNIT	UNIT	UNIT	UNIT	UNIT	UNIT	
02	ETR	0. OFF		EPGS	EMER	TRIP	RESET				PCM	
03	PT581	0. PSI	XXX	EPGS	TURBIN	STEAM	PRESS	H	1500.	L	800.	PCM
04	TT583	92. F	XXX	EPGS	TURBIN	STEAM		H	990.	L	800.	PCM
05	ST582	0. RPM	XXX	EPGS	GEN	SPEED		H	1270.	L	0.	PCM
06	FCV501	0. OFF		EPGS	TURBIN	STOP						PCM
07	ZSH501	0. OFF	XXX	EPGS	TURBIN	STOP	VALVE					PCM
08	ZSL501	1. ON	XXX	EPGS	TURBIN	STOP	VALVE					PCM
09	TVM. OPN	0. OFF		EPGS	THROTL	VALVE	MOTOR					PCM
10	TVM. CLS	0. OFF		EPGS	THROTL	VALVE	MOTOR					PCM
11	ZT581	0. PCT	XXX	EPGS	THROTL	VALVE	POS	H	100.0	L	0.	PCM
12	PT582	2. PSI	XXX	EPGS	STEAM	SEAL	PRESS	H	4.	L	0.	PCM
13	PT502	23.9 IN	XXX	EPGS	CONDSR	PRESS		H	15.0	L	0.	PCM
14	LT511	13.9 IN	XXX	EPGS	HOT	WELL	LEVEL	H	16.0	L	8.0	PCM
15	PT501	0. PSI	XXX	EPGS	OIL	SUPPLY	PRESS	H	40.	L	10.	PCM
16	PT531	1. PSI	XXX	EPGS	HYDRO	OIL	PRESS	H	100.	L	55.	PCM
17	TT501	78. F	XXX	EPGS	TURBIN	OUTBD	BEARNG	H	170.	L	110.	PCM
18	TT502	78. F	XXX	EPGS	TURBIN	INBD	BEARNG	H	170.	L	110.	PCM
19	TE503	77. F	XXX	EPGS	TURBIN	OUTBD	GEAR	H	170.	L	110.	PCM
20	TE505	78. F	XXX	EPGS	GEN	OUTBD	GEAR	H	170.	L	110.	PCM
21	TE506	78. F	XXX	EPGS	GEN	INBD	GEAR	H	170.	L	110.	PCM
22	AZT581	0.1 PCT	XXX	EPGS	TURBIN	VIBRAT	0...5G	H	100.0	L	0.	PCM

COPY

GROUP 22

01	UT581	0. VAC	XXX	EPGS	POWER	0. 480	NUM	IS	H	480.	L	0.	PCM	22
02	ET581	0. VAC	XXX	EPGS	VOLTS				H	480.	L	450.	PCM	22
03	ST582	0. RPM	XXX	EPGS	GEN	SPEED			H	1270.	L	0.	PCM	22
04	ST581	0. PCT	XXX	EPGS	FREQ	55. .65	HERTZ		H	60.0	L	40.0	PCM	22
05	IT581	0. AMP	XXX	EPGS	CURRNT				H	1200.	L	0.	PCM	22
06	PFT581	1.00	LAG	XXX	EPGS	POWER	FACTOR		H	1.00	L	.85	PCM	22
07	VT581	0. VAR	XXX	EPGS	VARS	0. .960	KVARS		H	960.	L	0.	PCM	22
08	TT507	79. F	XXX	EPGS	GEN	OUTBD	BEARNG		H	170.	L	110.	PCM	22
09	TE508	78. F	XXX	EPGS	GEN	AIR	TEMP		H	100.	L	-300.	PCM	22
10	TT510	96. F	XXX	EPGS	STATOR	WINDNG	1		H	260.	L	0.	PCM	22
11	TT511	93. F	XXX	EPGS	STATOR	WINDNG	2		H	260.	L	0.	PCM	22
12	TT512	90. F	XXX	EPGS	STATOR	WINDNG	3		H	260.	L	0.	PCM	22
13	TT513	92. F	XXX	EPGS	STATOR	WINDNG	4		H	260.	L	0.	PCM	22
14	TT514	94. F	XXX	EPGS	STATOR	WINDNG	5		H	260.	L	0.	PCM	22
15	TT515	93. F	XXX	EPGS	STATOR	WINDNG	6		H	260.	L	0.	PCM	22

8-31

COPY

GROUP 23  
27-JUL-84 16:25:31

01	EPS1.RST	0.OFF		EPS	RESET	FROM	PCM1	PCM	1
02	EPS2.RST	0.OFF		EPS	RESET	FROM	PCM2	PCM	2
03	EPS3.RST	0.OFF		EPS	RESET	FROM	PCM3	PCM	3
04	TR181	0.OFF	XXX	RCVR	SALT	HIGH	TEMP	PCM	1
05	TR183	0.OFF	XXX	RCVR	INLET	PRESS	LOW	PCM	1
06	TR184	0.OFF	XXX	RCVR	TUBE	HIGH	TEMP	PCM	1
07	TR185	0.OFF	XXX	RCVR	HTANK	HIGH	LEVEL	PCM	1
08	TR182	0.OFF	XXX	BOOST	PUMP	LOW	PRESS	PCM	3
09	TR186	0.OFF	XXX	BOOST	PUMP	SUMP	LEVEL	PCM	3
10	TR281	0.OFF	XXX	HOT	SUMP	HIGH	LEVEL	PCM	3
11	TR282	0.OFF	XXX	COLD	SUMP	HIGH	LEVEL	PCM	3
12	TR381	0.OFF	XXX	SGS	DRUM	LEVEL	LO.LO	PCM	3
13	TR382	0.OFF	XXX	SGS	WATER	RECIRC	PUMP	PCM	3
14	TR383	0.OFF	XXX	SGS	DRUM	LEVEL	HI.HI	PCM	3
15	TR582	0.OFF	COS	EPCS	MANUAL	TRBGEN	TRIP	PCM	2
16	TR583	0.OFF	XXX	EPCS	OIL	PRESS	LOW	PCM	2
17	TR584	0.OFF	XXX	EPCS	GEN	BEARNG	TEMP	PCM	2
18	TR585	0.OFF	XXX	EPCS	GEN	AIR	TEMP	PCM	2
19	TR586	0.OFF	XXX	EPCS	GEN	BRKR	TRIP	PCM	2
20	TR587	0.OFF	XXX	EPCS	YIBRAT	HIGH		PCM	2
21	TR588	0.OFF	XXX	EPCS	STEAM	ENERGY	LOW	PCM	2

8-32

COPY

GROUP 26  
27-JUL-84 16:27:28

01	LV181	0.OFF	XXX	RCVR	SUMP	HIGH	TEMP	PCM	3
02	TR182	0.OFF	XXX	BOOST	PUMP	LOW	PRESS	PCM	3
03	TR183	0.OFF	XXX	RCVR	INLET	PRESS	LOW	PCM	1
04	TR184	0.OFF	XXX	RCVR	TUBE	HIGH	TEMP	PCM	1
05	TR185	0.OFF	XXX	RCVR	HTANK	HIGH	LEVEL	PCM	1
06	TR186	0.OFF	XXX	BOOST	PUMP	SUMP	LEVEL	PCM	3
07	LV181	1.ON	XXX	24VDC	CONTRL	POWER	SUPPLY	PCM	1
08	TR281	0.OFF	XXX	HOT	SUMP	HIGH	LEVEL	PCM	3
09	TR282	0.OFF	XXX	COLD	SUMP	HIGH	LEVEL	PCM	3
10	LV281	1.ON	XXX	24VDC	CONTRL	POWER	SUPPLY	PCM	3
11	TR381	0.OFF	XXX	SGS	DRUM	LEVEL	LO, LO	PCM	3
12	TR382	0.OFF	XXX	SGS	WATER	RECIRC	PUMP	PCM	3
13	N90.PS	1.OK	XXX	NETWRK	90	POWER	SUPPLY	PCM	3
14	N90.ALM	0.ALM	XXX	NETWRK	90	ALARM		PCM	3
15	LV481	1.ON	XXX	24VDC	CONTRL	POWER	SUPPLY	PCM	2
16	VIB.OVR	1.ON		EPGS	VIBRAT	OVRIDE		PCM	2
17	TR583	0.OFF	XXX	EPGS	OIL	PRESS	LOW	PCM	2
18	TR584	0.OFF	XXX	EPGS	GEN	BEARNG	TEMP	PCM	2
19	TR585	0.OFF	XXX	EPGS	GEN	AIR	TEMP	PCM	2
20	TR586	0.OFF	XXX	EPGS	GEN	BRKR	TRIP	PCM	2
21	TR587	0.OFF	XXX	EPGS	VIBRAT	HIGH		PCM	2
22	TR588	0.OFF	XXX	EPGS	STEAM	ENERGY	LOW	PCM	2

COPY

GROUP 27  
27-JUL-84 16:28:49

**COP #1 CONTROL ROOM PRETEST CHECKLIST**

**TEST DATE**  
**10/04/84**

This Console operating procedure will be utilized to verify process control integrity prior to all tests. It is unnecessary to verify control integrity of subsystems not used (not applicable). This checklist shall be completed by the control room process console operator.

**I. Test Description** \_\_\_\_\_

Start Time

**II. Responsible operating personnel**

**Primary**

**Backup**

Test Conductor (MDAC)

Stan Saloff

HelioStat Operator

Arleen Vance

Console Operator

Evans/Nelson

Operation/Safety Engineer

John Holmes

Subsystem Technicians

RS

Jerome Griego

TSS

Matt Matthews

SGS

Matt Matthews

HRFS

Jay Holton

EPGS

Jay Holton

**COP #1 CONTROL ROOM PRETEST CHECKLIST**

**III. Safety Checklist**

O/S

Complete this checklist for all operations.

**1. Site occupants**

A. Verify that all test personnel have been briefed on the scheduled test description, objectives, individual responsibilities, and expected response to emergencies \_\_\_\_\_

B. Communications established to all manned control points \_\_\_\_\_

C. Safety equipment in place:

1. OSHA protective gloves \_\_\_\_\_

2. Fire retardant coveralls \_\_\_\_\_

3. Hard hats/Face shields \_\_\_\_\_

4. Approved fire extinguishers \_\_\_\_\_

**2. Solar only**

A. "Test In Progress" lights on in the tower \_\_\_\_\_

B. Non-Test personnel informed and in secure location \_\_\_\_\_

C. Diesel-Generator on and frequency OK \_\_\_\_\_

D. Field monitor on call after solar start-up \_\_\_\_\_

E. Communications established \_\_\_\_\_

F. Tower top barricade up \_\_\_\_\_

G. Gates closed and posted with red lights or signs \_\_\_\_\_

H. Field clear and ready for start-up \_\_\_\_\_

**3. Control Room locked** \_\_\_\_\_

**4. Beam up command shall be given only after above checklist is completed by O/S Engineer** \_\_\_\_\_





**COP #1 CONTROL ROOM PRETEST CHECKLIST**

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
<b>B. ACUREX START-UP CHECKLIST</b>		
Complete this checklist for all operations using salt.		
1.	Equipment powered up:	
	a) Host chassis - Autodate Ten/50	
	b) Electrohome monitor	
	c) GT-100 Terminal	
	d) Texas Instruments 820 RO Terminal	_____
2.	Tape Cassette loaded in host drive.	_____
3.	Recent (within 60 minutes) logout of temperatures available on T1 printer.	_____
		Last Print Time
4.	Set scan rate to every 60 minutes.	_____
<b>C. AUXILIARY DATA LOGGING/DISPLAY SYSTEM</b>		
Data acquisition checklist completion optional as required.		
1.	Equipment powered up:	
	a) H-P 1000 Cabinet	
	b) H-P 2645 Terminal	
	c) H-P 2621 Terminal	
	d) Tektronix 4014 Terminal	
	e) Tektronix 463 hard-copy unit	
	f) (6) Display CRTs	
	g) Versatec Video Copier	
	h) Versatec Printer	
	i) H-P 7925 Disc Drive	_____
2.	Disk pack installed in drive, disc drive running with "READY" lamp lit.	_____
3.	System booted:	
	a) Correct date and time	
	b) Transfer file IMSRP executed	_____
4.	MSPAS program executing when data logging/display is required and MSSN2 has been started on the EMCON host.	_____
5.	Following support programs available for execut:	
	a) MSRTP	
	b) MSPSU	
	c) MSDSD	
	d) MSSL1 through MSSL6	
	e) MSCDT	_____
6.	Label file used: _____	_____
7.	Data file used: _____	_____

COP #1 CONTROL ROOM PRETEST CHECKLIST

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
-------------	--------------------	---------------------

D. NETWORK 90 SETUP CHECKLIST

Complete this checklist for operation with SGS.

1. Verify equipment powered up and operational.

- a) Bailey PCU
- b) Operator Interface Drive Unit
- \*c) Keyboard Console
- \*d) Printer

\*These components may be turned off when not in use.

V. RS - RECEIVER SUBSYSTEM

Complete this checklist for operation with Receiver.

1. Verify acceptable limits on winds (less than 30 MPH), solar insolation (above 600 W/m<sup>2</sup>) and cloud condition (partly cloudy or clear).

2. Verify TV cameras are on and operational.

3. Verify the Control Room SCRAM and EPS power supplies behind Weather Monitor Panel are On and set at 24VDC.

02 4. Open the Receiver cavity door upon the request of the RS technician for the RS pretest check. Reclose or leave open as required. (DR.OPN/CLS).

07 5. Verify Emcon RS header temperatures are above 480°F. (TE-188 inoperable).

6. Verify the Acurex RS trace heaters are operating and the temperatures are above 480°F (Table A). NOTE EXCEPTIONS. If required, heat tracing control can be taken over locally at the module control room.

7. Align/verify the following valve alignment; confirm valve temps are acceptable before moving. (to avoid bellows damage) Coordinate with Receiver technician. RCK 'ON' may be used to auto align these, turning itself off when complete.

Time

	<u>Valve</u>	<u>Description</u>	<u>Position</u>		
01	FCV-101	Salt flow control	Man/Open/N		
	FCV-102	Salt flow control	Man/Open/N		
	FCV-180-189	Drain valves	On/Open/N	(ZSH180-189 On)	08
	FCV-190-198	Purge valves	On/Open/N	(ZSH190-198 On)	09
04	CSP.EN	Enable CSP control	On		
	BP.EN	Enable BP control	ON		

COP #1 CONTROL ROOM PRETEST CHECKLIST

STEP DESCRIPTION VERIFICATION

VI. TSS - THERMAL STORAGE SUBSYSTEM

Complete this checklist for all operations using salt.

- Verify that the Acurex TSS trace heaters are operating and the temperatures are above 480°F (Table B). NOTE EXCEPTIONS. If req'd, heat tracing control can be controlled locally at salt storage control building. ✓ 8:55  
Time

- If operating Propane Heater without SGS, verify that these Acurex SGS inlet trace heaters are above 480°F (Ref. Table C): ✓

Channel	Channel	Local Temp. Verific.
204	255	FCV-241
205	256	Hot Tank inlet line
206	257	
	258	

- Verify salt levels in storage tanks and sumps are commensurate with test requirements ✓

LT-201 Cold Sump 29.5 in. (60" max)\*\*@ 606 °F (Acurex Chan 124,125)

LT-281 Cold Tank 39.8 in. (40" min)\* @ 580 °F (Acurex Chan 110-112)

LT-221 Hot Sump 25.8 in. (43" max)\*\*@ 925 °F (Acurex Chan 126,127)

LT-291 Hot Tank 32.9 in. @ 867 °F (Acurex Chan 134-136)

\*Minimum level req'd to maintain cold sump level during fill operations  
 \*\*Maximum levels automatically close FCV-211 and 231 thru Emcon and lockout may overridden by turning OVR3 on. Maximum levels require vent checks; advise technician.

- Align/verify the following valves for operation with RS, with SGS, & without Propane Heater. Confirm valve temps are accept. before moving. Coordinate with thermal storage technician. TCK 'ON' may be used to auto align these, turning itself off when complete. ✓

Valve	Description	Position	
*FCV-151	CST Level Control	Man/Closed/N	✓ checked
FCV-161	HST Level Control(Hot)	Man/Closed/N	✓ Locked
FCV-162	HST Level Control(Cold)	Man/Closed/N	✓ Open
FCV-199	Bypass valve	Off/Open /N	(ZSH199 on)
FCV-201	Cold Sump Level Control	Auto/Closed/N	SP 23"
FCV-211	Cold Sump Isol. (OPN/CLS.211)	Closed/Locked	(ZSL211 on)
FCV-221	Hot Sump Level Control	Auto/Closed/N	SP 20"
FCV-231	Hot Sump Isol. (OPN/CLS.231)	Closed/Locked	(ZSL231 on)
FCV-241	Propane Heater Inlet	Man/Closed/Locked	
FCV-242	Propane Heater Isolation	Off/Closed/Locked	✓ (ZSL242 on)
FCV-301	Bypass Salt Flow	Closed/N	(MAN on, SP Auto 0)
FCV-341	Cold Salt Isol.	Closed/N	(MAN on, SP Auto 0)
FCV-351	Hot Salt Isol.	Closed/N	(MAN on, SP Auto 0)
CSP.EN	Enable CSP Control	On	

\*Bad signal (blue) can indicate EPS closure. Clear trips and reset EPS1 & EPS3 to regain control.

COP #1 CONTROL ROOM PRETEST CHECKLIST

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>																					
	5. For operation with Propane Heater instead of Receiver <u>OR for SGS alone</u> , Modify the valve alignment of step 4 as follows:	✓																					
	<table border="1"> <thead> <tr> <th><u>Valve</u></th> <th><u>Position</u></th> </tr> </thead> <tbody> <tr> <td>FCV-151</td> <td>Locked</td> </tr> <tr> <td>FCV-161</td> <td>Locked</td> </tr> <tr> <td>FCV-162</td> <td>Man/Open/N</td> </tr> <tr> <td>FCV-242</td> <td>Neutral</td> </tr> </tbody> </table>	<u>Valve</u>	<u>Position</u>	FCV-151	Locked	FCV-161	Locked	FCV-162	Man/Open/N	FCV-242	Neutral												
<u>Valve</u>	<u>Position</u>																						
FCV-151	Locked																						
FCV-161	Locked																						
FCV-162	Man/Open/N																						
FCV-242	Neutral																						
02																							
05																							
	6. For operation without SGS, Modify the valve alignment of step 4 as follows:	N/A																					
	<table border="1"> <thead> <tr> <th><u>Valve</u></th> <th><u>Position</u></th> </tr> </thead> <tbody> <tr> <td>FCV-301</td> <td>Locked</td> </tr> <tr> <td>FCV-341</td> <td>Locked</td> </tr> </tbody> </table>	<u>Valve</u>	<u>Position</u>	FCV-301	Locked	FCV-341	Locked																
<u>Valve</u>	<u>Position</u>																						
FCV-301	Locked																						
FCV-341	Locked																						
13																							
04	7. Verify pump bearing temp's are less than 190°F (TE 180, 286, & 387 on EMCON) and alarms on.	✓																					
<b>VII. <u>SGS - STEAM GENERATION SUBSYSTEM</u></b>																							
Complete this checklist for operation with SGS.																							
	1. Verify that the Acurex SGS trace heaters are operating and the temperatures are above 480°F (Table C). NOTE EXCEPTIONS. If required, heat tracing control can be taken over locally at the salt storage control building Acurex cabinet back.	9:30 Time																					
	2. Align/verify the following valve positions. Confirm valve temps are accept. before moving. Coordinate with thermal storage technician. All SGS control valve MAN signals should be On. (Emcon commands not applicable from Net 90) SCK 'ON' may be used to auto align these, turning itself off when complete.	✓																					
	<table border="1"> <thead> <tr> <th><u>Emcon Command</u></th> <th><u>Valve Description</u></th> <th><u>Position</u></th> </tr> </thead> <tbody> <tr> <td>MAN.321 On/ SP-321 Auto 100%</td> <td>Main Salt Flow</td> <td>Open</td> </tr> <tr> <td>MAN.331 On/ SP-331 Auto 10%</td> <td>Steam Attemp.</td> <td>10% Open</td> </tr> <tr> <td>MAN.38182 On/FCV-38182 On</td> <td>Salt Drain</td> <td>Open</td> </tr> <tr> <td>*MAN.384 On/ FCV-384 On</td> <td>Circ Htr Supply</td> <td>Open</td> </tr> <tr> <td>*MAN.383 On/ FCV-383 Off</td> <td>Circ Htr Bypass</td> <td>Closed</td> </tr> <tr> <td>HSP.EN</td> <td>Enable HSP Control</td> <td>On</td> </tr> </tbody> </table>	<u>Emcon Command</u>	<u>Valve Description</u>	<u>Position</u>	MAN.321 On/ SP-321 Auto 100%	Main Salt Flow	Open	MAN.331 On/ SP-331 Auto 10%	Steam Attemp.	10% Open	MAN.38182 On/FCV-38182 On	Salt Drain	Open	*MAN.384 On/ FCV-384 On	Circ Htr Supply	Open	*MAN.383 On/ FCV-383 Off	Circ Htr Bypass	Closed	HSP.EN	Enable HSP Control	On	
<u>Emcon Command</u>	<u>Valve Description</u>	<u>Position</u>																					
MAN.321 On/ SP-321 Auto 100%	Main Salt Flow	Open																					
MAN.331 On/ SP-331 Auto 10%	Steam Attemp.	10% Open																					
MAN.38182 On/FCV-38182 On	Salt Drain	Open																					
*MAN.384 On/ FCV-384 On	Circ Htr Supply	Open																					
*MAN.383 On/ FCV-383 Off	Circ Htr Bypass	Closed																					
HSP.EN	Enable HSP Control	On																					
13																							
04																							

\*Open FCV-384 before closing FCV-383 to avoid SGS Pump and Heater Shut-off

**COP #1 CONTROL ROOM PRETEST CHECKLIST**

---

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
-------------	--------------------	---------------------

Complete the following steps after completing HRFS startup.  
(Presuming SGS is in Diurnal Shutdown).

- |    |   |                 |
|----|---|-----------------|
| 3. | If SGS F.W. inlet pipe temp. (Acurex Channel 132) is below 200°F, increase bridge pipe feedwater temperature:   |                 |
| a) | Verify D/D TE-451 is above 250°F  | <u>✓</u>        |
| b) | Advise the SGS technician to open the bridge feedwater drain HV-370, then open FCV-411 to 20% (Emcon MAN.411 on/SP Auto 20%)  | <u>✓</u>        |
| c) | Verify Acurex channel 132 increases above 200°F (Approx 5 min after opening FCV-411)  | <u>✓</u>        |
| d) | Reclose HV-370 and FCV-411  | <u>✓</u>        |
| 4. | Verify drum level LT-311 is at 0.0 inches. If drum level is below 0.0 inches; open HV-488, then open FCV-411 to 20% and fill to 0.0". Close FCV-411 and HV-488 to avoid FW leakage into drum. | <u>        </u> |
| 5. | Verify that the boiler water circulation pump (BWCP) <u>is</u> running (ZSHBCP). If it is <u>not</u> running:   |                 |
| a) | Review overnight data to determine reason and correct.  |                 |
| b) | Start BWCP  |                 |
| c) | Start circulation heater (pulse EHAC.ON)  | <u>        </u> |
| 6. | If freezing ambient temperatures have been experienced, resolve any suspicious instr. transmitter readings with the SGS technician. Be skeptical of all readings until proven.                | <u>        </u> |

**COP #1 CONTROL ROOM PRETEST CHECKLIST**

STEP

DESCRIPTION

VERIFICATION

**VIII. HRFS - HEAT REJECTION AND FEEDWATER SUBSYSTEM**

Complete this checklist for all water system operations.

1. Set/Verify the following control devices in the listed positions: HCK 'ON' may be used to auto align these, turning itself off when complete.

	<u>Identifier</u>	<u>Description</u>	<u>Command</u>	<u>Position</u>
call up	GSTAT	D/D Press Enable	Off (PT-431 control)	N/A
	EN.DTC451	D/D Heater 1 Enable	Off	N/A
	EN.DTC452	D/D Heater 2 Enable	Off	N/A
	DTC-451	D/D Heater 1	Auto SP 390 or 400°F	Not Enabled
	DTC-452	D/D Heater 2	Auto SP 390 or 400°F	Not Enabled
	FCV-401	FWP Press Recirc	Auto SP 1250 psi	Closed
	FCV-411	Feedwater Delivery	MAN.411 On/SP-411 AUTO 0%	Closed
	FCV-421	FWH Steam Supply	Man	Closed
18	FCV-431	D/D Steam Inlet	Auto/Casc to PT-431	Closed
	PT-431	Steam Line Press	Auto SP 1080 psi	N/A
	PT-432	D/D Press	Auto SP 225 psi	N/A
	FCV-432	SWHX Divert	Auto SP 233 psi	Open to Bypass
	FCV-471	T-G Condensate Return	Auto SP 0%	Closed
	FY-472	CMUP Stroke Positioner	Auto SP 0%	Closed
	FCV-491	SGS Steam Delivery	Auto SP 900 psi	Closed
21	ZSL-501	Main Steam Stop micro	On	Closed
	TCPMS	EPGS Control Mode	Off (local)	N/A
	CF1.EN	Cooling Fan 1 Enable	On	N/A
20	CF2.EN	2	On	N/A
	CF3.EN	3	On	N/A
	CF4.EN	4	On	N/A
	CF5.EN	5	On	N/A
	CF6.EN	6	On	N/A
	CFP.EN	Cycle Fill Pump	Enable	N/A
19	CMP.EN	Cond. Make-up Pump	On	N/A
	CWP.EN	Cooling Water Pump	On	N/A
	SWP.EN	Spray Water Pump	On	N/A
	FWP.EN	Feed Water Pump	On	N/A

**IX. EPGS ELECTRIC POWER GENERATION SUBSYSTEM**

Complete this checklist for all turbine-generator operations.

1. Verify RGP Gen Breaker green (open) light is on.
2. Verify that the Sync switch handle has been procured from the MSEE key box if synch is to be completed or observed from the control room.

T/C	DESCRIPTION	ACUREX CHANNEL	T/C	DESCRIPTION	ACUREX CHANNEL
TEH-190	Purge Valve #1	000	TEH-157	Receiver Outlet-Heater R	027
TEH-191	Purge Valve #2	001	TEH-158	Receiver Outlet-Heater R	028
TEH-192	Purge Valve #3	002	TEH-153	Hot Surge Tank Inlet-Heater N	029
TEH-193	Purge Valve #4	003	TEH-159	Hot Surge Tank Outlet-Heater N	030
TEH-194	Purge Valve #5	004	TEH-152	Cold Surge Tank Inlet-Heater O	031
TEH-195	Purge Valve #6	005	TEH-156	Cold Surge Tank-Heater O	032
TEH-196	Purge Valve #7	006	TEH-150	Receiver Inlet-Heater P	033
TEH-197	Purge Valve #8	007	TEH-151	Receiver Inlet-Heater P	034
TEH-198	Purge Valve #9	008	TEH-162	FCV-101-Heater Q	035
TEH-180	Drain Valve #1	009	TEH-163	FCV-102-Heater Q	036
TEH-181	Drain Valve #2	010	TEH-154	Drain Line-Heater T	037
TEH-182	Drain Valve #3	011	TEH-155	Drain Line-Heater T	038
TEH-183	Drain Valve #4	012	TEH-166	Hot Surge-Heater U	039
TEH-184	Drain Valve #5	013	TEH-167	Hot Surge-Heater U	040
TEH-185	Drain Valve #6	014	TEH-164	Cold Surge-Heater V	041
TEH-186	Drain Valve #7	015 (Bad)	TEH-165	Cold Surge-Heater V	042
TEH-187	Drain Valve #8	016	TEH-131	Riser-Heater H	300
TEH-188	Drain Valve #9	017	TEH-133	Riser-Heater I	301
TEH-189	Drain Valve #10	018	TEH-134	Riser-Heater I	302
TEH-160	Purge Line-Heater S	019	TEH-135	Riser-Heater J	303
TEH-161	Purge Line-Heater S	020	TEH-136	Riser-Heater J	304
TEH-176	Drain Line	021	TEH-130	Downcomer-Heater K	305
TEH-177	Drain Line	022	TEH-132	Downcomer-Heater L	306
TEH-172	Outlet of Pass #1 (Header)	023	TEH-137	Downcomer-Heater M	307
TEH-173	Pass #10	024	TEH-138	Downcomer-Heater M	308
TEH-174	Pass #11	025	TEH-139	Downcomer-Heater L	(Skip) 309
TEH-175	Pass #18	026			

TABLE A RS HEAT TRACE INSTRUMENTATION

T/C	DESCRIPTION	ACUREX CHANNEL	T/C	DESCRIPTION	ACURE CHANN
TEH-218	Hot Tank Outlet	(B)100	TEH-207	Boost Pump Outlet - Heater A	122
TEH-216	FCV-211, Line X	(B)101	TEH-208	Boost Pump Outlet - Heater A	123
TEH-219	Hot Sump Outlet	(B)102	TEH-227	Cold Sump	*124
TEH-222	Hot Sump	(B)103	TEH-228	Cold Sump	*125
TEH-225	Cold Sump Outlet	104	TEH-220	Hot Sump	(B)*126
TEH-230	Cold Tank Inlet	105	TEH-221	Hot Sump	(B)*127
TEH-201	Boost Sump Drain - Heater D	106	TEH-211	Riser - Storage End - Heater H	128
TEH-202	Cold Pump Outlet - Heater C	107	TEH-241	FCV-151, Heater H	(A)129
TEH-265	Cold Sump Outlet	108	TEH-212	Downcomer - Storage - Heater K	130
TEH-229	Cold Sump Inlet	109	TEH-240	FCV-161, Heaters A-Y, K	131
TEH-233	Cold Tank #1, CT-1 thru 7	*110	TEH-213	Hot Tank #1	*134
TEH-234	Cold Tank #2, CT--1 thru 7	*111	TEH-214	Hot Tank #2	*135
TEH-235	Cold Tank #3, CT-1 thru 7	*112	TEH-215	Hot Tank #3	*136
TEH-231	FCV-201	113	TEH-217	Cold/Hot Tank Bypass-Heater AA	(A,B)137
TEH-232	Cold Tank Outlet	114	TEH-223	Propane Heater	(A)138
TEH-205	Boost Sump - Heater W	115	TEH-224	Propane Heater	(A)139
TEH-206	Boost Sump - Heater W	116	TEH-236	Cold/Hot Tank Bypass, Heater AA	(A,B)140
TEH-203	Boost Pump Bypass - Heater E	117	TEH-238	FCV-242	141
TEH-204	Boost Pump Outlet - Heater B	118	TEH-239	Propane Heater Outlet	(A)142
TEH-209	Cold Tank Inlet - Heater F	(B)119			
TEH-210	Cold Tank Bypass - Heater G	120	* <u>Record for TSS Step 2, stored salt temp's</u>		
TEH-237	FCV-162, Heater F	(B)121	(A) Normally not operating during system operation		
			(B) Not required for Propane Heater operation		

TABLE B TSS HEAT TRACE INSTRUMENTATION



T/C	DESCRIPTION	ACUREX CHANNEL	
TEH-305, 306	Hot Salt Inlet Lines	200, 201	
TEH-307, 308	Salt Piping Between SH and EV	202, 203	
TEH-309 thru 311	Cold Salt Inlet Lines	204 thru 206	
TEH-312 thru 314	EV Salt Outlet	207 thru 209	
TEH-315 thru 317	Salt Drain Lines	<u>210 thru 212</u>	
TEH-318, 319	SH and EV Outlet Overpressure	**213, 214	
TEH-320, 321	Superheater	215, 216	
TEH-322, 323	Evaporator	<u>217, 218</u>	
6005 thru 6009	Misc. Salt Lines (info.)	230 thru 234	233 (Skip)
6011 thru 6016	Superheater (info.)	##236 thru 241	234 (O.R.)
----	FCV-351 Body, Bonnet	<u>242, /243</u>	
6020 thru 6025	Evaporator (info.)	##245 thru 250	
6026 thru 6029	Hot Salt Inlet (info.)	251 thru 254	
6030, 6031	FCV-341 Body, Bonnet	<u>255, /256</u>	
6032, 6033	FCV-301 Body, Bonnet	257, 258	
6034, 6035	FCV-321 Body, Bonnet	259, 260	
6036, 6037	FCV-381 Body, Bonnet	261, 262	
6038, 6039	FCV-382 Body, Bonnet	263, 264	
6040 thru 6042	Salt Drain Lines (info.)	##265 thru 267	
6043	SH Drain (info.)	<u>**268</u>	
6044 thru 6053	Misc. Lines (info.)	269 thru 278	275 (Skip) 277 (O.R.)

\*\*These will normally be below salt freezing temperature (no problem).

##These may be below 480°F - But they should be above 400°F prior to salt flow.

TABLE C SGS HEAT TRACE INSTRUMENTATION

TABLE D GROUP ALARM LIST

GAL GENERAL ALARMS

LT-201	TE-180	TE-383	TE-508	LS-541	LV-28
LT-221	TE-181	387	-509	PS-281	LV-481
LT-281	TE-184	388	-581	PS-485	LV-N91
LT-291	TE-211	TE-481		TS-501	N90-AL
LT-311	TE-231	484		TS-502	
LT-471	TE-281	486			
LT-511	TE-286				

RAL REGENER OPERATIONAL ALARMS

FT-101	LT-151	TE-101	PT-181	RMINT
	LT-161	TE-102	PT-182	RMAXT
		TE-161		
		<del>TE-161</del>		

SAL STEAM GENERATOR OPERATIONAL ALARMS

TE-301	TE-384	PT-321	PT-431
TE-331	386	382	432
332	421	383	483
TE-382	483	384	
		386	

PAL ELECT. POWER OPERATIONAL ALARMS

ET-581	TT-501	TE-505	TT-521	PT-501	PT-531
ST-581	TT-502	TE-506	TT-583	502	581
ZSH-AEP	TE-503	TT-507			583

TABLE E MSEE REMOTE OPERATED VALVE ALIGNMENT

VALVE	FUNCTION	PRETEST			OPERATION		POST TEST
		BASIC FULL SYSTEM	MODIFICATION TO OPERATE 1. W/O RECVR 2. W/OR W/O PROPANE HTR	MODIFICATION TO OPERATE 1. RECVR ONLY -OR- 2. PROPANE HTR ONLY	BASIC FULL SYSTEM	MODIFICATION TO OPERATE 1. W/O RECVR -AND- 2. W/PROPANE HTR	
FCV-101	RECVR FLOW CTRL	○ MAN			⊙ CASE SP,SALT SP 1000 °F	○ MAN	○ MAN
FCV-102	RECVR FLOW CTRL	○ MAN			⊙ CASE SP,SALT SP 1000 °F	○ MAN	○ MAN
FCV-151	CST LEVEL CTRL	● MAN	● L MAN	● L MAN (W/HTR)	⊙ CASE LT-151 SP 87"	● L MAN	○ MAN
FCV-161	HST LEVEL CTRL	● MAN	● L MAN	● L MAN (W/HTR)	⊙ AUTO SP 20"	● L MAN	○ MAN
FCV-162	HST LEVEL CTRL	● MAN	○ MAN	○ MAN (W/HTR)	● AUTO SP 20"	○ MAN	○ MAN
FCV-180-189	RECVR DRAIN	○			●		●
FCV-190-198	RECVR PURGE	○			●		●
FCV-501	TURBINE STOP	●			○		●
FCV-511	HOTWELL OVERFLOW	●			⊙ EN,HLC ON		●
FCV-512	HOTWELL MAKE-UP	● EN,HLC OFF (LOCAL CNTRL)			⊙ (AUTO CNTRL)		● (LOCAL CNTRL)
FCV-521	OIL COOLANT FLOW CTRL	● AUTO SP 120° F			⊙ AUTO SP 120° F		● MAN
FCV-541	CNST MAKE-UP	● LOCAL CNTRL			LOCAL CNTRL		● LOCAL CNTRL
FCV-551	CONDENSATE RECIRC	●			●		●
FCV-561	TURBINE TRIP	● ET OFF			● ET OFF		● ET OFF
TVM	TURBINE THROTTLE	●			⊙		●
		● L	○	⊙			
		└ LOCKED	└ OPEN	└ CONTROLLING			
		└ CLOSED					

**COP #2 CONTROL ROOM POST-TEST CHECKLIST**

Test Date  
9/22/84

This Console operating procedure will be utilized to secure the process controls following all tests. This checklist shall be completed by the Control Room process console operator.

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
<b>I. HELIOSTAT SUBSYSTEM</b>		
	1. Verify system returned to a safe condition; (Heliostats, salt, steam, water)	_____
<b>II. RS RECEIVER SUBSYSTEM</b>		
	1. Verify the following valve alignment:	_____
01	FCV-101 Man/Open	
	FCV-102 Man/Open	
	FCV-180 thru 189 Off/Closed (ZSL's on)	08
	FCV-190 thru 198 Off/Closed (ZSL's on)	09
02	2. Verify the receiver cavity door is fully closed (ZSLDR on).	_____
	3. Verify RS secured from technician - post test checklist completed (ROP #4).	_____
<b>III. TSS THERMAL STORAGE SUBSYSTEM</b>		
	1. Verify the following valve alignment in MAN:	
02	FCV-151 Open 04 FCV-211 Closed/Locked ✓	
	FCV-161 Open 04 FCV-221 Closed	
	FCV-162 Open 04 FCV-231 Closed/Locked ✓	
	FCV-199 Open 05 FCV-241 Closed	
04	FCV-201 Closed 05 FCV-242 Closed	
	CSP.EN Off, BP.EN Off, HSP.EN Off	_____
	2. Record the following salt levels & temp's:	
	LT-201 Cold sump _____ in. @ _____ °F (Acurex Chan 124,125)	
03	LT-281 Cold tank _____ in. @ _____ °F (Acurex Chan 110-112)	
	LT-221 Hot sump _____ in. @ _____ °F (Acurex Chan 126,127)	
	LT-291 Hot tank _____ in. @ _____ °F (Acurex Chan 134-136)	
	3. Verify TSS secured from technician - post test checklist completed (TOP #4).	_____

COP #2 CONTROL ROOM POST-TEST CHECKLIST

<u>STEP</u>	<u>DESCRIPTION</u>	<u>VERIFICATION</u>
-------------	--------------------	---------------------

IV. SGS STEAM GENERATION SUBSYSTEM

1. Verify the following valve alignment:

_____	*FCV-301	Closed	MAN.384 On
_____	*FCV-321	Open	FCV.384 On (open)
13	*FCV-331	10% Open	MAN.38182 On
_____	*FCV-341	Closed	FCV.38182 Off (closed)
_____	*FCV-351	Closed	

\*Emcon commands - MAN signals on with SP in Auto to the positions noted.

2. Verify SGS secured from technician - post test checklist completed (SOP #4).

V. HRFS HEAT REJECTION AND FEEDWATER SUBSYSTEM

1. Verify the following device alignment:

_____	EN.DTC451	--	Off
_____	EN.DTC452	--	Off
_____	GSTAT	--	Off
18	FCV-431	Closed	Casc
_____	FCV-432	Open	Auto SP 233
_____	FCV-471	Closed	Auto SP 0%
_____	FY-472	Closed	Auto SP 0%
_____	FCV-411	Closed	MAN.411 On/SP.411 Auto 0%
_____	FCV-491	Closed	Auto Closed
19	FCV-501	Closed	Off/ZSL-501 On
20	Pump EN Signals		Off

2. Verify HRFS secured from technician - post test checklist completed (HOP #4).


VI. EPGS ELECTRIC POWER GENERATION SUBSYSTEM

- 21
1. Verify TCRMS is off.
  2. If used, reset bkr control switch to green flag, remove the RGP Sync switch handle and return it to the MSEE key box. Set Run Volt and Speed controls down.
  3. Verify EPGS secured from technician - post test checklist completed (POP #4).

VII. MCS MASTER CONTROL SUBSYSTEM

1. Disable general alarms by turning GAL off.
2. Safe the Emcon and Net. 90 control consoles to eliminate any inadvertant control inputs. (Lock-up)

MSEE



FT321  
77.9KLB

INSOL:  
952.WSN

PUMP STATUS:

CSP  BP  HSP  BCP  FWP  SWP  CWP  CMP  CFP  CTP  CNP  AEP  EOP

12:41:41 19-JUL-84 DSP991

8-3

**COP #1 CONTROL ROOM PRETEST CHECKLIST**

TEST DATE  
10/04/84

This Console operating procedure will be utilized to verify process control integrity prior to all tests. It is unnecessary to verify control integrity of subsystems not used (not applicable). This checklist shall be completed by the control room process console operator.

**I. Test Description** \_\_\_\_\_

Start Time

**II. Responsible operating personnel**

**Primary**

**Backup**

Test Conductor (MDAC)

Stan Saloff

Heliostat Operator

Arleen Vance

Console Operator

Evans/Nelson

Operation/Safety Engineer

John Holmes

Subsystem Technicians

RS

Jerome Griego

TSS

Matt Matthews

SGS

Matt Matthews

HRFS

Jay Holton

EPGS

Jay Holton

**COP #1 CONTROL ROOM PRETEST CHECKLIST**

**STEP DESCRIPTION VERIFICATION**

**VIII. HRFS - HEAT REJECTION AND FEEDWATER SUBSYSTEM**

Complete this checklist for all water system operations.

1. Set/Verify the following control devices in the listed positions: HCK 'ON' may be used to auto align these, turning itself off when complete.

Identifier	Description	Command	Position	
call up	GSTAT	D/D Press Enable	Off (PT-431 control)	N/A
	EN.DTC451	D/D Heater 1 Enable	Off	N/A
	EN.DTC452	D/D Heater 2 Enable	Off	N/A
	DTC-451	D/D Heater 1	Auto SP 390 or 400°F	Not Enabled
	DTC-452	D/D Heater 2	Auto SP 390 or 400°F	Not Enabled
	FCV-401	FWP Press Recirc	Auto SP 1250 psi	Closed
	FCV-411	Feedwater Delivery	MAN.411 On/SP-411 AUTO 0%	Closed
	FCV-421	FWH Steam Supply	Man	Closed
18	FCV-431	D/D Steam Inlet	Auto/Casc to PT-431	Closed
	PT-431	Steam Line Press	Auto SP 1080 psi	N/A
	PT-432	D/D Press	Auto SP 225 psi	N/A
	FCV-432	SWHX Divert	Auto SP 233 psi	Open to Bypass
	FCV-471	T-G Condensate Return	Auto SP 0%	Closed
	FY-472	CMUP Stroke Positioner	Auto SP 0%	Closed
	FCV-491	SGS Steam Delivery	Auto SP 900 psi	Closed
21	ZSL-501	Main Steam Stop micro	On	Closed
	TCPMS	EPGS Control Mode	Off (local)	N/A
	CF1.EN	Cooling Fan 1 Enable	On	N/A
20	CF2.EN	2	On	N/A
	CF3.EN	3	On	N/A
	CF4.EN	4	On	N/A
	CF5.EN	5	On	N/A
	CF6.EN	6	On	N/A
	CFP.EN	Cycle Fill Pump	Enable	N/A
19	CMP.EN	Cond. Make-up Pump	On	N/A
	CWP.EN	Cooling Water Pump	On	N/A
	SWP.EN	Spray Water Pump	On	N/A
	FWP.EN	Feed Water Pump	On	N/A

**IX. EPGS ELECTRIC POWER GENERATION SUBSYSTEM**

Complete this checklist for all turbine-generator operations.

1. Verify RGP Gen Breaker green (open) light is on.
2. Verify that the Sync switch handle has been procured from the MSEE key box if synch is to be completed or observed from the control room.



June 28, 1984

Telephone Numbers for maintenance calls:

- MODCOMP 1-800-327-8928 give site number found on sticker on cabinet front panel.
- HEWLETT-PACKARD 9-842-1283 give model, serial, and ADP information on attached sheet.
- RAMTEK look for on-site spares first, no existing maintenance contract.
- DIGITAL (DEC) 9-345-4471 give following information: CPU 11/34A, Serial No. AG 25174, identify faulty item.
- EMC (EMCON) 8-713-665-9911 give nature of problem to Bob Marian or Jerry Kulbeck
- BAILEY (N90) 8-303-757-5408 give nature of problem to Denver office. <sup>Bill</sup> Mahoney
- VERSATEC PRINTER  
VERSATEC VIDEO COPIER 292-1212 (BFA) give P.O. number 47-4080 and nature of problem.
- TECKTRONIX 4014  
TEXAS INST TERMINALS 4-3091 (Orig. 2617) give nature of problem, terminal type, S #, serial number.

Mr Allen:

842-1283

The ADP numbers for the equipment that you requested as to put on maintenance are:

<u>Model</u>		<u>Serial number</u>	<u>ADP No.</u>	<u>Prop. No.</u>
2113B	DSP	2015A06179	288-45	S263101
2112A	MCS	1611A00666	284-54A	S24497
2113B	DEV	1737A00225	284-69	S2486
2113B	L. CYCLE	2020A06523	288-53	S2729
2117F	BCS	1810A00132	284-78	S2540
2117F	FCS	2012A01467	288-45	S2631

DSP and MCS are covered for 4 hour response, all others are covered for next day response. Systems not listed will be covered via T & M contracts.

TE161	③	-99. → 2500.
TE281	③	-99. → 2500.
TE291	③	-99. → 2500.
TE101	①	-99. → 2500.
TE102	①	-99. → 2500.
SP.SALT	①	-99. → 2500.

Bob Marlon or Jerry

A/D converter card into PCM 1.]



if it has to be calibrated in place they have to come & do it

4-6360 & leave message

[Exchange cards 15 in PCM 1 & PCM 2.]

[

WARMUP PATTERN



EAST

UNCLASSIFIED	
MELOSTAY FIELD LAYOUT	
E 14213	19205-B

Follow this sequence  
when you get to step #10  
of ROP #2

### RECEIVER AUTO FILL SEQUENCE CHECKLIST

<u>Step</u>	<u>Description</u>	<u>Verification</u>
1.	Cold Salt Pump ON	<input checked="" type="checkbox"/>
2.	Boost Pump ON	<input checked="" type="checkbox"/>
3.	Boost Pump Discharge Pressure PT-180 to 310 PSI	<input checked="" type="checkbox"/>
4.	FCV-151 OPEN 50%	<input checked="" type="checkbox"/>
5.	TE-161 Responds to Salt	<input checked="" type="checkbox"/>
6.	Salt in Cold Surge Tank	<input checked="" type="checkbox"/>
7.	TE-101 Responds to Salt FT-101 Starts Indicating Flow	<input checked="" type="checkbox"/>
8.	Salt in Hot Surge Tank (when cold surge tank level LT-151 reaches 40-50 inches).	<input type="checkbox"/>
9.	FCV-199 CLOSED (when hot surge tank level LT-161 reaches 10")	<input type="checkbox"/>
10.	Drain Valves CLOSED (when hot surge tank level LT-161 reaches 56")	<input type="checkbox"/>
11.	Purge Valves Sequentially Close (EMCON Group 09)	<input type="checkbox"/>
12.	Hot Surge Tank Level LT-161 Decrease to 20" With FCV-162 Controlling	<input type="checkbox"/>
13.	Cold Sump Level Controlling at 20"	<input type="checkbox"/>
14.	FCV-101/102 Controlling Receiver Salt Flow at 30 Klb/hr	<input type="checkbox"/>
15.	FCV-151 100% OPEN Increasing Cold Surge Tank Level LT-151 to 80-85"	<input type="checkbox"/>
16.	Return to Step 26 of Receiver Startup Procedure ROP #2	<input type="checkbox"/>

Procedure

Completed

3. Confirm receiver technician is completing receiver pretest checklist (ROP #1)

4. Confirm thermal storage technician is completing TSS pretest checklist (TOP #1) ✓

5. Complete control room pretest checklist (COP ~~#3~~ Sections I - VI #1)

\_\_\_\_\_

6. Fill receiver, establish serpentine flow, and transition to extended warm standby mode (ROP #2 Sections 1 - 35) 27

\_\_\_\_\_

*group 01*

7. Increase salt flow to 45 KLB/hr, stabilize and confirm level controls of hot and cold surge tanks and cold sump. *LOOK at FCV162*

\_\_\_\_\_

8. Increase salt flow to 60 KLB/hr, restabilize and reconfirm level controls. *(COP #17)*

\_\_\_\_\_

9. Increase salt flow to 85 KLB/hr, monitor cold sump level and compare to low alarm level. Reduce flow if necessary and restabilize at a flow rate which allows the sump level to be maintained. Determine the maximum steady state flow rate as limited by the sump supply line.

FT-101	Max steady state flow	_____
LT-281	Cold storage tank level	_____

10. Reduce flow demand to 30 KLB/hr

\_\_\_\_\_

11. Shut down receiver (ROP#3)

\_\_\_\_\_

## 5.2 OPERATIONAL EXERCISES

### 5.2.1 Receiver Cold Flow

#### Description

- o Fill receiver
- o Circulate the cold salt through the receiver and back to the cold storage tank
- o Drain receiver

#### Objectives

- o Introduce the operator to receiver start-up and shutdown operations
- o Familiarize the operator with the receiver loop equipment and controls

#### Initial System Conditions

- o RS2 - Receiver drained with trace heat on
- o TSS2- Hot and cold salt tanks warm and ready for operation
- o SGS not applicable
- o EPGS not applicable

#### Procedure

#### Completed

1. Advise data system operator to load system data package.
2. Advise data system operator to display the following on the data display screens:

\_\_\_\_\_ ✓

\_\_\_\_\_ ✓

LT-281	Cold storage tank level
FT-101	Receiver salt flow rate
TE-101	Receiver inlet salt temp
TE-102	Receiver outlet salt temp
LT-151	Cold salt surge tank level
LT-161	Hot salt surge tank level

